TOWNSHIP OF SOUTH FRONTENAC
COUNCIL MEETING
AGENDA

Online via Teleconference and Broadcast live to the South Frontenac's Facebook Page
https://www.facebook.com/SouthFrontenacTwp/

TIME: 7:00 PM,
DATE: Tuesday, June 2, 2020
PLACE: Electronic Participation.

1. *Call to Order*

a) **Roll Call - Council Members and Staff**

b) **Resolution**

2. *Declaration of pecuniary interest and the general nature thereof*

3. *Approval of Agenda*

a) **Resolution**

4. *Scheduled Closed Session - not applicable*

5. ****Recess *** - not applicable*

6. *Staff Presentations/Delegations*

a) **Provincial Policy Statement - 2020 - Presented by Christine Woods, Senior Planner** 3 - 74

7. *Public Meeting - not applicable*

8. *Approval of Minutes*

a) **May 19, 2020 Special Committee of the Whole Meeting** 75

b) **May 19, 2020 Council Meeting** 76 - 81

9. *Business Arising from the Minutes*

a) **CAO Performance Appraisal Process** 82 - 84

10. *Reports Requiring Action*

a) **Green Bay Cemetery** 85 - 88

b) **Tender # PS-2020-09 - 2020 Micro-Surfacing Program** 89 - 92

c)	**Tender # PS-2020-10 - Pavement Program**	93 - 94
d)	**Road and Property Exchange - Norman Lane/Perth Road (Spicer/Postma)**	95 - 98
11.	*Committee Meeting Minutes - not applicable*	
12.	*By-laws*	
a)	**By-law 2020-29 - Dedicate travelled portion of Norman Lane as common and public highway**	99
13.	*Reports for Information*	
a)	**Accounts Payable and Payroll Listing**	100 - 128
14.	*Information Items - not applicable*	
15.	*Notice of Motions*	
16.	*Announcements/Statements by Councillors*	
17.	*Question of Clarity (from the public on outcome of agenda items)*	
a)	**Questions for Council from the Public Regarding COVID-19 and Township Services**	129 - 131
18.	*Closed Session (if requested)*	
19.	*Confirmatory By-law*	
a)	**By-law 2020-30**	132
20.	*Adjournment*	
a)	**Resolution**	

Provincial Policy Statement, 2020

Presentation to South Frontenac Council

June 2, 2020

Outline

1. Background
2. Purpose of Provincial Policy Statement
3. Main policy sections
4. Council response to Province: October 2019
5. Themes for changes to 2020 PPS
6. Impacts to Township by theme
7. Questions & Comments

Background

- Issued under section 3 of the Planning Act
- Replaces the 2014 Provincial Policy Statement (PPS)
- Came into effect May 1, 2020
- All decisions affecting planning matters “shall be consistent” with PPS 2020



Purpose of Provincial Policy Statement

- Provides policy direction on matters of provincial interest related to land use planning and development
- Matters of provincial interest impact Ontario's long-term prosperity, environmental health and social well-being
- Intend to provide for appropriate development while protecting resources of provincial interest, public health and safety, and the quality of the natural and built environment
- Establishes a policy framework for County and local official plan policies

Main Policy Sections

1. Building strong healthy communities
2. Wise use and management of resources
3. Protecting public health and safety
4. Implementation and interpretation

Council Response to Province: October 2019

- Proposed changes to the PPS that Council supported
  - Keep the existing natural heritage policies
  - A higher level of environmental protection
  - Continue to require that all planning approvals “shall be consistent” with the PPS
  - Provide more flexibility for rural communities
  - Sustain and protect agricultural resources
  - Opportunity for more housing options
  - Facilitate the use of communal services in villages and hamlets

Council Response to Province: October 2019

- Recommended and Requested Changes
  - Maintain the 20 year planning horizon
  - Maintain 10 year housing land supply
  - Clarify the term “limited” rural residential development
  - Clarify the term “recreational dwellings”
  - Clarify the term “market-based” housing
  - Clarify how mineral aggregate extraction in natural heritage features can demonstrate no negative impact through rehabilitation plans
  - Provide clarification and guidance materials

Themes for Changes to 2020 PPS

1. Increase housing supply and mix
2. Protect the environment and public safety
3. Reduce barriers and costs
4. Support rural, northern and Indigenous communities
5. Support certainty and economic growth

1. Increasing Housing Supply and Mix

- Long term planning time horizon increased from 20 years to 25 years
- Housing land supply increased from 10 years to 15 years
- Relaxes the process and considerations in expanding settlement areas
- More flexibility around phasing and form of development in settlement areas
- Provide for an appropriate range and mix of housing options
  - Meet market-based and affordable housing needs and changing demographic needs
  - Supports the role of market consideration in determining the range and mix of housing
  - Definition of housing includes second residential units and tiny homes
  - Aligns affordable housing targets with housing and homelessness plans

2. Protecting the Environment and Public Safety

- Prepare for regional and local impacts of a changing climate
  - Through effective storm water management and the use of green infrastructure
- Continue to protect natural features such as wetlands
- Continue to direct development away from hazardous areas

3. Reducing Barriers and Costs

- Cannot try to regulate the depth of extraction for new and existing mineral aggregate operations
  - This may only be done under the Aggregate Resources Act
- Strengthen cultural heritage policies
  - Direction provided on how to identify and conserve cultural heritage resources while allowing for compatible development
- Support for a broad range of energy types and opportunities for increased energy supply
  - e.g. renewable or alternative energy systems
- Required to engage with Indigenous communities
  - Coordinate on land use planning matters
  - Consider their interests when identifying, protecting and managing cultural heritage and archaeological resources

4. Supporting Rural, Northern and Indigenous Communities

- Permit locally-appropriate rural residential development
  - Including lot creation
- May allow private communal servicing for multi-unit/lot development
- May use an agricultural system approach
  - This considers both the agricultural land base and the agri-food network
- Assess long-term impacts of individual on-site sewage and water services on the health and character of rural settlement areas and the feasibility of moving to municipal or private communal servicing at the time of the Official Plan update
- Required to engage with Indigenous communities
  - Coordinate on land use planning matters

5. Supporting Certainty and Economic Growth

- Encouraged to facilitate conditions for economic investment
- Assess local employment areas to ensure designations are appropriate and provide a 25 year land supply
- Maintain long-term viability of employment areas by protecting them from sensitive land uses
- Integrate planning for infrastructure needs with growth management and land use planning

Implementation and Interpretation of PPS

- Province made commitment to support implementation through education, training and guidance materials (including engagement with Indigenous communities)
- The proposed policy about fast-tracking residential and priority applications was not included in the PPS.

Any questions or comments?

Christine Woods MCIP, RPP
Senior Planner

Anna Geladi
Planner

Provincial Policy Statement, 2020

Under the *Planning Act*

Ontario

PROVINCIAL POLICY STATEMENT, 2020

Approved by the Lieutenant Governor in Council, Order in Council No. 229/2020

This Provincial Policy Statement was issued under section 3 of the *Planning Act* and came into effect May 1, 2020. It replaces the Provincial Policy Statement issued April 30, 2014.

Table of Contents

PART I: PREAMBLE 1

PART II: LEGISLATIVE AUTHORITY 2

PART III: HOW TO READ THE PROVINCIAL POLICY STATEMENT 2

PART IV: VISION FOR ONTARIO'S LAND USE PLANNING SYSTEM 5

PART V: POLICIES 7

1.0 BUILDING STRONG HEALTHY COMMUNITIES 7

1.1 Managing and Directing Land Use to Achieve Efficient and Resilient Development and Land Use Patterns 7
- Settlement Areas 8
- Rural Areas in Municipalities 10
- Rural Lands in Municipalities 11
- Territory Without Municipal Organization 12

1.2 Coordination 12
- Land Use Compatibility 14

1.3 Employment 14
- Employment Areas 15

1.4 Housing 16

1.5 Public Spaces, Recreation, Parks, Trails and Open Space 17

1.6 Infrastructure and Public Service Facilities 17
- Sewage, Water and Stormwater 18
- Transportation Systems 20
- Transportation and Infrastructure Corridors 20
- Airports, Rail and Marine Facilities 21
- Waste Management 21
- Energy Supply 22

1.7 Long-Term Economic Prosperity 22

1.8 Energy Conservation, Air Quality and Climate Change 22

2.0 WISE USE AND MANAGEMENT OF RESOURCES 24

2.1 Natural Heritage 24

2.2 Water 25

2.3 Agriculture 26

2.4 Minerals and Petroleum 28

2.5 Mineral Aggregate Resources 29

2.6 Cultural Heritage and Archaeology 31

3.0 PROTECTING PUBLIC HEALTH AND SAFETY 32

3.1 Natural Hazards 32

3.2 Human-Made Hazards 34

4.0 IMPLEMENTATION AND INTERPRETATION 35

5.0 FIGURE 1 37

6.0 DEFINITIONS 40

Part I: Preamble

The Provincial Policy Statement provides policy direction on matters of provincial interest related to land use planning and development. As a key part of Ontario's policy-led planning system, the Provincial Policy Statement sets the policy foundation for regulating the development and use of land. It also supports the provincial goal to enhance the quality of life for all Ontarians.

The Provincial Policy Statement provides for appropriate development while protecting resources of provincial interest, public health and safety, and the quality of the natural and built environment. The Provincial Policy Statement supports improved land use planning and management, which contributes to a more effective and efficient land use planning system.

The policies of the Provincial Policy Statement may be complemented by provincial plans or by locally-generated policies regarding matters of municipal interest. Provincial plans and municipal official plans provide a framework for comprehensive, integrated, place-based and long-term planning that supports and integrates the principles of strong communities, a clean and healthy environment and economic growth, for the long term.

Municipal official plans are the most important vehicle for implementation of this Provincial Policy Statement and for achieving comprehensive, integrated and long-term planning. Official plans shall identify provincial interests and set out appropriate land use designations and policies.

Official plans should also coordinate cross-boundary matters to complement the actions of other planning authorities and promote mutually beneficial solutions. Official plans shall provide clear, reasonable and attainable policies to protect provincial interests and direct development to suitable areas. In order to protect provincial interests, planning authorities shall keep their official plans up-to-date with this Provincial Policy Statement.

Zoning and development permit by-laws are also important for implementation of this Provincial Policy Statement. Planning authorities shall keep their zoning and development permit by-laws up-to-date with their official plans and this Provincial Policy Statement.

Land use planning is only one of the tools for implementing provincial interests. A wide range of legislation, regulations, policies and programs may apply to decisions with respect to *Planning Act* applications and affect planning matters, and assist in implementing these interests.

Within the Great Lakes – St. Lawrence River Basin, there may be circumstances where planning authorities should consider agreements related to the protection or restoration of the Great Lakes – St. Lawrence River Basin. Examples of these agreements include Great Lakes agreements between Ontario and Canada, between Ontario and Quebec and the Great Lakes States of the United States of America, and between Canada and the United States of America.

Part II: Legislative Authority

The Provincial Policy Statement is issued under the authority of section 3 of the *Planning Act* and came into effect on May 1, 2020.

In respect of the exercise of any authority that affects a planning matter, section 3 of the *Planning Act* requires that decisions affecting planning matters "shall be consistent with" policy statements issued under the Act.

Comments, submissions or advice that affect a planning matter that are provided by the council of a municipality, a local board, a planning board, a minister or ministry, board, commission or agency of the government "shall be consistent with" this Provincial Policy Statement.

Part III: How to Read the Provincial Policy Statement

The provincial policy-led planning system recognizes and addresses the complex inter-relationships among environmental, economic and social factors in land use planning. The Provincial Policy Statement supports a comprehensive, integrated and long-term approach to planning, and recognizes linkages among policy areas.

Read the Entire Provincial Policy Statement

The Provincial Policy Statement is more than a set of individual policies. It is to be read in its entirety and the relevant policies are to be applied to each situation. When more than one policy is relevant, a decision-maker should consider all of the relevant policies to understand how they work together. The language of each policy, including the Implementation and Interpretation policies, will assist decision-makers in understanding how the policies are to be implemented.

While specific policies sometimes refer to other policies for ease of use, these cross-references do not take away from the need to read the Provincial Policy Statement as a whole.

There is no implied priority in the order in which the policies appear.

Consider Specific Policy Language

When applying the Provincial Policy Statement it is important to consider the specific language of the policies. Each policy provides direction on how it is to be implemented, how it is situated within the broader Provincial Policy Statement, and how it relates to other policies.

Some policies set out positive directives, such as "settlement areas shall be the focus of growth and development." Other policies set out limitations and prohibitions, such as "development and site alteration shall not be permitted." Other policies use enabling or supportive language, such as "should," "promote" and "encourage."

The choice of language is intended to distinguish between the types of policies and the nature of implementation. There is some discretion when applying a policy with enabling or supportive language in contrast to a policy with a directive, limitation or prohibition.

Geographic Scale of Policies

The Provincial Policy Statement recognizes the diversity of Ontario and that local context is important. Policies are outcome-oriented, and some policies provide flexibility in their implementation provided that provincial interests are upheld.

While the Provincial Policy Statement is to be read as a whole, not all policies will be applicable to every site, feature or area. The Provincial Policy Statement applies at a range of geographic scales.

Some of the policies refer to specific areas or features and can only be applied where these features or areas exist. Other policies refer to planning objectives that need to be considered in the context of the municipality or planning area as a whole, and are not necessarily applicable to a specific site or development proposal.

Policies Represent Minimum Standards

The policies of the Provincial Policy Statement represent minimum standards.

Within the framework of the provincial policy-led planning system, planning authorities and decision-makers may go beyond these minimum standards to address matters of importance to a specific community, unless doing so would conflict with any policy of the Provincial Policy Statement.

Defined Terms and Meanings

Except for references to legislation which are italicized, other italicized terms in the Provincial Policy Statement are defined in the Definitions section. For non-italicized terms, the normal meaning of the word applies. Terms may be italicized only in specific policies; for these terms, the defined meaning applies where they are italicized and the normal meaning applies where they are not italicized. Defined terms in the Definitions section are intended to capture both singular and plural forms of these terms in the policies.

Guidance Material

Guidance material and technical criteria may be issued from time to time to assist planning authorities and decision-makers with implementing the policies of the Provincial Policy Statement. Information, technical criteria and approaches outlined in guidance material are meant to support but not add to or detract from the policies of the Provincial Policy Statement.

Relationship with Provincial Plans

The Provincial Policy Statement provides overall policy directions on matters of provincial interest related to land use planning and development in Ontario, and applies province-wide, except where this policy statement or another provincial plan provides otherwise.

Provincial plans, such as the Greenbelt Plan, A Place to Grow: Growth Plan for the Greater Golden Horseshoe and the Growth Plan for Northern Ontario, build upon the policy foundation provided by the Provincial Policy Statement. They provide additional land use planning policies to address issues facing specific geographic areas in Ontario.

Provincial plans are to be read in conjunction with the Provincial Policy Statement. They take precedence over the policies of the Provincial Policy Statement to the extent of any conflict, except where the relevant legislation provides otherwise.

Where the policies of provincial plans address the same, similar, related, or overlapping matters as the policies of the Provincial Policy Statement, applying the more specific policies of the provincial plan satisfies the more general requirements of the Provincial Policy Statement. In contrast, where matters addressed in the Provincial Policy Statement do not overlap with policies in provincial plans, the policies in the Provincial Policy Statement must be independently satisfied.

Land use planning decisions made by municipalities, planning boards, the Province, or a commission or agency of the government must be consistent with the Provincial Policy Statement. Where provincial plans are in effect, planning decisions must conform or not conflict with them, as the case may be.

Part IV: Vision for Ontario's Land Use Planning System

The long-term prosperity and social well-being of Ontario depends upon planning for strong, sustainable and resilient communities for people of all ages, a clean and healthy environment, and a strong and competitive economy.

Ontario is a vast province with diverse urban, rural and northern communities which may face different challenges related to diversity in population, economic activity, pace of growth and physical and natural conditions. Some areas face challenges related to maintaining population and diversifying their economy, while other areas face challenges related to accommodating and managing the development and population growth which is occurring, while protecting important resources and the quality of the natural environment.

The Province's rich cultural diversity is one of its distinctive and defining features. Indigenous communities have a unique relationship with the land and its resources, which continues to shape the history and economy of the Province today. Ontario recognizes the unique role Indigenous communities have in land use planning and development, and the contribution of Indigenous communities' perspectives and traditional knowledge to land use planning decisions. The Province recognizes the importance of consulting with Aboriginal communities on planning matters that may affect their section 35 Aboriginal or treaty rights. Planning authorities are encouraged to build constructive, cooperative relationships through meaningful engagement with Indigenous communities to facilitate knowledge-sharing in land use planning processes and inform decision-making.

The Provincial Policy Statement focuses growth and development within urban and rural settlement areas while supporting the viability of rural areas. It recognizes that the wise management of land use change may involve directing, promoting or sustaining development. Land use must be carefully managed to accommodate appropriate development to meet the full range of current and future needs, while achieving efficient development patterns and avoiding significant or sensitive resources and areas which may pose a risk to public health and safety. Planning authorities are encouraged to permit and facilitate a range of housing options, including new development as well as residential intensification, to respond to current and future needs.

Efficient development patterns optimize the use of land, resources and public investment in infrastructure and public service facilities. These land use patterns promote a mix of housing, including affordable housing, employment, recreation, parks and open spaces, and transportation choices that increase the use of active transportation and transit before other modes of travel. They support the financial well-being of the Province and municipalities over the long term, and minimize the undesirable effects of development, including impacts on air, water and other resources. They also permit better adaptation and response to the impacts of a changing climate, which will vary from region to region.

Strong, liveable and healthy communities promote and enhance human health and social well-being, are economically and environmentally sound, and are resilient to climate change.

The Province's natural heritage resources, water resources, including the Great Lakes, agricultural resources, mineral resources, and cultural heritage and archaeological resources provide important environmental, economic and social benefits. The wise use and management of these resources over the long term is a key provincial interest. The Province must ensure that its resources are managed in a sustainable way to conserve biodiversity, protect essential ecological processes and public health and safety, provide for the production of food and fibre, minimize environmental and social impacts, provide for recreational opportunities (e.g. fishing, hunting and hiking) and meet its long-term needs.

It is equally important to protect the overall health and safety of the population, including preparing for the impacts of a changing climate. The Provincial Policy Statement directs development away from areas of natural and human-made hazards. This preventative approach supports provincial and municipal financial well-being over the long term, protects public health and safety, and minimizes cost, risk and social disruption.

Taking action to conserve land and resources avoids the need for costly remedial measures to correct problems and supports economic and environmental principles.

Strong communities, a clean and healthy environment and a strong economy are inextricably linked. Long-term prosperity, human and environmental health and social well-being should take precedence over short-term considerations.

The fundamental principles set out in the Provincial Policy Statement apply throughout Ontario. To support our collective well-being, now and in the future, all land use must be well managed.

Part V: Policies

1.0 Building Strong Healthy Communities

Ontario is a vast province with urban, rural, and northern communities with diversity in population, economic activities, pace of growth, service levels and physical and natural conditions. Ontario's long-term prosperity, environmental health and social well-being depend on wisely managing change and promoting efficient land use and development patterns. Efficient land use and development patterns support sustainability by promoting strong, liveable, healthy and resilient communities, protecting the environment and public health and safety, and facilitating economic growth.

Accordingly:

1.1 Managing and Directing Land Use to Achieve Efficient and Resilient Development and Land Use Patterns

1.1.1 Healthy, liveable and safe communities are sustained by:

a) promoting efficient development and land use patterns which sustain the financial well-being of the Province and municipalities over the long term;
b) accommodating an appropriate affordable and market-based range and mix of residential types (including single-detached, additional residential units, multi-unit housing, affordable housing and housing for older persons), employment (including industrial and commercial), institutional (including places of worship, cemeteries and long-term care homes), recreation, park and open space, and other uses to meet long-term needs;
c) avoiding development and land use patterns which may cause environmental or public health and safety concerns;
d) avoiding development and land use patterns that would prevent the efficient expansion of *settlement areas* in those areas which are adjacent or close to *settlement areas*;
e) promoting the integration of land use planning, growth management, *transit-supportive* development, *intensification* and *infrastructure* planning to achieve cost-effective development patterns, optimization of transit investments, and standards to minimize land consumption and servicing costs;
f) improving accessibility for persons with disabilities and older persons by addressing land use barriers which restrict their full participation in society;
g) ensuring that necessary *infrastructure* and *public service facilities* are or will be available to meet current and projected needs;
h) promoting development and land use patterns that conserve biodiversity; and
i) preparing for the regional and local impacts of a changing climate.

1.1.2 Sufficient land shall be made available to accommodate an appropriate range and mix of land uses to meet projected needs for a time horizon of up to 25 years, informed by provincial guidelines. However, where an alternate time period has been established for specific areas of the Province as a result of a provincial planning exercise or a *provincial plan*, that time frame may be used for municipalities within the area.

Within *settlement areas*, sufficient land shall be made available through *intensification* and *redevelopment* and, if necessary, *designated growth areas.*

Nothing in policy 1.1.2 limits the planning for *infrastructure*, *public service facilities* and *employment areas* beyond a 25-year time horizon.

1.1.3 Settlement Areas

Settlement areas are urban areas and rural settlement areas, and include cities, towns, villages and hamlets. Ontario's settlement areas vary significantly in terms of size, density, population, economic activity, diversity and intensity of land uses, service levels, and types of infrastructure available.

The vitality and regeneration of settlement areas is critical to the long-term economic prosperity of our communities. Development pressures and land use change will vary across Ontario. It is in the interest of all communities to use land and resources wisely, to promote efficient development patterns, protect resources, promote green spaces, ensure effective use of infrastructure and public service facilities and minimize unnecessary public expenditures.

1.1.3.1 *Settlement areas* shall be the focus of growth and development.

1.1.3.2 Land use patterns within *settlement areas* shall be based on densities and a mix of land uses which:

a) efficiently use land and resources;
b) are appropriate for, and efficiently use, the *infrastructure* and *public service facilities* which are planned or available, and avoid the need for their unjustified and/or uneconomical expansion;
c) minimize negative impacts to air quality and climate change, and promote energy efficiency;
d) prepare for the *impacts of a changing climate*;
e) support *active transportation*;
f) are *transit-supportive*, where transit is planned, exists or may be developed; and
g) are *freight-supportive*.

Land use patterns within *settlement areas* shall also be based on a range of uses and opportunities for *intensification* and *redevelopment* in accordance with the criteria in policy 1.1.3.3, where this can be accommodated.

1.1.3.3 Planning authorities shall identify appropriate locations and promote opportunities for *transit-supportive* development, accommodating a significant supply and range of *housing options* through *intensification* and *redevelopment* where this can be accommodated taking into account existing building stock or areas, including *brownfield sites*, and the availability of suitable existing or planned *infrastructure* and *public service facilities* required to accommodate projected needs.

1.1.3.4 Appropriate development standards should be promoted which facilitate *intensification*, *redevelopment* and compact form, while avoiding or mitigating risks to public health and safety.

1.1.3.5 Planning authorities shall establish and implement minimum targets for *intensification* and *redevelopment* within built-up areas, based on local conditions. However, where provincial targets are established through *provincial plans*, the provincial target shall represent the minimum target for affected areas.

1.1.3.6 New development taking place in *designated growth areas* should occur adjacent to the existing built-up area and should have a compact form, mix of uses and densities that allow for the efficient use of land, *infrastructure* and *public service facilities*.

1.1.3.7 Planning authorities should establish and implement phasing policies to ensure:

a) that specified targets for *intensification* and *redevelopment* are achieved prior to, or concurrent with, new development within *designated growth areas*; and
b) the orderly progression of development within *designated growth areas* and the timely provision of the *infrastructure* and *public service facilities* required to meet current and projected needs.

1.1.3.8 A planning authority may identify a *settlement area* or allow the expansion of a *settlement area* boundary only at the time of a *comprehensive review* and only where it has been demonstrated that:

a) sufficient opportunities to accommodate growth and to satisfy market demand are not available through *intensification*, *redevelopment* and *designated growth areas* to accommodate the projected needs over the identified planning horizon;
b) the *infrastructure* and *public service facilities* which are planned or available are suitable for the development over the long term, are financially viable over their life cycle, and protect public health and safety and the natural environment;
c) in *prime agricultural areas*:
    1. the lands do not comprise *specialty crop areas*;
    2. alternative locations have been evaluated, and

i. there are no reasonable alternatives which avoid *prime agricultural areas*; and
ii. there are no reasonable alternatives on lower priority agricultural lands in *prime agricultural areas*;

d) the new or expanding *settlement area* is in compliance with the *minimum distance separation formulae*; and
e) impacts from new or expanding *settlement areas* on agricultural operations which are adjacent or close to the *settlement area* are mitigated to the extent feasible.

In undertaking a *comprehensive review*, the level of detail of the assessment should correspond with the complexity and scale of the settlement boundary expansion or development proposal.

1.1.3.9 Notwithstanding policy 1.1.3.8, municipalities may permit adjustments of *settlement area* boundaries outside a *comprehensive review* provided:

a) there would be no net increase in land within the *settlement areas*;
b) the adjustment would support the municipality's ability to meet *intensification* and *redevelopment* targets established by the municipality;
c) *prime agricultural areas* are addressed in accordance with 1.1.3.8 (c), (d) and (e); and
d) the *settlement area* to which lands would be added is appropriately serviced and there is sufficient reserve *infrastructure* capacity to service the lands.

1.1.4 Rural Areas in Municipalities

Rural areas are important to the economic success of the Province and our quality of life. Rural areas are a system of lands that may include rural settlement areas, rural lands, prime agricultural areas, natural heritage features and areas, and other resource areas. Rural areas and urban areas are interdependent in terms of markets, resources and amenities. It is important to leverage rural assets and amenities and protect the environment as a foundation for a sustainable economy.

Ontario's rural areas have diverse population levels, natural resources, geographies and physical characteristics, and economies. Across rural Ontario, local circumstances vary by region. For example, northern Ontario's natural environment and vast geography offer different opportunities than the predominately agricultural areas of southern regions of the Province.

1.1.4.1 Healthy, integrated and viable *rural areas* should be supported by:

a) building upon rural character, and leveraging rural amenities and assets;
b) promoting regeneration, including the redevelopment of *brownfield sites*;
c) accommodating an appropriate range and mix of housing in rural *settlement areas*;
d) encouraging the conservation and *redevelopment* of existing rural housing stock on *rural lands*;
e) using rural *infrastructure* and *public service facilities* efficiently;

f) promoting diversification of the economic base and employment opportunities through goods and services, including value-added products and the sustainable management or use of resources;
g) providing opportunities for sustainable and diversified tourism, including leveraging historical, cultural, and natural assets;
h) conserving biodiversity and considering the ecological benefits provided by nature; and
i) providing opportunities for economic activities in *prime agricultural areas*, in accordance with policy 2.3.

1.1.4.2 In *rural areas*, rural *settlement areas* shall be the focus of growth and development and their vitality and regeneration shall be promoted.

1.1.4.3 When directing development in rural *settlement areas* in accordance with policy 1.1.3, planning authorities shall give consideration to rural characteristics, the scale of development and the provision of appropriate service levels.

1.1.4.4 Growth and development may be directed to *rural lands* in accordance with policy 1.1.5, including where a municipality does not have a *settlement area*.

1.1.5 Rural Lands in Municipalities

1.1.5.1 When directing development on *rural lands*, a planning authority shall apply the relevant policies of Section 1: Building Strong Healthy Communities, as well as the policies of Section 2: Wise Use and Management of Resources and Section 3: Protecting Public Health and Safety.

1.1.5.2 On *rural lands* located in municipalities, permitted uses are:

a) the management or use of resources;
b) resource-based recreational uses (including recreational dwellings);
c) residential development, including lot creation, that is locally appropriate;
d) a*gricultural uses*, *agriculture-related uses*, *on-farm diversified uses* and *normal farm practices,* in accordance with provincial standards;
e) home occupations and home industries;
f) cemeteries; and
g) other rural land uses.

1.1.5.3 Recreational, tourism and other economic opportunities should be promoted.

1.1.5.4 Development that is compatible with the rural landscape and can be sustained by rural service levels should be promoted.

1.1.5.5 Development shall be appropriate to the *infrastructure* which is planned or available, and avoid the need for the unjustified and/or uneconomical expansion of this *infrastructure*.

1.1.5.6 Opportunities should be retained to locate new or expanding land uses that require separation from other uses.

1.1.5.7 Opportunities to support a diversified rural economy should be promoted by protecting agricultural and other resource-related uses and directing non-related development to areas where it will minimize constraints on these uses.

1.1.5.8 New land uses, including the creation of lots, and new or expanding livestock facilities, shall comply with the *minimum distance separation formulae*.

1.1.6 Territory Without Municipal Organization

1.1.6.1 On *rural lands* located in territory without municipal organization, the focus of development activity shall be related to the sustainable management or use of resources and resource-based recreational uses (including recreational dwellings).

1.1.6.2 Development shall be appropriate to the *infrastructure* which is planned or available, and avoid the need for the unjustified and/or uneconomical expansion of this *infrastructure*.

1.1.6.3 The establishment of new permanent townsites shall not be permitted.

1.1.6.4 In areas adjacent to and surrounding municipalities, only development that is related to the sustainable management or use of resources and resource-based recreational uses (including recreational dwellings) shall be permitted. Other uses may only be permitted if:

a) the area forms part of a planning area;
b) the necessary *infrastructure* and *public service facilities* are planned or available to support the development and are financially viable over their life cycle; and
c) it has been determined, as part of a *comprehensive review*, that the impacts of development will not place an undue strain on the *public service facilities* and *infrastructure* provided by adjacent municipalities, regions and/or the Province.

1.2 Coordination

1.2.1 A coordinated, integrated and comprehensive approach should be used when dealing with planning matters within municipalities, across lower, single and/or upper-tier municipal boundaries, and with other orders of government, agencies and boards including:

a) managing and/or promoting growth and development that is integrated with *infrastructure* planning;
b) economic development strategies;

c) managing natural heritage, water, agricultural, mineral, and cultural heritage and archaeological resources;
d) *infrastructure*, *multimodal transportation systems*, *public service facilities* and *waste management systems*;
e) ecosystem, shoreline, watershed, and Great Lakes related issues;
f) natural and human-made hazards;
g) population, housing and employment projections, based on *regional market areas*; and
h) addressing housing needs in accordance with provincial policy statements such as the Policy Statement: Service Manager Housing and Homelessness Plans.

1.2.2 Planning authorities shall engage with Indigenous communities and coordinate on land use planning matters.

1.2.3 Planning authorities should coordinate emergency management and other economic, environmental and social planning considerations to support efficient and resilient communities.

1.2.4 Where planning is conducted by an upper-tier municipality, the upper-tier municipality in consultation with lower-tier municipalities shall:

a) identify and allocate population, housing and employment projections for lower-tier municipalities. Allocations and projections by upper-tier municipalities shall be based on and reflect *provincial plans* where these exist and informed by provincial guidelines;
b) identify areas where growth or development will be directed, including the identification of nodes and the corridors linking these nodes;
c) identify targets for *intensification* and *redevelopment* within all or any of the lower-tier municipalities, including minimum targets that should be met before expansion of the boundaries of *settlement areas* is permitted in accordance with policy 1.1.3.8;
d) where major transit corridors exist or are to be developed, identify density targets for areas adjacent or in proximity to these corridors and stations, including minimum targets that should be met before expansion of the boundaries of *settlement areas* is permitted in accordance with policy 1.1.3.8; and
e) provide policy direction for the lower-tier municipalities on matters that cross municipal boundaries.

1.2.5 Where there is no upper-tier municipality, planning authorities shall ensure that policy 1.2.4 is addressed as part of the planning process, and should coordinate these matters with adjacent planning authorities.

1.2.6 Land Use Compatibility

1.2.6.1 *Major facilities* and *sensitive land uses* shall be planned and developed to avoid, or if avoidance is not possible, minimize and mitigate any potential *adverse effects* from odour, noise and other contaminants, minimize risk to public health and safety, and to ensure the long-term operational and economic viability of *major facilities* in accordance with provincial guidelines, standards and procedures.

1.2.6.2 Where avoidance is not possible in accordance with policy 1.2.6.1, planning authorities shall protect the long-term viability of existing or planned industrial, manufacturing or other uses that are vulnerable to encroachment by ensuring that the planning and *development* of proposed adjacent *sensitive land uses* are only permitted if the following are demonstrated in accordance with provincial guidelines, standards and procedures:

a) there is an identified need for the proposed use;
b) alternative locations for the proposed use have been evaluated and there are no reasonable alternative locations;
c) *adverse effects* to the proposed *sensitive land use* are minimized and mitigated; and
d) potential impacts to industrial, manufacturing or other uses are minimized and mitigated.

1.3 Employment

1.3.1 Planning authorities shall promote economic development and competitiveness by:

a) providing for an appropriate mix and range of employment, institutional, and broader mixed uses to meet long-term needs;
b) providing opportunities for a diversified economic base, including maintaining a range and choice of suitable sites for employment uses which support a wide range of economic activities and ancillary uses, and take into account the needs of existing and future businesses;
c) facilitating the conditions for economic investment by identifying strategic sites for investment, monitoring the availability and suitability of employment sites, including market-ready sites, and seeking to address potential barriers to investment;
d) encouraging compact, mixed-use development that incorporates compatible employment uses to support liveable and resilient communities, with consideration of housing policy 1.4; and
e) ensuring the necessary *infrastructure* is provided to support current and projected needs.

1.3.2 Employment Areas

1.3.2.1 Planning authorities shall plan for, protect and preserve *employment areas* for current and future uses and ensure that the necessary *infrastructure* is provided to support current and projected needs.

1.3.2.2 At the time of the official plan review or update, planning authorities should assess *employment areas* identified in local official plans to ensure that this designation is appropriate to the planned function of the *employment area*.

Employment areas planned for industrial and manufacturing uses shall provide for separation or mitigation from *sensitive land uses* to maintain the long-term operational and economic viability of the planned uses and function of these areas.

1.3.2.3 Within *employment areas* planned for industrial or manufacturing uses, planning authorities shall prohibit residential uses and prohibit or limit other *sensitive land uses* that are not ancillary to the primary employment uses in order to maintain land use compatibility.

Employment areas planned for industrial or manufacturing uses should include an appropriate transition to adjacent non-*employment areas*.

1.3.2.4 Planning authorities may permit conversion of lands within *employment areas* to non-employment uses through a *comprehensive review*, only where it has been demonstrated that the land is not required for employment purposes over the long term and that there is a need for the conversion.

1.3.2.5 Notwithstanding policy 1.3.2.4, and until the official plan review or update in policy 1.3.2.4 is undertaken and completed, lands within existing *employment areas* may be converted to a designation that permits non-employment uses provided the area has not been identified as provincially significant through a provincial plan exercise or as regionally significant by a regional economic development corporation working together with affected upper and single-tier municipalities and subject to the following:

a) there is an identified need for the conversion and the land is not required for employment purposes over the long term;
b) the proposed uses would not adversely affect the overall viability of the *employment area*; and
c) existing or planned *infrastructure* and *public service facilities* are available to accommodate the proposed uses.

1.3.2.6 Planning authorities shall protect *employment areas* in proximity to *major goods movement facilities and corridors* for employment uses that require those locations.

1.3.2.7 Planning authorities may plan beyond 25 years for the long-term protection of employment areas provided lands are not designated beyond the planning horizon identified in policy 1.1.2.

1.4 Housing

1.4.1 To provide for an appropriate range and mix of *housing options* and densities required to meet projected requirements of current and future residents of the *regional market area*, planning authorities shall:

a) maintain at all times the ability to accommodate residential growth for a minimum of 15 years through *residential intensification* and *redevelopment* and, if necessary, lands which are *designated and available* for residential development; and
b) maintain at all times where new development is to occur, land with servicing capacity sufficient to provide at least a three-year supply of residential units available through lands suitably zoned to facilitate *residential intensification* and *redevelopment*, and land in draft approved and registered plans.

Upper-tier and single-tier municipalities may choose to maintain land with servicing capacity sufficient to provide at least a five-year supply of residential units available through lands suitably zoned to facilitate *residential intensification* and *redevelopment*, and land in draft approved and registered plans.

1.4.2 Where planning is conducted by an upper-tier municipality:

a) the land and unit supply maintained by the lower-tier municipality identified in policy 1.4.1 shall be based on and reflect the allocation of population and units by the upper-tier municipality; and
b) the allocation of population and units by the upper-tier municipality shall be based on and reflect *provincial plans* where these exist.

1.4.3 Planning authorities shall provide for an appropriate range and mix of *housing options* and densities to meet projected market-based and affordable housing needs of current and future residents of the *regional market area* by:

a) establishing and implementing minimum targets for the provision of housing which is *affordable* to *low and moderate income households* and which aligns with applicable housing and homelessness plans. However, where planning is conducted by an upper-tier municipality, the upper-tier municipality in consultation with the lower-tier municipalities may identify a higher target(s) which shall represent the minimum target(s) for these lower-tier municipalities;
b) permitting and facilitating:
    1. all *housing options* required to meet the social, health, economic and well-being requirements of current and future residents, including *special needs* requirements and needs arising from demographic changes and employment opportunities; and
    2. all types of *residential intensification*, including additional residential units, and *redevelopment* in accordance with policy 1.1.3.3;

c) directing the development of new housing towards locations where appropriate levels of *infrastructure* and *public service facilities* are or will be available to support current and projected needs;
d) promoting densities for new housing which efficiently use land, resources, *infrastructure* and *public service facilities*, and support the use of *active transportation* and transit in areas where it exists or is to be developed;
e) requiring *transit-supportive* development and prioritizing *intensification,* including potential air rights development, in proximity to transit, including corridors and stations; and
f) establishing development standards for *residential intensification*, *redevelopment* and new residential development which minimize the cost of housing and facilitate compact form, while maintaining appropriate levels of public health and safety.

1.5 Public Spaces, Recreation, Parks, Trails and Open Space

1.5.1 Healthy, active communities should be promoted by:

a) planning public streets, spaces and facilities to be safe, meet the needs of pedestrians, foster social interaction and facilitate *active transportation* and community connectivity;
b) planning and providing for a full range and equitable distribution of publicly-accessible built and natural settings for *recreation*, including facilities, parklands, public spaces, open space areas, trails and linkages, and, where practical, water-based resources;
c) providing opportunities for public access to shorelines; and
d) recognizing provincial parks, conservation reserves, and other protected areas, and minimizing negative impacts on these areas.

1.6 Infrastructure and Public Service Facilities

1.6.1 *Infrastructure* and *public service facilities* shall be provided in an efficient manner that prepares for the *impacts of a changing climate* while accommodating projected needs.

Planning for *infrastructure* and *public service facilities* shall be coordinated and integrated with land use planning and growth management so that they are:

a) financially viable over their life cycle, which may be demonstrated through asset management planning; and
b) available to meet current and projected needs.

1.6.2 Planning authorities should promote g*reen infrastructure* to complement *infrastructure*.

1.6.3 Before consideration is given to developing new *infrastructure* and *public service facilities*:

a) the use of existing *infrastructure* and *public service facilities* should be optimized; and
b) opportunities for adaptive re-use should be considered, wherever feasible.

1.6.4 *Infrastructure* and *public service facilities* should be strategically located to support the effective and efficient delivery of emergency management services, and to ensure the protection of public health and safety in accordance with the policies in Section 3.0: Protecting Public Health and Safety.

1.6.5 *Public service facilities* should be co-located in community hubs, where appropriate, to promote cost-effectiveness and facilitate service integration, access to transit and *active transportation*.

1.6.6 Sewage, Water and Stormwater

1.6.6.1 Planning for *sewage and water services* shall:

a) accommodate forecasted growth in a manner that promotes the efficient use and optimization of existing:
    1. *municipal sewage services* and *municipal water services*; and
    2. *private communal sewage services* and *private communal water services*, where *municipal sewage services* and *municipal water services* are not available or feasible;
b) ensure that these systems are provided in a manner that:
    1. can be sustained by the water resources upon which such services rely;
    2. prepares for the *impacts of a changing climate;*
    3. is feasible and financially viable over their lifecycle; and
    4. protects human health and safety, and the natural environment;
c) promote water conservation and water use efficiency;
d) integrate servicing and land use considerations at all stages of the planning process; and
e) be in accordance with the servicing hierarchy outlined through policies 1.6.6.2, 1.6.6.3, 1.6.6.4 and 1.6.6.5. For clarity, where *municipal sewage services and municipal water services* are not available, planned or feasible, planning authorities have the ability to consider the use of the servicing options set out through policies 1.6.6.3, 1.6.6.4, and 1.6.6.5 provided that the specified conditions are met.

1.6.6.2 *Municipal sewage services* and *municipal water services* are the preferred form of servicing for *settlement areas* to support protection of the environment and minimize potential risks to human health and safety. Within *settlement areas* with existing *municipal sewage services* and *municipal water services*, *intensification* and *redevelopment* shall be promoted wherever feasible to optimize the use of the services.

1.6.6.3 Where *municipal sewage services* and *municipal water services* are not available, planned or feasible, *private communal sewage services* and *private communal water services* are the preferred form of servicing for multi-unit/lot *development* to support protection of the environment and minimize potential risks to human health and safety.

1.6.6.4 Where *municipal sewage services* and *municipal water services* or *private communal sewage services* and *private communal water services* are not available, planned or feasible, *individual on-site sewage services* and *individual on-site water services* may be used provided that site conditions are suitable for the long-term provision of such services with no *negative impacts*. In *settlement areas*, *individual on-site sewage services* and *individual on-site water services* may be used for infilling and minor rounding out of existing development.

At the time of the official plan review or update, planning authorities should assess the long-term impacts of *individual on-site sewage services* and *individual on-site water services* on the environmental health and the character of rural *settlement areas*. Where planning is conducted by an upper-tier municipality, the upper-tier municipality should work with lower-tier municipalities at the time of the official plan review or update to assess the long-term impacts of *individual on-site sewage services* and *individual on-site water services* on the environmental health and the desired character of rural *settlement areas* and the feasibility of other forms of servicing set out in policies 1.6.6.2 and 1.6.6.3.

1.6.6.5 *Partial services* shall only be permitted in the following circumstances:

a) where they are necessary to address failed *individual on-site sewage services* and *individual on-site water services* in existing development; or
b) within *settlement areas*, to allow for infilling and minor rounding out of existing development on *partial services* provided that site conditions are suitable for the long-term provision of such services with no *negative impacts*.

Where *partial services* have been provided to address failed services in accordance with subsection (a), infilling on existing lots of record in *rural areas* in municipalities may be permitted where this would represent a logical and financially viable connection to the existing *partial service* and provided that site conditions are suitable for the long-term provision of such services with no *negative impacts*. In accordance with subsection (a), the extension of *partial services* into *rural areas* is only permitted to address failed *individual on-site sewage* and *individual on-site water services* for existing development.

1.6.6.6 Subject to the hierarchy of services provided in policies 1.6.6.2, 1.6.6.3, 1.6.6.4 and 1.6.6.5, planning authorities may allow lot creation only if there is confirmation of sufficient *reserve sewage system capacity* and *reserve water system capacity* within *municipal sewage services* and *municipal water services* or *private communal sewage services* and *private communal water services*. The determination of

sufficient *reserve sewage system capacity* shall include treatment capacity for hauled sewage from *private communal sewage services* and *individual on-site sewage services*.

1.6.6.7 Planning for stormwater management shall:

a) be integrated with planning for *sewage and water services* and ensure that systems are optimized, feasible and financially viable over the long term;
b) minimize, or, where possible, prevent increases in contaminant loads;
c) minimize erosion and changes in water balance, and prepare for the *impacts of a changing climate* through the effective management of stormwater, including the use of *green infrastructure*;
d) mitigate risks to human health, safety, property and the environment;
e) maximize the extent and function of vegetative and pervious surfaces; and
f) promote stormwater management best practices, including stormwater attenuation and re-use, water conservation and efficiency, and low impact development.

1.6.7 Transportation Systems

1.6.7.1 *Transportation systems* should be provided which are safe, energy efficient, facilitate the movement of people and goods, and are appropriate to address projected needs.

1.6.7.2 Efficient use should be made of existing and planned *infrastructure*, including through the use of *transportation demand management* strategies, where feasible.

1.6.7.3 As part of a *multimodal transportation system*, connectivity within and among *transportation systems* and modes should be maintained and, where possible, improved including connections which cross jurisdictional boundaries.

1.6.7.4 A land use pattern, density and mix of uses should be promoted that minimize the length and number of vehicle trips and support current and future use of transit and *active transportation*.

1.6.8 Transportation and Infrastructure Corridors

1.6.8.1 Planning authorities shall plan for and protect corridors and rights-of-way for *infrastructure*, including transportation, transit and electricity generation facilities and transmission systems to meet current and projected needs.

1.6.8.2 *Major goods movement facilities and corridors* shall be protected for the long term.

1.6.8.3 Planning authorities shall not permit *development* in *planned corridors* that could preclude or negatively affect the use of the corridor for the purpose(s) for which it was identified.

New *development* proposed on *adjacent lands* to existing or *planned corridors* and transportation facilities should be compatible with, and supportive of, the long-term purposes of the corridor and should be designed to avoid, mitigate or minimize negative impacts on and from the corridor and transportation facilities.

1.6.8.4 The preservation and reuse of abandoned corridors for purposes that maintain the corridor's integrity and continuous linear characteristics should be encouraged, wherever feasible.

1.6.8.5 The co-location of linear *infrastructure* should be promoted, where appropriate.

1.6.8.6 When planning for corridors and rights-of-way for significant transportation, electricity transmission, and *infrastructure* facilities, consideration will be given to the significant resources in Section 2: Wise Use and Management of Resources.

1.6.9 Airports, Rail and Marine Facilities

1.6.9.1 Planning for land uses in the vicinity of *airports*, *rail facilities* and *marine facilities* shall be undertaken so that:

a) their long-term operation and economic role is protected; and
b) *airports*, *rail facilities* and *marine facilities* and *sensitive land uses* are appropriately designed, buffered and/or separated from each other, in accordance with policy 1.2.6.

1.6.9.2 *Airports* shall be protected from incompatible land uses and development by:

a) prohibiting new residential *development* and other sensitive land uses in areas near *airports* above 30 NEF/NEP;
b) considering redevelopment of existing residential uses and other sensitive land uses or infilling of residential and other sensitive land uses in areas above 30 NEF/NEP only if it has been demonstrated that there will be no negative impacts on the long-term function of the *airport*; and
c) discouraging land uses which may cause a potential aviation safety hazard.

1.6.10 Waste Management

1.6.10.1 *Waste management systems* need to be provided that are of an appropriate size and type to accommodate present and future requirements, and facilitate, encourage and promote reduction, reuse and recycling objectives.

Waste management systems shall be located and designed in accordance with provincial legislation and standards.

1.6.11 Energy Supply

1.6.11.1 Planning authorities should provide opportunities for the development of energy supply including electricity generation facilities and transmission and distribution systems, district energy, and *renewable energy systems* and *alternative energy systems*, to accommodate current and projected needs.

1.7 Long-Term Economic Prosperity

1.7.1 Long-term economic prosperity should be supported by:

a) promoting opportunities for economic development and community investment-readiness;
b) encouraging residential uses to respond to dynamic market-based needs and provide necessary housing supply and range of *housing options* for a diverse workforce;
c) optimizing the long-term availability and use of land, resources, *infrastructure* and *public service facilities*;
d) maintaining and, where possible, enhancing the vitality and viability of downtowns and mainstreets;
e) encouraging a sense of place, by promoting well-designed built form and cultural planning, and by conserving features that help define character, including *built heritage resources* and *cultural heritage landscapes*;
f) promoting the redevelopment of *brownfield sites*;
g) providing for an efficient, cost-effective, reliable *multimodal transportation system* that is integrated with adjacent systems and those of other jurisdictions, and is appropriate to address projected needs to support the movement of goods and people;
h) providing opportunities for sustainable tourism development;
i) sustaining and enhancing the viability of the *agricultural system* through protecting agricultural resources, minimizing land use conflicts, providing opportunities to support local food, and maintaining and improving the *agri-food network;*
j) promoting energy conservation and providing opportunities for increased energy supply;
k) minimizing negative impacts from a changing climate and considering the ecological benefits provided by nature; and
l) encouraging efficient and coordinated communications and telecommunications infrastructure.

1.8 Energy Conservation, Air Quality and Climate Change

1.8.1 Planning authorities shall support energy conservation and efficiency, improved air quality, reduced greenhouse gas emissions, and preparing for the *impacts of a changing climate* through land use and development patterns which:

a) promote compact form and a structure of nodes and corridors;
b) promote the use of *active transportation* and transit in and between residential, employment (including commercial and industrial) and institutional uses and other areas;
c) focus major employment, commercial and other travel-intensive land uses on sites which are well served by transit where this exists or is to be developed, or designing these to facilitate the establishment of transit in the future;
d) focus freight-intensive land uses to areas well served by major highways, *airports*, *rail facilities* and *marine facilities*;
e) encourage *transit-supportive* development and *intensification* to improve the mix of employment and housing uses to shorten commute journeys and decrease transportation congestion;
f) promote design and orientation which maximizes energy efficiency and conservation, and considers the mitigating effects of vegetation and *green infrastructure*; and
g) maximize vegetation within *settlement areas*, where feasible.

2.0 Wise Use and Management of Resources

Ontario's long-term prosperity, environmental health, and social well-being depend on conserving biodiversity, protecting the health of the Great Lakes, and protecting natural heritage, water, agricultural, mineral and cultural heritage and archaeological resources for their economic, environmental and social benefits.

Accordingly:

2.1 Natural Heritage

2.1.1 Natural features and areas shall be protected for the long term.

2.1.2 The diversity and connectivity of natural features in an area, and the long-term *ecological function* and biodiversity of *natural heritage systems*, should be maintained, restored or, where possible, improved, recognizing linkages between and among *natural heritage features and areas*, *surface water features* and *ground water features*.

2.1.3 *Natural heritage systems* shall be identified in Ecoregions 6E & 7E[1], recognizing that *natural heritage systems* will vary in size and form in *settlement areas*, *rural areas*, and *prime agricultural areas*.

2.1.4 *Development* and *site alteration* shall not be permitted in:

a) *significant wetlands* in Ecoregions 5E, 6E and 7E[1]; and
b) *significant coastal wetlands*.

2.1.5 *Development* and *site alteration* shall not be permitted in:

a) *significant wetlands* in the Canadian Shield north of Ecoregions 5E, 6E and 7E[1];
b) *significant woodlands* in Ecoregions 6E and 7E (excluding islands in Lake Huron and the St. Marys River)[1];
c) *significant valleylands* in Ecoregions 6E and 7E (excluding islands in Lake Huron and the St. Marys River)[1];
d) *significant wildlife habitat*;
e) *significant areas of natural and scientific interest*; and
f) *coastal wetlands* in Ecoregions 5E, 6E and 7E[1] that are not subject to policy 2.1.4(b)

unless it has been demonstrated that there will be no *negative impacts* on the natural features or their *ecological functions*.

[1] Ecoregions 5E, 6E and 7E are shown on Figure 1.

2.1.6 *Development* and *site alteration* shall not be permitted in *fish habitat* except in accordance with *provincial and federal requirements*.

2.1.7 *Development* and *site alteration* shall not be permitted in *habitat of endangered species and threatened species*, except in accordance with *provincial and federal requirements*.

2.1.8 *Development* and *site alteration* shall not be permitted on *adjacent lands* to the *natural heritage features and areas* identified in policies 2.1.4, 2.1.5, and 2.1.6 unless the *ecological function* of the *adjacent lands* has been evaluated and it has been demonstrated that there will be no *negative impacts* on the natural features or on their *ecological functions*.

2.1.9 Nothing in policy 2.1 is intended to limit the ability of *agricultural uses* to continue.

2.2 Water

2.2.1 Planning authorities shall protect, improve or restore the *quality and quantity of water* by:

a) using the *watershed* as the ecologically meaningful scale for integrated and long-term planning, which can be a foundation for considering cumulative impacts of development;
b) minimizing potential *negative impacts*, including cross-jurisdictional and cross-*watershed* impacts;
c) evaluating and preparing for the *impacts of a changing climate* to water resource systems at the watershed level;
d) identifying water resource systems consisting of *ground water features*, *hydrologic functions*, *natural heritage features and areas*, and *surface water features* including shoreline areas, which are necessary for the ecological and hydrological integrity of the *watershed*;
e) maintaining linkages and related functions among *ground water features*, *hydrologic functions*, *natural heritage features and areas*, and *surface water features* including shoreline areas;
f) implementing necessary restrictions on *development* and *site alteration* to:
    1. protect all municipal drinking water supplies and *designated vulnerable areas*; and
    2. protect, improve or restore *vulnerable* surface and ground water, *sensitive surface water features* and *sensitive ground water features*, and their *hydrologic functions*;
g) planning for efficient and sustainable use of water resources, through practices for water conservation and sustaining water quality;
h) ensuring consideration of environmental lake capacity, where applicable; and
i) ensuring stormwater management practices minimize stormwater volumes and contaminant loads, and maintain or increase the extent of vegetative and pervious surfaces.

2.2.2 *Development* and *site alteration* shall be restricted in or near *sensitive surface water features* and *sensitive ground water features* such that these features and their related *hydrologic functions* will be protected, improved or restored.

Mitigative measures and/or alternative development approaches may be required in order to protect, improve or restore *sensitive surface water features*, *sensitive ground water features*, and their *hydrologic functions*.

2.3 Agriculture

2.3.1 *Prime agricultural areas* shall be protected for long-term use for agriculture.

Prime agricultural areas are areas where *prime agricultural lands* predominate. *Specialty crop areas* shall be given the highest priority for protection, followed by Canada Land Inventory Class 1, 2, and 3 lands, and any associated Class 4 through 7 lands within the *prime agricultural area*, in this order of priority.

2.3.2 Planning authorities shall designate *prime agricultural areas* and *specialty crop areas* in accordance with guidelines developed by the Province, as amended from time to time.

Planning authorities are encouraged to use an *agricultural system* approach to maintain and enhance the geographic continuity of the agricultural land base and the functional and economic connections to the *agri-food network.*

2.3.3 Permitted Uses

2.3.3.1 In *prime agricultural areas*, permitted uses and activities are: *agricultural uses*, *agriculture-related uses* and *on-farm diversified uses*.

Proposed *agriculture-related uses* and *on-farm diversified uses* shall be compatible with, and shall not hinder, surrounding agricultural operations. Criteria for these uses may be based on guidelines developed by the Province or municipal approaches, as set out in municipal planning documents, which achieve the same objectives.

2.3.3.2 In *prime agricultural areas*, all types, sizes and intensities of *agricultural uses* and *normal farm practices* shall be promoted and protected in accordance with provincial standards.

2.3.3.3 New land uses in *prime agricultural areas,* including the creation of lots and new or expanding livestock facilities, shall comply with the *minimum distance separation formulae*.

2.3.4 Lot Creation and Lot Adjustments

2.3.4.1 Lot creation in *prime agricultural areas* is discouraged and may only be permitted for:

a) *agricultural uses*, provided that the lots are of a size appropriate for the type of agricultural use(s) common in the area and are sufficiently large to maintain flexibility for future changes in the type or size of agricultural operations;
b) *agriculture-related uses*, provided that any new lot will be limited to a minimum size needed to accommodate the use and appropriate *sewage and water services*;
c) a *residence surplus to a farming operation* as a result of farm consolidation, provided that:
   1. the new lot will be limited to a minimum size needed to accommodate the use and appropriate *sewage and water services*; and
   2. the planning authority ensures that new residential dwellings are prohibited on any remnant parcel of farmland created by the severance. The approach used to ensure that no new residential dwellings are permitted on the remnant parcel may be recommended by the Province, or based on municipal approaches which achieve the same objective; and
d) *infrastructure*, where the facility or corridor cannot be accommodated through the use of easements or rights-of-way.

2.3.4.2 Lot adjustments in *prime agricultural areas* may be permitted for *legal or technical reasons*.

2.3.4.3 The creation of new residential lots in *prime agricultural areas* shall not be permitted, except in accordance with policy 2.3.4.1(c).

2.3.5 Removal of Land from Prime Agricultural Areas

2.3.5.1 Planning authorities may only exclude land from *prime agricultural areas* for expansions of or identification of *settlement areas* in accordance with policy 1.1.3.8.

2.3.6 Non-Agricultural Uses in Prime Agricultural Areas

2.3.6.1 Planning authorities may only permit non-agricultural uses in *prime agricultural areas* for:

a) extraction of *minerals*, *petroleum resources* and *mineral aggregate resources*; or
b) limited non-residential uses, provided that all of the following are demonstrated:

1. the land does not comprise a *specialty crop area*;
2. the proposed use complies with the *minimum distance separation formulae*;
3. there is an identified need within the planning horizon provided for in policy 1.1.2 for additional land to accommodate the proposed use; and
4. alternative locations have been evaluated, and
   i. there are no reasonable alternative locations which avoid *prime agricultural areas*; and
   ii. there are no reasonable alternative locations in *prime agricultural areas* with lower priority agricultural lands.

2.3.6.2 Impacts from any new or expanding non-agricultural uses on surrounding agricultural operations and lands are to be mitigated to the extent feasible.

2.4 Minerals and Petroleum

2.4.1 *Minerals* and *petroleum resources* shall be protected for long-term use.

2.4.2 Protection of Long-Term Resource Supply

2.4.2.1 *Mineral mining operations* and *petroleum resource operations* shall be identified and protected from *development* and activities that would preclude or hinder their expansion or continued use or which would be incompatible for reasons of public health, public safety or environmental impact.

2.4.2.2 Known *mineral deposits*, known *petroleum resources* and *significant areas of mineral potential* shall be identified and *development* and activities in these resources or on *adjacent lands* which would preclude or hinder the establishment of new operations or access to the resources shall only be permitted if:

a) resource use would not be feasible; or
b) the proposed land use or development serves a greater long-term public interest; and
c) issues of public health, public safety and environmental impact are addressed.

2.4.3 Rehabilitation

2.4.3.1 Rehabilitation to accommodate subsequent land uses shall be required after extraction and other related activities have ceased. Progressive rehabilitation should be undertaken wherever feasible.

2.4.4 Extraction in Prime Agricultural Areas

2.4.4.1 Extraction of *minerals* and *petroleum resources* is permitted in *prime agricultural areas* provided that the site will be rehabilitated.

2.5 Mineral Aggregate Resources

2.5.1 *Mineral aggregate resources* shall be protected for long-term use and, where provincial information is available, *deposits of mineral aggregate resources* shall be identified.

2.5.2 Protection of Long-Term Resource Supply

2.5.2.1 As much of the *mineral aggregate resources* as is realistically possible shall be made available as close to markets as possible.

Demonstration of need for *mineral aggregate resources*, including any type of supply/demand analysis, shall not be required, notwithstanding the availability, designation or licensing for extraction of *mineral aggregate resources* locally or elsewhere.

2.5.2.2 Extraction shall be undertaken in a manner which minimizes social, economic and environmental impacts.

2.5.2.3 *Mineral aggregate resource conservation* shall be undertaken, including through the use of accessory aggregate recycling facilities within operations, wherever feasible.

2.5.2.4 *Mineral aggregate operations* shall be protected from *development* and activities that would preclude or hinder their expansion or continued use or which would be incompatible for reasons of public health, public safety or environmental impact. Existing *mineral aggregate operations* shall be permitted to continue without the need for official plan amendment, rezoning or development permit under the *Planning Act*. Where the *Aggregate Resources Act* applies, only processes under the *Aggregate Resources Act* shall address the depth of extraction of new or existing *mineral aggregate operations*. When a license for extraction or operation ceases to exist, policy 2.5.2.5 continues to apply.

2.5.2.5 In known *deposits of mineral aggregate resources* and on *adjacent lands*, *development* and activities which would preclude or hinder the establishment of new operations or access to the resources shall only be permitted if:

a) resource use would not be feasible; or
b) the proposed land use or development serves a greater long-term public interest; and
c) issues of public health, public safety and environmental impact are addressed.

2.5.3 Rehabilitation

2.5.3.1 Progressive and final rehabilitation shall be required to accommodate subsequent land uses, to promote land use compatibility, to recognize the interim nature of extraction, and to mitigate negative impacts to the extent possible. Final rehabilitation shall take surrounding land use and approved land use designations into consideration.

2.5.3.2 *Comprehensive rehabilitation* planning is encouraged where there is a concentration of mineral aggregate operations.

2.5.3.3 In parts of the Province not designated under the *Aggregate Resources Act*, rehabilitation standards that are compatible with those under the Act should be adopted for extraction operations on private lands.

2.5.4 Extraction in Prime Agricultural Areas

2.5.4.1 In *prime agricultural areas*, on *prime agricultural land,* extraction of *mineral aggregate resources* is permitted as an interim use provided that the site will be rehabilitated back to an *agricultural condition*.

Complete rehabilitation to an *agricultural condition* is not required if:

a) outside of a *specialty crop area*, there is a substantial quantity of *mineral aggregate resources* below the water table warranting extraction, or the depth of planned extraction in a quarry makes restoration of pre-extraction agricultural capability unfeasible;
b) in a *specialty crop area*, there is a substantial quantity of *high quality mineral aggregate resources* below the water table warranting extraction, and the depth of planned extraction makes restoration of pre-extraction agricultural capability unfeasible;
c) other alternatives have been considered by the applicant and found unsuitable. The consideration of other alternatives shall include resources in areas of Canada Land Inventory Class 4 through 7 lands, resources on lands identified as *designated growth areas*, and resources on *prime agricultural lands* where rehabilitation is feasible. Where no other alternatives are found, *prime agricultural lands* shall be protected in this order of priority: *specialty crop areas*, Canada Land Inventory Class 1, 2 and 3 lands; and
d) agricultural rehabilitation in remaining areas is maximized.

2.5.5 Wayside Pits and Quarries, Portable Asphalt Plants and Portable Concrete Plants

2.5.5.1 *Wayside pits and quarries*, *portable asphalt plants* and *portable concrete plants* used on public authority contracts shall be permitted, without the need for an official plan

amendment, rezoning, or development permit under the *Planning Act* in all areas, except those areas of existing development or particular environmental sensitivity which have been determined to be incompatible with extraction and associated activities.

2.6 Cultural Heritage and Archaeology

2.6.1 *Significant built heritage resources* and *significant cultural heritage landscapes* shall be *conserved*.

2.6.2 *Development* and *site alteration* shall not be permitted on lands containing *archaeological resources* or *areas of archaeological potential* unless *significant archaeological resources* have been *conserved*.

2.6.3 Planning authorities shall not permit *development* and *site alteration* on *adjacent lands* to *protected heritage property* except where the proposed *development* and *site alteration* has been evaluated and it has been demonstrated that the *heritage attributes* of the *protected heritage property* will be *conserved*.

2.6.4 Planning authorities should consider and promote archaeological management plans and cultural plans in conserving cultural heritage and archaeological resources.

2.6.5 Planning authorities shall engage with Indigenous communities and consider their interests when identifying, protecting and managing cultural heritage and archaeological resources.

3.0 Protecting Public Health and Safety

Ontario's long-term prosperity, environmental health and social well-being depend on reducing the potential for public cost or risk to Ontario's residents from natural or human-made hazards.

Development shall be directed away from areas of natural or human-made hazards where there is an unacceptable risk to public health or safety or of property damage, and not create new or aggravate existing hazards.

Mitigating potential risk to public health or safety or of property damage from natural hazards, including the risks that may be associated with the impacts of a changing climate, will require the Province, planning authorities, and conservation authorities to work together.

Accordingly:

3.1 Natural Hazards

3.1.1 Development shall generally be directed, in accordance with guidance developed by the Province (as amended from time to time), to areas outside of:

a) *hazardous lands* adjacent to the shorelines of the *Great Lakes - St. Lawrence River System* and *large inland lakes* which are impacted by *flooding hazards*, *erosion hazards* and/or *dynamic beach hazards*;
b) *hazardous lands* adjacent to *river*, *stream and small inland lake systems* which are impacted by *flooding hazards* and/or *erosion hazards*; and
c) *hazardous sites.*

3.1.2 *Development* and *site alteration* shall not be permitted within:

a) the *dynamic beach hazard*;
b) *defined portions of the flooding hazard along connecting channels* (the St. Marys, St. Clair, Detroit, Niagara and St. Lawrence Rivers);
c) areas that would be rendered inaccessible to people and vehicles during times of *flooding hazards*, *erosion hazards* and/or *dynamic beach hazards*, unless it has been demonstrated that the site has safe access appropriate for the nature of the *development* and the natural hazard; and
d) a *floodway* regardless of whether the area of inundation contains high points of land not subject to flooding.

3.1.3 Planning authorities shall prepare for the *impacts of a changing climate* that may increase the risk associated with natural hazards.

3.1.4 Despite policy 3.1.2, *development* and *site alteration* may be permitted in certain areas associated with the *flooding hazard* along *river*, *stream and small inland lake systems*:

a) in those exceptional situations where a *Special Policy Area* has been approved. The designation of a *Special Policy Area*, and any change or modification to the official plan policies, land use designations or boundaries applying to *Special Policy Area* lands, must be approved by the Ministers of Municipal Affairs and Housing and Natural Resources and Forestry prior to the approval authority approving such changes or modifications; or
b) where the *development* is limited to uses which by their nature must locate within the *floodway*, including flood and/or erosion control works or minor additions or passive non-structural uses which do not affect flood flows.

3.1.5 *Development* shall not be permitted to locate in *hazardous lands* and *hazardous sites* where the use is:

a) an *institutional use* including hospitals, long-term care homes, retirement homes, pre-schools, school nurseries, day cares and schools;
b) an *essential emergency service* such as that provided by fire, police and ambulance stations and electrical substations; or
c) uses associated with the disposal, manufacture, treatment or storage of *hazardous substances*.

3.1.6 Where the *two zone concept* for *flood plains* is applied, *development* and *site alteration* may be permitted in the *flood fringe*, subject to appropriate floodproofing to the *flooding hazard* elevation or another *flooding hazard* standard approved by the Minister of Natural Resources and Forestry.

3.1.7 Further to policy 3.1.6, and except as prohibited in policies 3.1.2 and 3.1.5, *development* and *site alteration* may be permitted in those portions of *hazardous lands* and *hazardous sites* where the effects and risk to public safety are minor, could be mitigated in accordance with provincial standards, and where all of the following are demonstrated and achieved:

a) *development* and *site alteration* is carried out in accordance with *floodproofing standards*, *protection works standards*, and *access standards*;
b) vehicles and people have a way of safely entering and exiting the area during times of flooding, erosion and other emergencies;
c) new hazards are not created and existing hazards are not aggravated; and
d) no adverse environmental impacts will result.

3.1.8 *Development* shall generally be directed to areas outside of lands that are unsafe for *development* due to the presence of *hazardous forest types for wildland fire*.

Development may however be permitted in lands with *hazardous forest types for wildland fire* where the risk is mitigated in accordance with *wildland fire assessment and mitigation standards.*

3.2 Human-Made Hazards

3.2.1 Development on, abutting or adjacent to lands affected by *mine hazards*; *oil*, *gas and salt hazards*; or former *mineral mining operations*, *mineral aggregate operations* or *petroleum resource operations* may be permitted only if rehabilitation or other measures to address and mitigate known or suspected hazards are under way or have been completed.

3.2.2 Sites with contaminants in land or water shall be assessed and remediated as necessary prior to any activity on the site associated with the proposed use such that there will be no *adverse effects*.

3.2.3 Planning authorities should support, where feasible, on-site and local re-use of excess soil through planning and development approvals while protecting human health and the environment.

4.0 Implementation and Interpretation

4.1 This Provincial Policy Statement applies to all decisions in respect of the exercise of any authority that affects a planning matter made on or after May 1, 2020.

4.2 This Provincial Policy Statement shall be read in its entirety and all relevant policies are to be applied to each situation.

4.3 This Provincial Policy Statement shall be implemented in a manner that is consistent with the recognition and affirmation of existing Aboriginal and treaty rights in section 35 of the *Constitution Act*, *1982*.

4.4 This Provincial Policy Statement shall be implemented in a manner that is consistent with Ontario *Human Rights Code* and the *Canadian Charter of Rights and Freedoms*.

4.5 In implementing the Provincial Policy Statement, the Minister of Municipal Affairs and Housing may take into account other considerations when making decisions to support strong communities, a clean and healthy environment and the economic vitality of the Province.

4.6 The official plan is the most important vehicle for implementation of this Provincial Policy Statement. Comprehensive, integrated and long-term planning is best achieved through official plans.

Official plans shall identify provincial interests and set out appropriate land use designations and policies. To determine the significance of some natural heritage features and other resources, evaluation may be required.

In order to protect provincial interests, planning authorities shall keep their official plans up-to-date with this Provincial Policy Statement. The policies of this Provincial Policy Statement continue to apply after adoption and approval of an official plan.

4.7 In addition to land use approvals under the *Planning Act*, *infrastructure* may also require approval under other legislation and regulations. An environmental assessment process may be required for new *infrastructure* and modifications to existing *infrastructure* under applicable legislation.

Wherever possible and practical, approvals under the *Planning Act* and other legislation or regulations should be integrated provided the intent and requirements of both processes are met.

4.8 The Province, in consultation with municipalities, Indigenous communities, other public bodies and stakeholders shall identify performance indicators for measuring the effectiveness of some or all of the policies. The Province shall monitor their implementation, including reviewing performance indicators concurrent with any review of this Provincial Policy Statement.

4.9 Municipalities are encouraged to monitor and report on the implementation of the policies in their official plans, in accordance with any reporting requirements, data standards and any other guidelines that may be issued by the Minister.

5.0 Figure 1 Natural Heritage Protection Line




Figure 1. (Enlarged Inset) Natural Heritage Protection Line
Northern limit of Ecoregions* 5E, 6E and 7E for the purposes of policies under 2.1
Northern limit of Ecoregions* 6E and 7E for the purposes of policies under 2.1
Ecoregions* 6E and 7E for the purposes of policies under 2.1
Notes:
* "Crins, W.J. 2002. Ecozones, Ecoregions, and Ecodistricts of Ontario. Ontario Ministry of Natural Resources. Prepared for Ecological Land Classification Working Group."
0
50
100 Km
N
ALGOMA
SUDBURY
TEMISKAMING
NIPISSING
PARRY SOUND
MUSKOKA
HALIBURTON
PETERBOROUGH
NORTHUMBERLAND
DURHAM
YORK
PEEL
DUFFERIN
SIMCOE
GREY
BRUCE
HURON
WELLINGTON
MANITOULIN
RENFREW
LANARK
FRONTENAC
LENNOX AND ADDINGTON
HASTINGS
LEEDS AND GRENVILLE

6.0 Definitions

Access standards: means methods or procedures to ensure safe vehicular and pedestrian movement, and access for the maintenance and repair of protection works, during times of *flooding hazards*, *erosion hazards* and/or *other water-related hazards*.

Active transportation: means human-powered travel, including but not limited to, walking, cycling, inline skating and travel with the use of mobility aids, including motorized wheelchairs and other power-assisted devices moving at a comparable speed.

Adjacent lands: means

a) for the purposes of policy 1.6.8.3, those lands contiguous to existing or planned corridors and transportation facilities where *development* would have a negative impact on the corridor or facility. The extent of the *adjacent lands* may be recommended in guidelines developed by the Province or based on municipal approaches that achieve the same objectives;
b) for the purposes of policy 2.1.8, those lands contiguous to a specific *natural heritage feature or area* where it is likely that *development* or *site alteration* would have a *negative impact* on the feature or area. The extent of the *adjacent lands* may be recommended by the Province or based on municipal approaches which achieve the same objectives;
c) for the purposes of policies 2.4.2.2 and 2.5.2.5, those lands contiguous to lands on the surface of known *petroleum resources*, *mineral deposits*, or *deposits of mineral aggregate resources* where it is likely that *development* would constrain future access to the resources. The extent of the *adjacent lands* may be recommended by the Province; and
d) for the purposes of policy 2.6.3, those lands contiguous to a *protected heritage property* or as otherwise defined in the municipal official plan.

Adverse effects: as defined in the *Environmental Protection Act*, means one or more of:

a) impairment of the quality of the natural environment for any use that can be made of it;
b) injury or damage to property or plant or animal life;
c) harm or material discomfort to any person;
d) an adverse effect on the health of any person;
e) impairment of the safety of any person;
f) rendering any property or plant or animal life unfit for human use;
g) loss of enjoyment of normal use of property; and
h) interference with normal conduct of business.

Affordable: means

a) in the case of ownership housing, the least expensive of:
    1. housing for which the purchase price results in annual accommodation costs which do not exceed 30 percent of gross annual household income for *low and moderate income households*; or
    2. housing for which the purchase price is at least 10 percent below the average purchase price of a resale unit in the *regional market area*;
b) in the case of rental housing, the least expensive of:
    1. a unit for which the rent does not exceed 30 percent of gross annual household income for *low and moderate income households*; or
    2. a unit for which the rent is at or below the average market rent of a unit in the *regional market area*.

Agricultural condition: means

a) in regard to *specialty crop areas*, a condition in which substantially the same areas and same average soil capability for agriculture are restored, the same range and productivity of specialty crops common in the area can be achieved, and, where

applicable, the microclimate on which the site and surrounding area may be dependent for specialty crop production will be maintained or restored; and

b) in regard to *prime agricultural land* outside of *specialty crop areas*, a condition in which substantially the same areas and same average soil capability for agriculture are restored.

Agricultural System: A system comprised of a group of inter-connected elements that collectively create a viable, thriving agricultural sector. It has two components:

a) An agricultural land base comprised of *prime agricultural areas*, including *specialty crop areas*, and *rural lands* that together create a continuous productive land base for agriculture; and
b) An *agri-food network* which includes *infrastructure*, services, and assets important to the viability of the agri-food sector.

Agricultural uses: means the growing of crops, including nursery, biomass, and horticultural crops; raising of livestock; raising of other animals for food, fur or fibre, including poultry and fish; aquaculture; apiaries; agro-forestry; maple syrup production; and associated on-farm buildings and structures, including, but not limited to livestock facilities, manure storages, value-retaining facilities, and accommodation for full-time farm labour when the size and nature of the operation requires additional employment.

Agri-food network: Within the *agricultural system*, a network that includes elements important to the viability of the agri-food sector such as regional *infrastructure* and transportation networks; on-farm buildings and infrastructure; agricultural services, farm markets, distributors, and primary processing; and vibrant, agriculture-supportive communities.

Agri-tourism uses: means those farm-related tourism uses, including limited accommodation such as a bed and breakfast, that promote the enjoyment, education or activities related to the farm operation.

Agriculture-related uses: means those farm-related commercial and farm-related industrial uses that are directly related to farm operations in the area, support agriculture, benefit from being in close proximity to farm operations, and provide direct products and/or services to farm operations as a primary activity.

Airports: means all Ontario airports, including designated lands for future airports, with Noise Exposure Forecast (NEF)/Noise Exposure Projection (NEP) mapping.

Alternative energy system: means a system that uses sources of energy or energy conversion processes to produce power, heat and/or cooling that significantly reduces the amount of harmful emissions to the environment (air, earth and water) when compared to conventional energy systems.

Archaeological resources: includes artifacts, archaeological sites, marine archaeological sites, as defined under the *Ontario Heritage Act*. The identification and evaluation of such resources are based upon archaeological fieldwork undertaken in accordance with the *Ontario Heritage Act*.

Areas of archaeological potential: means areas with the likelihood to contain *archaeological resources*. Criteria to identify archaeological potential are established by the Province. The *Ontario Heritage Act* requires archaeological potential to be confirmed by a licensed archaeologist.

Areas of mineral potential: means areas favourable to the discovery of *mineral deposits* due to geology, the presence of known *mineral deposits* or other technical evidence.

Areas of natural and scientific interest (ANSI): means areas of land and water containing natural landscapes or features that have been identified as having life science or earth science values related to protection, scientific study or education.

Brownfield sites: means undeveloped or previously developed properties that may be

contaminated. They are usually, but not exclusively, former industrial or commercial properties that may be underutilized, derelict or vacant.

Built heritage resource: means a building, structure, monument, installation or any manufactured or constructed part or remnant that contributes to a property's cultural heritage value or interest as identified by a community, including an Indigenous community. *Built heritage resources* are located on property that may be designated under Parts IV or V of the *Ontario Heritage Act*, or that may be included on local, provincial, federal and/or international registers.

Coastal wetland: means

a) any *wetland* that is located on one of the Great Lakes or their connecting channels (Lake St. Clair, St. Marys, St. Clair, Detroit, Niagara and St. Lawrence Rivers); or
b) any other *wetland* that is on a tributary to any of the above-specified water bodies and lies, either wholly or in part, downstream of a line located 2 kilometres upstream of the 1:100 year floodline (plus wave run-up) of the large water body to which the tributary is connected.

Comprehensive rehabilitation: means rehabilitation of land from which *mineral aggregate resources* have been extracted that is coordinated and complementary, to the extent possible, with the rehabilitation of other sites in an area where there is a high concentration of *mineral aggregate operations*.

Comprehensive review: means

a) for the purposes of policies 1.1.3.8, 1.1.3.9 and 1.3.2.4, an official plan review which is initiated by a planning authority, or an official plan amendment which is initiated or adopted by a planning authority, which:
    1. is based on a review of population and employment projections and which reflect projections and allocations by upper-tier municipalities and *provincial plans*, where applicable; considers alternative directions for growth or development; and determines how best to accommodate the development while protecting provincial interests;
    2. utilizes opportunities to accommodate projected growth or development through *intensification* and *redevelopment*; and considers physical constraints to accommodating the proposed development within existing *settlement area* boundaries;
    3. is integrated with planning for *infrastructure* and *public service facilities*, and considers financial viability over the life cycle of these assets, which may be demonstrated through asset management planning;
    4. confirms sufficient water quality, quantity and assimilative capacity of receiving water are available to accommodate the proposed development;
    5. confirms that sewage and water services can be provided in accordance with policy 1.6.6; and
    6. considers cross-jurisdictional issues.
b) for the purposes of policy 1.1.6, means a review undertaken by a planning authority or comparable body which:
    1. addresses long-term population projections, *infrastructure* requirements and related matters;
    2. confirms that the lands to be developed do not comprise *specialty crop areas* in accordance with policy 2.3.2; and
    3. considers cross-jurisdictional issues.

In undertaking a *comprehensive review* the level of detail of the assessment should correspond with the complexity and scale of the settlement boundary or development proposal.

Conserved: means the identification, protection, management and use of *built heritage resources, cultural heritage landscapes* and *archaeological resources* in a manner that ensures their cultural heritage value or interest is retained. This may be achieved by the implementation of recommendations set out in a conservation plan, archaeological assessment, and/or heritage impact assessment that has been approved, accepted or adopted by the relevant planning authority and/or decision-

maker. Mitigative measures and/or alternative development approaches can be included in these plans and assessments.

Cultural heritage landscape: means a defined geographical area that may have been modified by human activity and is identified as having cultural heritage value or interest by a community, including an Indigenous community. The area may include features such as buildings, structures, spaces, views, archaeological sites or natural elements that are valued together for their interrelationship, meaning or association. *Cultural heritage landscapes* may be properties that have been determined to have cultural heritage value or interest under the *Ontario Heritage Act*, or have been included on federal and/or international registers, and/or protected through official plan, zoning by-law, or other land use planning mechanisms.

Defined portions of the flooding hazard along connecting channels: means those areas which are critical to the conveyance of the flows associated with the *one hundred year flood level* along the St. Marys, St. Clair, Detroit, Niagara and St. Lawrence Rivers, where *development* or *site alteration* will create *flooding hazards*, cause updrift and/or downdrift impacts and/or cause adverse environmental impacts.

Deposits of mineral aggregate resources: means an area of identified *mineral aggregate resources*, as delineated in Aggregate Resource Inventory Papers or comprehensive studies prepared using evaluation procedures established by the Province for surficial and bedrock resources, as amended from time to time, that has a sufficient quantity and quality to warrant present or future extraction.

Designated and available: means lands designated in the official plan for urban residential use. For municipalities where more detailed official plan policies (e.g. secondary plans) are required before development applications can be considered for approval, only lands that have commenced the more detailed planning process are considered to be *designated and available* for the purposes of this definition.

Designated growth areas: means lands within *settlement areas* designated in an official plan for growth over the long-term planning horizon provided in policy 1.1.2, but which have not yet been fully developed. *Designated growth areas* include lands which are *designated and available* for residential growth in accordance with policy 1.4.1(a), as well as lands required for employment and other uses.

Designated vulnerable area: means areas defined as vulnerable, in accordance with provincial standards, by virtue of their importance as a drinking water source.

Development: means the creation of a new lot, a change in land use, or the construction of buildings and structures requiring approval under the *Planning Act*, but does not include:

a) activities that create or maintain *infrastructure* authorized under an environmental assessment process;
b) works subject to the *Drainage Act*; or
c) for the purposes of policy 2.1.4(a), underground or surface mining of *minerals* or advanced exploration on mining lands in *significant areas of mineral potential* in Ecoregion 5E, where advanced exploration has the same meaning as under the *Mining Act*. Instead, those matters shall be subject to policy 2.1.5(a).

Dynamic beach hazard: means areas of inherently unstable accumulations of shoreline sediments along the *Great Lakes - St. Lawrence River System* and *large inland lakes*, as identified by provincial standards, as amended from time to time. The *dynamic beach hazard* limit consists of the *flooding hazard* limit plus a dynamic beach allowance.

Ecological function: means the natural processes, products or services that living and non-living environments provide or perform within or between species, ecosystems and landscapes. These may include biological, physical and socio-economic interactions.

Employment area: means those areas designated in an official plan for clusters of business and economic activities including, but not limited to, manufacturing, warehousing, offices, and associated retail and ancillary facilities.

Endangered species: means a species that is classified as "Endangered Species" on the Species at Risk in Ontario List, as updated and amended from time to time.

Erosion hazard: means the loss of land, due to human or natural processes, that poses a threat to life and property. The *erosion hazard* limit is determined using considerations that include the 100 year erosion rate (the average annual rate of recession extended over a one hundred year time span), an allowance for slope stability, and an erosion/erosion access allowance.

Essential emergency service: means services which would be impaired during an emergency as a result of flooding, the failure of floodproofing measures and/or protection works, and/or erosion.

Fish: means fish, which as defined in the *Fisheries Act*, includes fish, shellfish, crustaceans, and marine animals, at all stages of their life cycles.

Fish habitat: as defined in the *Fisheries Act*, means spawning grounds and any other areas, including nursery, rearing, food supply, and migration areas on which *fish* depend directly or indirectly in order to carry out their life processes.

Flood fringe: for *river*, *stream and small inland lake systems*, means the outer portion of the *flood plain* between the *floodway* and the *flooding hazard* limit. Depths and velocities of flooding are generally less severe in the flood fringe than those experienced in the *floodway*.

Flood plain: for *river*, *stream and small inland lake systems*, means the area, usually low lands adjoining a watercourse, which has been or may be subject to *flooding hazards*.

Flooding hazard: means the inundation, under the conditions specified below, of areas adjacent to a shoreline or a river or stream system and not ordinarily covered by water:

a) along the shorelines of the *Great Lakes - St. Lawrence River System* and *large inland lakes*, the *flooding hazard* limit is based on the *one hundred year flood level* plus an allowance for *wave uprush* and *other water-related hazards*;
b) along *river*, *stream and small inland lake systems*, the *flooding hazard* limit is the greater of:
    1. the flood resulting from the rainfall actually experienced during a major storm such as the Hurricane Hazel storm (1954) or the Timmins storm (1961), transposed over a specific watershed and combined with the local conditions, where evidence suggests that the storm event could have potentially occurred over watersheds in the general area;
    2. the *one hundred year flood*; and
    3. a flood which is greater than 1. or 2. which was actually experienced in a particular watershed or portion thereof as a result of ice jams and which has been approved as the standard for that specific area by the Minister of Natural Resources and Forestry;

    except where the use of the *one hundred year flood* or the actually experienced event has been approved by the Minister of Natural Resources and Forestry as the standard for a specific watershed (where the past history of flooding supports the lowering of the standard).

Floodproofing standard: means the combination of measures incorporated into the basic design and/or construction of buildings, structures, or properties to reduce or eliminate *flooding hazards*, *wave uprush* and *other water-related hazards* along the shorelines of the *Great Lakes - St. Lawrence River System* and *large inland lakes*, and *flooding hazards* along *river*, *stream and small inland lake systems*.

Floodway: for *river*, *stream and small inland lake systems*, means the portion of the *flood*

plain where *development* and *site alteration* would cause a danger to public health and safety or property damage.

Where the one zone concept is applied, the *floodway* is the entire contiguous *flood plain*.

Where the *two zone concept* is applied, the *floodway* is the contiguous inner portion of the *flood plain*, representing that area required for the safe passage of flood flow and/or that area where flood depths and/or velocities are considered to be such that they pose a potential threat to life and/or property damage. Where the *two zone concept* applies, the outer portion of the *flood plain* is called the *flood fringe*.

Freight-supportive: in regard to land use patterns, means transportation systems and facilities that facilitate the movement of goods. This includes policies or programs intended to support efficient freight movement through the planning, design and operation of land use and transportation systems. Approaches may be recommended in guidelines developed by the Province or based on municipal approaches that achieve the same objectives.

Great Lakes - St. Lawrence River System: means the major water system consisting of Lakes Superior, Huron, St. Clair, Erie and Ontario and their connecting channels, and the St. Lawrence River within the boundaries of the Province of Ontario.

Green infrastructure: means natural and human-made elements that provide ecological and hydrological functions and processes. *Green infrastructure* can include components such as natural heritage features and systems, parklands, stormwater management systems, street trees, urban forests, natural channels, permeable surfaces, and green roofs.

Ground water feature: means water-related features in the earth's subsurface, including recharge/discharge areas, water tables, aquifers and unsaturated zones that can be defined by surface and subsurface hydrogeologic investigations.

Habitat of endangered species and threatened species: means habitat within the meaning of Section 2 of the *Endangered Species Act, 2007*.

Hazardous forest types for wildland fire: means forest types assessed as being associated with the risk of high to extreme wildland fire using risk assessment tools established by the Ontario Ministry of Natural Resources and Forestry, as amended from time to time.

Hazardous lands: means property or lands that could be unsafe for development due to naturally occurring processes. Along the shorelines of the *Great Lakes - St. Lawrence River System*, this means the land, including that covered by water, between the international boundary, where applicable, and the furthest landward limit of the *flooding hazard*, *erosion hazard* or *dynamic beach hazard* limits. Along the shorelines of *large inland lakes*, this means the land, including that covered by water, between a defined offshore distance or depth and the furthest landward limit of the *flooding hazard*, *erosion hazard* or *dynamic beach hazard* limits. Along *river*, *stream and small inland lake systems*, this means the land, including that covered by water, to the furthest landward limit of the *flooding hazard* or *erosion hazard* limits.

Hazardous sites: means property or lands that could be unsafe for *development* and *site alteration* due to naturally occurring hazards. These may include unstable soils (sensitive marine clays [leda], organic soils) or unstable bedrock (karst topography).

Hazardous substances: means substances which, individually, or in combination with other substances, are normally considered to pose a danger to public health, safety and the environment. These substances generally include a wide array of materials that are toxic, ignitable, corrosive, reactive, radioactive or pathological.

Heritage attributes: means the principal features or elements that contribute to a *protected heritage property*'s cultural heritage value or interest, and may include the

property's built, constructed, or manufactured elements, as well as natural landforms, vegetation, water features, and its visual setting (e.g. significant views or vistas to or from a *protected heritage property*).

High quality: means primary and secondary sand and gravel resources and bedrock resources as defined in the Aggregate Resource Inventory Papers (ARIP).

Housing options: means a range of housing types such as, but not limited to single-detached, semi-detached, rowhouses, townhouses, stacked townhouses, multiplexes, additional residential units, tiny homes, multi-residential buildings. The term can also refer to a variety of housing arrangements and forms such as, but not limited to life lease housing, co-ownership housing, co-operative housing, community land trusts, land lease community homes, *affordable* housing, housing for people with *special needs*, and housing related to employment, institutional or educational uses.

Hydrologic function: means the functions of the hydrological cycle that include the occurrence, circulation, distribution and chemical and physical properties of water on the surface of the land, in the soil and underlying rocks, and in the atmosphere, and water's interaction with the environment including its relation to living things.

Impacts of a changing climate: means the present and future consequences from changes in weather patterns at local and regional levels including extreme weather events and increased climate variability.

Individual on-site sewage services: means sewage systems, as defined in O. Reg. 332/12 under the *Building Code Act*, *1992*, that are owned, operated and managed by the owner of the property upon which the system is located.

Individual on-site water services: means individual, autonomous water supply systems that are owned, operated and managed by the owner of the property upon which the system is located.

Infrastructure: means physical structures (facilities and corridors) that form the foundation for development. *Infrastructure* includes: sewage and water systems, septage treatment systems, stormwater management systems, waste management systems, electricity generation facilities, electricity transmission and distribution systems, communications/telecommunications, transit and transportation corridors and facilities, oil and gas pipelines and associated facilities.

Institutional use: for the purposes of policy 3.1.5, means land uses where there is a threat to the safe evacuation of vulnerable populations such as older persons, persons with disabilities, and those who are sick or young, during an emergency as a result of flooding, failure of floodproofing measures or protection works, or erosion.

Intensification: means the development of a property, site or area at a higher density than currently exists through:

a) *redevelopment*, including the reuse of *brownfield sites*;
b) the development of vacant and/or underutilized lots within previously developed areas;
c) infill development; and
d) the expansion or conversion of existing buildings.

Large inland lakes: means those waterbodies having a surface area of equal to or greater than 100 square kilometres where there is not a measurable or predictable response to a single runoff event.

Legal or technical reasons: means severances for purposes such as easements, corrections of deeds, quit claims, and minor boundary adjustments, which do not result in the creation of a new lot.

Low and moderate income households: means

a) in the case of ownership housing, households with incomes in the lowest 60 percent of the income distribution for the *regional market area*; or

b) in the case of rental housing, households with incomes in the lowest 60 percent of the income distribution for renter households for the *regional market area*.

Major facilities: means facilities which may require separation from *sensitive land uses*, including but not limited to airports, manufacturing uses, transportation infrastructure and corridors, *rail facilities*, *marine facilities*, sewage treatment facilities, *waste management systems*, oil and gas pipelines, industries, energy generation facilities and transmission systems, and resource extraction activities.

Major goods movement facilities and corridors: means transportation facilities and corridors associated with the inter- and intra-provincial movement of goods. Examples include: inter-modal facilities, ports, *airports, rail facilities*, truck terminals, freight corridors, freight facilities, and haul routes and primary transportation corridors used for the movement of goods. Approaches that are *freight-supportive* may be recommended in guidelines developed by the Province or based on municipal approaches that achieve the same objectives.

Marine facilities: means ferries, harbours, ports, ferry terminals, canals and associated uses, including designated lands for future *marine facilities*.

Mine hazard: means any feature of a mine as defined under the *Mining Act*, or any related disturbance of the ground that has not been rehabilitated.

Minerals: means metallic minerals and non-metallic minerals as herein defined, but does not include *mineral aggregate resources* or *petroleum resources*.

Metallic minerals means those minerals from which metals (e.g. copper, nickel, gold) are derived.

Non-metallic minerals means those minerals that are of value for intrinsic properties of the minerals themselves and not as a source of metal. They are generally synonymous with industrial minerals (e.g. asbestos, graphite, kyanite, mica, nepheline syenite, salt, talc, and wollastonite).

Mineral aggregate operation: means

a) lands under license or permit, other than for *wayside pits and quarries*, issued in accordance with the *Aggregate Resources Act*;
b) for lands not designated under the *Aggregate Resources Act*, established pits and quarries that are not in contravention of municipal zoning by-laws and including adjacent land under agreement with or owned by the operator, to permit continuation of the operation; and
c) associated facilities used in extraction, transport, beneficiation, processing or recycling of *mineral aggregate resources* and derived products such as asphalt and concrete, or the production of secondary related products.

Mineral aggregate resources: means gravel, sand, clay, earth, shale, stone, limestone, dolostone, sandstone, marble, granite, rock or other material prescribed under the *Aggregate Resources Act* suitable for construction, industrial, manufacturing and maintenance purposes but does not include metallic ores, asbestos, graphite, kyanite, mica, nepheline syenite, salt, talc, wollastonite, mine tailings or other material prescribed under the *Mining Act*.

Mineral aggregate resource conservation: means

a) the recovery and recycling of manufactured materials derived from mineral aggregates (e.g. glass, porcelain, brick, concrete, asphalt, slag, etc.), for re-use in construction, manufacturing, industrial or maintenance projects as a substitute for new mineral aggregates; and
b) the wise use of mineral aggregates including utilization or extraction of on-site *mineral aggregate resources* prior to development occurring.

Mineral deposits: means areas of identified *minerals* that have sufficient quantity and quality based on specific geological evidence to warrant present or future extraction.

Mineral mining operation: means mining operations and associated facilities, or, past producing mines with remaining mineral development potential that have not been permanently rehabilitated to another use.

Minimum distance separation formulae: means formulae and guidelines developed by the Province, as amended from time to time, to separate uses so as to reduce incompatibility concerns about odour from livestock facilities.

Multimodal transportation system: means a transportation system which may include several forms of transportation such as automobiles, walking, trucks, cycling, buses, rapid transit, rail (such as commuter and freight), air and marine.

Municipal sewage services: means a sewage works within the meaning of section 1 of the *Ontario Water Resources Act* that is owned or operated by a municipality, including centralized and decentralized systems.

Municipal water services: means a municipal drinking-water system within the meaning of section 2 of the *Safe Drinking Water Act*, *2002*, including centralized and decentralized systems.

Natural heritage features and areas: means features and areas, including *significant wetlands*, *significant coastal wetlands*, other *coastal wetlands* in Ecoregions 5E, 6E and 7E, *fish habitat*, *significant woodlands* and *significant valleylands* in Ecoregions 6E and 7E (excluding islands in Lake Huron and the St. Marys River), *habitat of endangered species and threatened species*, *significant wildlife habitat*, and *significant areas of natural and scientific interest*, which are important for their environmental and social values as a legacy of the natural landscapes of an area.

Natural heritage system: means a system made up of *natural heritage features and areas*, and linkages intended to provide connectivity (at the regional or site level) and support natural processes which are necessary to maintain biological and geological diversity, natural functions, viable populations of indigenous species, and ecosystems. These systems can include *natural heritage features and areas*, federal and provincial parks and conservation reserves, other natural heritage features, lands that have been restored or have the potential to be restored to a natural state, areas that support hydrologic functions, and working landscapes that enable ecological functions to continue. The Province has a recommended approach for identifying *natural heritage systems*, but municipal approaches that achieve or exceed the same objective may also be used.

Negative impacts: means

a) in regard to policy 1.6.6.4 and 1.6.6.5, potential risks to human health and safety and degradation to the *quality and quantity of water*, *sensitive surface water features* and *sensitive ground water features*, and their related *hydrologic functions*, due to single, multiple or successive *development*. *Negative impacts* should be assessed through environmental studies including hydrogeological or water quality impact assessments, in accordance with provincial standards;
b) in regard to policy 2.2, degradation to the *quality and quantity of water*, *sensitive surface water features* and *sensitive ground water features*, and their related *hydrologic functions*, due to single, multiple or successive *development* or *site alteration* activities;
c) in regard to *fish habitat*, any permanent alteration to, or destruction of *fish habitat*, except where, in conjunction with the appropriate authorities, it has been authorized under the *Fisheries Act*; and
d) in regard to other *natural heritage features and areas*, degradation that threatens the health and integrity of the natural features or *ecological functions* for which an area is identified due to single, multiple or successive *development* or *site alteration* activities.

Normal farm practices: means a practice, as defined in the *Farming and Food Production Protection Act*, *1998*, that is conducted in a manner consistent with proper and acceptable customs and standards as established and followed by similar agricultural operations under similar circumstances; or makes use of innovative technology in a manner consistent with proper advanced farm management practices. Normal farm practices shall be consistent with the *Nutrient Management Act*, *2002* and regulations made under that Act.

Oil, gas and salt hazards: means any feature of a well or work as defined under the *Oil*, *Gas and Salt Resources Act*, or any related disturbance of the ground that has not been rehabilitated.

On-farm diversified uses: means uses that are secondary to the principal agricultural use of the property, and are limited in area. *On-farm diversified uses* include, but are not limited to, home occupations, home industries, *agri-tourism uses*, and uses that produce value-added agricultural products. Ground-mounted solar facilities are permitted in *prime agricultural areas,* including *specialty crop areas,* only as *on-farm diversified uses.*

One hundred year flood: for *river, stream and small inland lake systems*, means that flood, based on an analysis of precipitation, snow melt, or a combination thereof, having a return period of 100 years on average, or having a 1% chance of occurring or being exceeded in any given year.

One hundred year flood level: means

a) for the shorelines of the Great Lakes, the peak instantaneous stillwater level, resulting from combinations of mean monthly lake levels and wind setups, which has a 1% chance of being equalled or exceeded in any given year;
b) in the connecting channels (St. Marys, St. Clair, Detroit, Niagara and St. Lawrence Rivers), the peak instantaneous stillwater level which has a 1% chance of being equalled or exceeded in any given year; and
c) for large inland lakes, lake levels and wind setups that have a 1% chance of being equalled or exceeded in any given year, except that, where sufficient water level records do not exist, the one hundred year flood level is based on the highest known water level and wind setups.

Other water-related hazards: means water-associated phenomena other than *flooding hazards* and *wave uprush* which act on shorelines. This includes, but is not limited to ship-generated waves, ice piling and ice jamming.

Partial services: means

a) *municipal sewage services* or *private communal sewage services* combined with *individual on-site water services*; or
b) *municipal water services* or *private communal water services* combined with *individual on-site sewage services*.

Petroleum resource operations: means oil, gas and salt wells and associated facilities and other drilling operations, oil field fluid disposal wells and associated facilities, and wells and facilities for the underground storage of natural gas and other hydrocarbons.

Petroleum resources: means oil, gas, and salt (extracted by solution mining method) and formation water resources which have been identified through exploration and verified by preliminary drilling or other forms of investigation. This may include sites of former operations where resources are still present or former sites that may be converted to underground storage for natural gas or other hydrocarbons.

Planned corridors: means corridors or future corridors which are required to meet projected needs, and are identified through *provincial plans*, preferred alignment(s) determined through the *Environmental Assessment Act* process, or identified through planning studies where the Ontario Ministry of Transportation, Metrolinx, Ontario Ministry of Energy, Northern Development and Mines or Independent Electricity System Operator (IESO) or any successor to those ministries or entities is actively pursuing the identification of a corridor.

Approaches for the protection of *planned corridors* may be recommended in guidelines developed by the Province.

Portable asphalt plant: means a facility
a) with equipment designed to heat and dry aggregate and to mix aggregate with bituminous asphalt to produce asphalt paving material, and includes stockpiling and storage of bulk materials used in the process; and
b) which is not of permanent construction, but which is to be dismantled at the completion of the construction project.

Portable concrete plant: means a building or structure
a) with equipment designed to mix cementing materials, aggregate, water and admixtures to produce concrete, and includes stockpiling and storage of bulk materials used in the process; and
b) which is not of permanent construction, but which is designed to be dismantled at the completion of the construction project.

Prime agricultural area: means areas where *prime agricultural lands* predominate. This includes areas of *prime agricultural lands* and associated Canada Land Inventory Class 4 through 7 lands, and additional areas where there is a local concentration of farms which exhibit characteristics of ongoing agriculture. *Prime agricultural areas* may be identified by the Ontario Ministry of Agriculture and Food using guidelines developed by the Province as amended from time to time. A *prime agricultural area* may also be identified through an alternative agricultural land evaluation system approved by the Province.

Prime agricultural land: means *specialty crop areas* and/or Canada Land Inventory Class 1, 2, and 3 lands, as amended from time to time, in this order of priority for protection.

Private communal sewage services: means a sewage works within the meaning of section 1 of the *Ontario Water Resources Act* that serves six or more lots or private residences and is not owned by a municipality.

Private communal water services: means a non-municipal drinking-water system within the meaning of section 2 of the *Safe Drinking Water Act*, *2002* that serves six or more lots or private residences.

Protected heritage property: means property designated under Parts IV, V or VI of the *Ontario Heritage Act*; property subject to a heritage conservation easement under Parts II or IV of the *Ontario Heritage Act*; property identified by the Province and prescribed public bodies as provincial heritage property under the Standards and Guidelines for Conservation of Provincial Heritage Properties; property protected under federal legislation, and UNESCO World Heritage Sites.

Protection works standards: means the combination of non-structural or structural works and allowances for slope stability and flooding/erosion to reduce the damage caused by *flooding hazards*, *erosion hazards* and *other water-related hazards*, and to allow access for their maintenance and repair.

Provincial and federal requirements: means
a) in regard to policy 2.1.6, legislation and policies administered by the federal or provincial governments for the purpose of fisheries protection (including *fish* and *fish habitat*), and related, scientifically established standards such as water quality criteria for protecting lake trout populations; and
b) in regard to policy 2.1.7, legislation and policies administered by the provincial government or federal government, where applicable, for the purpose of protecting species at risk and their habitat.

Provincial plan: means a provincial plan within the meaning of section 1 of the *Planning Act*.

Public service facilities: means land, buildings and structures for the provision of programs and services provided or subsidized by a government or other body, such as social assistance, recreation, police and fire protection, health and educational programs, long-term care services, and cultural services.

Public service facilities do not include *infrastructure*.

Quality and quantity of water: is measured by indicators associated with hydrologic function such as minimum base flow, depth to water table, aquifer pressure, oxygen levels, suspended solids, temperature, bacteria, nutrients and hazardous contaminants, and hydrologic regime.

Rail facilities: means rail corridors, rail sidings, train stations, inter-modal facilities, rail yards and associated uses, including designated lands for future *rail facilities*.

Recreation: means leisure time activity undertaken in built or natural settings for purposes of physical activity, health benefits, sport participation and skill development, personal enjoyment, positive social interaction and the achievement of human potential.

Redevelopment: means the creation of new units, uses or lots on previously developed land in existing communities, including *brownfield sites*.

Regional market area: refers to an area that has a high degree of social and economic interaction. The upper or single-tier municipality, or planning area, will normally serve as the *regional market area*. However, where a *regional market area* extends significantly beyond these boundaries, then the *regional market area* may be based on the larger market area. Where *regional market areas* are very large and sparsely populated, a smaller area, if defined in an official plan, may be utilized.

Renewable energy source: means an energy source that is renewed by natural processes and includes wind, water, biomass, biogas, biofuel, solar energy, geothermal energy and tidal forces.

Renewable energy system: means a system that generates electricity, heat and/or cooling from a *renewable energy source.*

Reserve sewage system capacity: means design or planned capacity in a centralized waste water treatment facility which is not yet committed to existing or approved development. For the purposes of policy 1.6.6.6, reserve capacity for *private communal sewage services* and *individual on-site sewage services* is considered sufficient if the hauled sewage from the development can be treated and land-applied on agricultural land under the *Nutrient Management Act*, or disposed of at sites approved under the *Environmental Protection Act* or the *Ontario Water Resources Act*, but not by land-applying untreated, hauled sewage.

Reserve water system capacity: means design or planned capacity in a centralized water treatment facility which is not yet committed to existing or approved development.

Residence surplus to a farming operation: means an existing habitable farm residence that is rendered surplus as a result of farm consolidation (the acquisition of additional farm parcels to be operated as one farm operation).

Residential intensification: means intensification of a property, site or area which results in a net increase in residential units or accommodation and includes:

a) redevelopment, including the redevelopment of *brownfield sites*;
b) the development of vacant or underutilized lots within previously developed areas;
c) infill development;
d) development and introduction of new *housing options* within previously developed areas;
e) the conversion or expansion of existing industrial, commercial and institutional buildings for residential use; and
f) the conversion or expansion of existing residential buildings to create new residential units or accommodation, including accessory apartments, additional residential units, rooming houses, and other *housing options*.

River, stream and small inland lake systems: means all watercourses, rivers, streams, and

small inland lakes or waterbodies that have a measurable or predictable response to a single runoff event.

Rural areas: means a system of lands within municipalities that may include rural *settlement areas*, *rural lands*, *prime agricultural areas*, natural heritage features and areas, and resource areas.

Rural lands: means lands which are located outside *settlement areas* and which are outside *prime agricultural areas*.

Sensitive: in regard to *surface water features* and *ground water features*, means areas that are particularly susceptible to impacts from activities or events including, but not limited to, water withdrawals, and additions of pollutants.

Sensitive land uses: means buildings, amenity areas, or outdoor spaces where routine or normal activities occurring at reasonably expected times would experience one or more *adverse effects* from contaminant discharges generated by a nearby *major facility*. *Sensitive land uses* may be a part of the natural or built environment. Examples may include, but are not limited to: residences, day care centres, and educational and health facilities.

Settlement areas: means urban areas and rural settlement areas within municipalities (such as cities, towns, villages and hamlets) that are:

a) built-up areas where development is concentrated and which have a mix of land uses; and
b) lands which have been designated in an official plan for development over the long-term planning horizon provided for in policy 1.1.2. In cases where land in *designated growth areas* is not available, the *settlement area* may be no larger than the area where development is concentrated.

Sewage and water services: includes *municipal sewage services* and *municipal water services*, *private communal sewage services* and *private communal water services*, *individual on-site sewage services* and *individual on-site water services*, and *partial services*.

Significant: means

a) in regard to *wetlands*, *coastal wetlands* and *areas of natural and scientific interest*, an area identified as provincially significant by the Ontario Ministry of Natural Resources and Forestry using evaluation procedures established by the Province, as amended from time to time;
b) in regard to *woodlands*, an area which is ecologically important in terms of features such as species composition, age of trees and stand history; functionally important due to its contribution to the broader landscape because of its location, size or due to the amount of forest cover in the planning area; or economically important due to site quality, species composition, or past management history. These are to be identified using criteria established by the Ontario Ministry of Natural Resources and Forestry;
c) in regard to other features and areas in policy 2.1, ecologically important in terms of features, functions, representation or amount, and contributing to the quality and diversity of an identifiable geographic area or *natural heritage system*;
d) in regard to *mineral* potential, an area identified as provincially significant through evaluation procedures developed by the Province, as amended from time to time, such as the Provincially Significant Mineral Potential Index; and
e) in regard to cultural heritage and archaeology, resources that have been determined to have cultural heritage value or interest. Processes and criteria for determining cultural heritage value or interest are established by the Province under the authority of the *Ontario Heritage Act*.

Criteria for determining significance for the resources identified in sections (c)-(d) are recommended by the Province, but municipal approaches that achieve or exceed the same objective may also be used.

While some significant resources may already be identified and inventoried by official sources,

the significance of others can only be determined after evaluation.

Site alteration: means activities, such as grading, excavation and the placement of fill that would change the landform and natural vegetative characteristics of a site.

For the purposes of policy 2.1.4(a), *site alteration* does not include underground or surface mining of *minerals* or advanced exploration on mining lands in *significant areas of mineral potential* in Ecoregion 5E, where advanced exploration has the same meaning as in the *Mining Act*. Instead, those matters shall be subject to policy 2.1.5(a).

Special needs: means any housing, including dedicated facilities, in whole or in part, that is used by people who have specific needs beyond economic needs, including but not limited to, needs such as mobility requirements or support functions required for daily living. Examples of *special needs* housing may include, but are not limited to long-term care homes, adaptable and accessible housing, and housing for persons with disabilities such as physical, sensory or mental health disabilities, and housing for older persons.

Special Policy Area: means an area within a community that has historically existed in the *flood plain* and where site-specific policies, approved by both the Ministers of Natural Resources and Forestry and Municipal Affairs and Housing, are intended to provide for the continued viability of existing uses (which are generally on a small scale) and address the significant social and economic hardships to the community that would result from strict adherence to provincial policies concerning *development*. The criteria and procedures for approval are established by the Province.

A *Special Policy Area* is not intended to allow for new or intensified *development* and *site alteration*, if a community has feasible opportunities for *development* outside the *flood plain*.

Specialty crop area: means areas designated using guidelines developed by the Province, as amended from time to time. In these areas, specialty crops are predominantly grown such as tender fruits (peaches, cherries, plums), grapes, other fruit crops, vegetable crops, greenhouse crops, and crops from agriculturally developed organic soil, usually resulting from:

a) soils that have suitability to produce specialty crops, or lands that are subject to special climatic conditions, or a combination of both;
b) farmers skilled in the production of specialty crops; and
c) a long-term investment of capital in areas such as crops, drainage, infrastructure and related facilities and services to produce, store, or process specialty crops.

Surface water feature: means water-related features on the earth's surface, including headwaters, rivers, stream channels, inland lakes, seepage areas, recharge/discharge areas, springs, wetlands, and associated riparian lands that can be defined by their soil moisture, soil type, vegetation or topographic characteristics.

Threatened species: means a species that is classified as "Threatened Species" on the Species at Risk in Ontario List, as updated and amended from time to time.

Transit-supportive: in regard to land use patterns, means development that makes transit viable, optimizes investments in transit infrastructure, and improves the quality of the experience of using transit. It often refers to compact, mixed-use development that has a high level of employment and residential densities, including air rights development, in proximity to transit stations, corridors and associated elements within the *transportation system*. Approaches may be recommended in guidelines developed by the Province or based on municipal approaches that achieve the same objectives.

Transportation demand management: means a set of strategies that result in more efficient use of the *transportation system* by influencing travel behaviour by mode, time of day,

frequency, trip length, regulation, route, or cost.

Transportation system: means a system consisting of facilities, corridors and rights-of-way for the movement of people and goods, and associated transportation facilities including transit stops and stations, sidewalks, cycle lanes, bus lanes, high occupancy vehicle lanes, *rail facilities*, parking facilities, park'n'ride lots, service centres, rest stops, vehicle inspection stations, inter-modal facilities, harbours, *airports*, *marine facilities*, ferries, canals and associated facilities such as storage and maintenance.

Two zone concept: means an approach to *flood plain* management where the *flood plain* is differentiated in two parts: the *floodway* and the *flood fringe*.

Valleylands: means a natural area that occurs in a valley or other landform depression that has water flowing through or standing for some period of the year.

Vulnerable: means surface and/or ground water that can be easily changed or impacted.

Waste management system: means sites and facilities to accommodate solid waste from one or more municipalities and includes recycling facilities, transfer stations, processing sites and disposal sites.

Watershed: means an area that is drained by a river and its tributaries.

Wave uprush: means the rush of water up onto a shoreline or structure following the breaking of a wave; the limit of wave uprush is the point of furthest landward rush of water onto the shoreline.

Wayside pits and quarries: means a temporary pit or quarry opened and used by or for a public authority solely for the purpose of a particular project or contract of road construction and not located on the road right-of-way.

Wetlands: means lands that are seasonally or permanently covered by shallow water, as well as lands where the water table is close to or at the surface. In either case the presence of abundant water has caused the formation of hydric soils and has favoured the dominance of either hydrophytic plants or water tolerant plants. The four major types of wetlands are swamps, marshes, bogs and fens.

Periodically soaked or wet lands being used for agricultural purposes which no longer exhibit wetland characteristics are not considered to be wetlands for the purposes of this definition.

Wildland fire assessment and mitigation standards: means the combination of risk assessment tools and environmentally appropriate mitigation measures identified by the Ontario Ministry of Natural Resources and Forestry to be incorporated into the design, construction and/or modification of buildings, structures, properties and/or communities to reduce the risk to public safety, infrastructure and property from wildland fire.

Wildlife habitat: means areas where plants, animals and other organisms live, and find adequate amounts of food, water, shelter and space needed to sustain their populations. Specific wildlife habitats of concern may include areas where species concentrate at a vulnerable point in their annual or life cycle; and areas which are important to migratory or non-migratory species.

Woodlands: means treed areas that provide environmental and economic benefits to both the private landowner and the general public, such as erosion prevention, hydrological and nutrient cycling, provision of clean air and the long-term storage of carbon, provision of wildlife habitat, outdoor recreational opportunities, and the sustainable harvest of a wide range of woodland products. *Woodlands* include treed areas, woodlots or forested areas and vary in their level of significance at the local, regional and provincial levels. *Woodlands* may be delineated according to the *Forestry Act* definition or the Province's Ecological Land Classification system definition for "forest".

Ministry of Municipal Affairs and Housing

© Queen's Printer for Ontario, 2020

ISBN 978-1-4868-4229-2 (Print)
ISBN 978-1-4868-4230-8 (HTML)
ISBN 978-1-4868-4231-5 (PDF)

370/02/20

Disponible en français

Minutes of Special Committee of the Whole
May 19, 2020

Time: 6:00 pm
Location: Council Chambers and Electronic Participation

Meeting # 11

Present in Council Chambers: Mayor Ron Vandewal, Neil Carbone - Chief Administrative Officer, Mark Segsworth - Director of Public Services, Louise Fragnito - Director of Corporate Services & Treasurer, Angela Maddocks - Clerk

Present via teleconference: Pat Barr, Ray Leonard, Doug Morey, Alan Revill, Norm Roberts, Randy Ruttan, Ron Sleeth, Ross Sutherland

1. Call to Order

a) Mayor Vandewal called the meeting to order.

The Clerk conducted a roll call of Council members and staff.

2. Declaration of pecuniary interest and the general nature thereof

a) There were no declarations.

3. Scheduled Closed Session

a) Resolution

Moved by Councillor Revill
Seconded by Councillor Sleeth
That Council move into closed session to discuss garbage and recycling contracts as permitted by Section 239. 2 (k) to discuss a position, plan, procedure, criteria or instruction to be applied to any negotiations carried on or to be carried on by or on behalf of the municipality or local board.

Carried.

b) Garbage and Recycling Contracts

4. Adjournment

a) The meeting was adjourned at 6:30 pm.

Minutes of Council
May, 19, 2020

Time: 7:00 PM
Location: Electronic Participation

Meeting #12

Present in Council Chambers: Mayor Ron Vandewal

Present via teleconference: Pat Barr, Ray Leonard, Doug Morey, Alan Revill, Norm Roberts, Randy Ruttan, Ron Sleeth, Ross Sutherland

Staff Present in Council Chambers: Neil Carbone - Chief Administrative Officer, Angela Maddocks - Clerk, Louise Fragnito - Director of Corporate Services & Treasurer, Mark Segsworth - Director of Public Services

Staff Present via teleconference Claire Dodds - Director of Development Services, Darcy Knott - Director of Fire and Emergency Services

1. Call to Order

a) **Roll Call - Council Members and Staff**

The Clerk conducted the roll call.

b) **Resolution**

Resolution No. 2020-12-01
Moved by Councillor Barr
Seconded by Deputy Mayor Sutherland
That the Council meeting of May 19, 2020 be called to order at 7:00 p.m.
Carried

2. Declaration of pecuniary interest and the general nature thereof

a) There were no declarations.

3. Approval of Agenda

a) **Resolution**

Resolution No. 2020-12-02
Moved by Councillor Ruttan
Seconded by Councillor Revill
That the agenda for the May 19, 2020 Council meeting be adopted as presented.
Carried

4. Scheduled Closed Session - not applicable

5. ***Recess*** - not applicable

6. Delegations - not applicable

7. Public Meeting - not applicable

8. Approval of Minutes

a) **April 14, 2020 Council Meeting**

Resolution No. 2020-12-03
Moved by Councillor Ruttan
Seconded by Councillor Revill
That the minutes of the April 14, 2020 Council meeting be approved.

Carried

b) **May 5, 2020 Council Meeting**

Resolution No. 2020-12-04
Moved by Councillor Sleeth
Seconded by Councillor Morey
That the minutes of the May 5, 2020 Council meeting be approved.

Carried

9. Business Arising from the Minutes

a) **Devil Lake Causeway - Pedestrian Safety**

See By-law 2020-25

10. Reports Requiring Action

a) **Support for WTC's Application to CRTC Broadband Fund**

Resolution No. 2020-12-05
Moved by Deputy Mayor Sutherland
Seconded by Councillor Barr
That the Council of the Township of South Frontenac strongly supports WTC Communication’s application to the CRTC Broadband Fund for the expansion of high-speed internet services to our community.

Carried

b) **Strategic Plan Action Items & Key Performance Indicators**

Resolution No. 2020-12-06
Moved by Councillor Roberts
Seconded by Councillor Leonard
That Council approves the list of 2020-2021 Strategic Plan Action Items requiring Council endorsement, attached to the CAO's report dated May 19, 2020 as Schedule A; and,

That Council approves the list of 2020-2021 Strategic Plan activity-based key performance indicators attached to the CAO's report dated May 19, 2020 as Schedule B; and,

That Council approves the list of 2020-2021 Strategic Plan Broad Economic and Community Indicators attached to the CAO's report dated May 19, 2020 as Schedule C.

Carried

c) **Flag Protocol Policy (Amendment)**

Resolution No. 2020-12-07
Moved by Councillor Morey
Seconded by Councillor Sleeth
That Council approve the amendment to the Flag Protocol Policy attached to the Clerks report dated May 19, 2020, as amended.

Carried

d) **Climate Change Adaptation**

Resolution No. 2020-12-08
Moved by Councillor Revill
Seconded by Councillor Ruttan
That Council approve a limited scope approach to the creation of a climate Change Adaptation and Mitigation Strategy as outlined in Option 2 under the Analysis/Discussion section of the Chief Administrative Officer's report dated May 19, 2020.

Carried

e) **Appointment of Acting Deputy Treasurer**

See By-law 2020-26.

f) **Sydenham Water Financial Plan 2020-2026**

Resolution No. 2020-12-09
Moved by Deputy Mayor Sutherland
Seconded by Councillor Ruttan
That Council support the 2020-2026 Financial Plan for Sydenham Water as attached to the report from the Director of Corporate Services and Treasurer dated May 19, 2020.

Carried

g) **Delegation of Consent Authority**

See By-law 2020-27

h) **Chief Administrative Officer - Performance Appraisal Framework**

The Clerk opened the floor for nominations to appoint two Councillors names to be inserted into the resolution.

Councillor Morey nominated Councillor Leonard and Councillor Barr seconded the nomination. Councillor Leonard accepted the nomination.

Councillor Roberts nominated Councillor Revill and Councillor Leonard seconded the nomination. Councillor Revill accepted the nomination.

Mayor Vandewal was not in support of the motion as presented therefore a recorded vote was conducted. Councillors Barr, Morey, Ruttan and Deputy Mayor Sutherland voted in favour of the motion with the remainder of Council voting against, therefore the motion was defeated.

Resolution No. 2020-12-10
Moved by Councillor Leonard
Seconded by Councillor Roberts
THAT Council adopt an approach to the CAO’s performance appraisal based upon the CAO Performance Evaluation Tool Kit created by the Canadian Association of Municipal Administrators (CAMA), attached as schedule A to the CAO's Report dated May 19, 2020; and,

THAT Council approve the modified CAO appraisal framework and timeline for 2020 as outlined in the CAO's Report dated May 19, 2020; and

THAT Council adopt the list of core competencies attached as Schedule B to the CAO's report dated May 19, 2020; and,

THAT Council adopt the CAO Performance Appraisal Template attached as Schedule C to the CAO's Report dated May 19, 2020,

THAT Council appoints Mayor Vandewal and Councillors Leonard and Revill to a CAO performance review committee for 2020.

Defeated

i) **Proclamation for Youth Month**

Resolution No. 2020-12-11
Moved by Councillor Revill
Seconded by Councillor Ruttan
That Council proclaim May as being Youth Month in South Frontenac.

Carried

j) **PW-RFQ1- 2020 Request for Contracted Equipment, Materials & Trades**

Resolution No. 2020-12-12
Moved by Councillor Revill
Seconded by Councillor Ruttan
That Council authorizes the purchase of materials and culverts, the contracting of trades and the rental of equipment all within set budgets as per the attachments to the 2018 Request for Quote, Equipment and Materials report from the Director of Public Services dated May 19, 2020.

Carried

11. Committee Meeting Minutes - not applicable

12. By-laws

a) **By-law 2020-25 - Devil Lake Causeway - Pedestrian Traffic**

Resolution No. 2020-12-13
Moved by Councillor Roberts
Seconded by Councillor Leonard
That the following by-laws be given first and second reading:

- By-law 2020-25
- By-law 2020-26
- By-law 2020-27

Carried

Resolution No. 2020-12-14
Moved by Councillor Revill
Seconded by Councillor Sleeth
That By-law 2020-25, being a by-law to prohibit pedestrians from standing and/or loitering at all times along Perth Road at the Devil Lake Causeway, be given third reading, signed and sealed.

Carried

b) **By-law 2020-26 - Appointment of Acting Deputy Treasurer**

Resolution No. 2020-12-15
Moved by Councillor Morey
Seconded by Councillor Ruttan
That By-law 2020-26, being a by-law to provide for the appointment of a Deputy Treasurer, be given third reading, signed and sealed.

Carried

c) **By-law 2020-27 - Delegation of Authority for Undisputed Consents**

Resolution No. 2020-12-16
Moved by Deputy Mayor Sutherland
Seconded by Councillor Barr
That By-law 2020-27, being a by-law to to delegate authority to grant consent and validation certificates to staff, be given third reading, signed and sealed.

Carried

13. Reports for Information

a) **County Extension of Draft Plan Approval for Plans of Subdivision and Condominiums**

b) **Planning Department - 1st Quarter Statistics**

c) **2019 Draft Financials**

d) **Tender PW-2020-22 - Tag Along Float Trailer**

e) **Tender No. PS-2020-07, 2020 Crack Sealing Program**

14. Information Items - not applicable

15. Notice of Motions - not applicable

16. Announcements/Statements by Councillors

a) As a follow up to Agenda Item 10 a) regarding broadband, Deputy Mayor Sutherland asked if staff could determine where fibre exists in South Frontenac. He asked if the Rideau Lakes agreement with WTC could be included in the next Council agenda.

Neil Carbone, CAO reported that he has stated the process by asking service providers however they do not provide a level of detail that is useful, this is better done by individual addresses. the CAO noted that the WTC agreement is a public document and will be included in the next council agenda.

b) Mayor Vandewal suggested that fellow Council members give some thought to having "in person" Council meetings as the social distancing aspect could be achieved in the chambers.

17. Question of Clarity (from the public on outcome of agenda items)

a) **COVID 19- Comments & Questions received up to and including May 13, 2020**

18. Closed Session - not applicable

19. Confirmatory By-law

a) **By-law 2020-28**

Resolution No. 2020-12-17
Moved by Councillor Roberts
Seconded by Councillor Leonard
That By-law 2020-28, being a by-law to confirm generally previous actions of the Council of the Township of South Frontenac, be given first and second reading this 19 day of May, 2020.

Carried

Resolution No. 2020-12-18
Moved by Councillor Sleeth
Seconded by Councillor Revill
That By-law 2020-28, being a by-law to confirm generally previous actions of the Council of the Township of South Frontenac, be given third reading, signed and sealed this 19 day of May , 2020.

Carried

20. Adjournment

a) **Resolution**

Resolution No. 2020-12-19
Moved by Councillor Barr
Seconded by Deputy Mayor Sutherland
That the Council meeting of May 19, 2020 be adjourned at 8:13 p.m.

Carried

Ron Vandewal, Mayor

Angela Maddocks, Clerk

REPORT TO COUNCIL

Office of the Chief Administrative Officer

AGENDA DATE: June 2, 2020

SUBJECT: CAO Performance Evaluation Process

RECOMMENDATION:

THAT Council approve the modified CAO appraisal framework and timeline as outlined in this report; and

THAT Council appoints Mayor Vandewal, Councillor Revill and Councillor Leonard to a CAO performance review committee for 2020.

BACKGROUND:

At the May 19, 2020 Council meeting, the CAO presented a report and recommendation regarding a CAO Performance Appraisal process based on the Canadian Association of Municipal Administrators (CAMA) Performance Management Tool Kit.

Council defeated that recommendation and asked that a more streamlined process be developed and brought back for approval. A method of 360°review from the CAO's direct reports was also requested.

The Township's current performance evaluation process is dated and would benefit from a more formal process and timeline, as well as the inclusion of annual performance objectives and core competencies that are relevant to the CAO position.

This revised process still follows the three (3) basic steps from the CAMA Tool Kit, but streamlines the process.

1. CAO conducts a self-evaluation
2. Council receives senior management input and conducts its evaluation
3. Council meets with the CAO to review the appraisal

DISCUSSION/ANALYSIS:

<u>Current Review Year (2020)</u>

In keeping with the principles outlined in the CAMA CAO Performance Review Tool Kit, the CAO recommends the following steps for the upcoming 2020 review:

1. The CAO will release a short survey to the senior management team – (Early June 2020);

2. The CAO will complete a self-evaluation and make a presentation to Council re: progress towards established priorities – (June 2020);

3. The CAO Review Committee will meet to conduct its own evaluation – (June 2020);

REPORT TO COUNCIL

Office of the
Chief Administrative Officer

4. The CAO Review Committee will review their evaluation with Council and obtain it's approval – (Early July 2020);

5. The Committee (or all of Council) will meet with the CAO to provide the review and related feedback before goal setting for the following year – (Mid-July 2020).

PA Template

The earlier list of competencies has been condensed into six (6) areas for review. These include:

- Staff effectiveness & human resource management
- Operational expertise and planning, and quality assurance
- Initiative, risk-taking, vision, creativity and innovation
- Public engagement; interpersonal communications and media relations
- Budgeting & financial analysis
- Strategic planning

Future Evaluations

Future evaluations will follow a similar structure as outlined above; however, at the beginning of the year, the CAO will develop a list of goals and objectives for approval by Council.

Progress on these objectives as well as Council's assessment of the CAO's core competencies will form the regular annual review.

FINANCIAL/STAFFING IMPLICATIONS:

None for the purposes of this report. The CAO PA Framework is administered by the CAO and Council directly.

ATTACHMENTS:

- CAO Competency Areas

Submitted/Approved by:

Neil Carbone
Chief Administrative Officer

CAO Competencies

COMPETENCY AREA	DEFINITION/EXAMPLES
Staff effectiveness/Human resource management	• Promoting the development and performance of staff and employees throughout the organization; • Creating an environment of involvement, respect, and connection of diverse ideas, backgrounds, and talent throughout the organization; • Ensuring that policies and procedures for hiring, promotion, performance appraisal, and discipline are equitable, legal, and current; • Ensuring that human resources are adequate to accomplish municipal objectives.
Operational expertise and planning/Quality assurance	• Ensuring an efficient org structure and operations; • Maintaining a consistently high level of quality in staff work, procedures, and service delivery; • Monitoring and adjusting based on data and evidence • Breaking down silos and integrating services; collaboration between departments for greater efficiencies and outcomes
Initiative, risk-taking, vision, creativity and innovation	• Setting an example that urges the organization and the community toward experimentation, change, creative problem solving, and prompt action; • Demonstrates an understanding of technology and ensuring that it is incorporated appropriately; • Evidence of calculated risk-taking • Promoting new ideas; out of the box thinking
Public engagement; interpersonal communication and media relations	• A commitment to the local democratic process by respecting and supporting elected officials, community groups, and the decision making process; • Educating citizens about local government; and acquiring knowledge of the social, economic, and political history of the community; • Facilitating the flow of ideas, information, and understanding between all parties; • Advocating effectively in the community's interest; • Communicating information to the media in a way that increases public understanding of local government issues and activities and builds a positive relationship with the media
Budgeting & Financial Analysis	• Preparing, administering and monitoring the annual budget; • Facilitating a pragmatic, priority-focused and inclusive approach to the budget process; • Interpreting financial information to assess the short-term and long-term fiscal condition of the community, • Determine the cost-effectiveness of programs, and compare alternative strategies.
Strategic Planning	• Positioning the organization and community for anticipated events and circumstances; • Being proactive, taking a strategic approach to day to day activities; • Focusing on the big picture and the long game • Rallying others around the Municipality's strategic vision and objectives;

REPORT TO COUNCIL

TREASURY DEPARTMENT

AGENDA DATE: June 2nd, 2020

SUBJECT: Green Bay Cemetery

RECOMMENDATION:

That Council approve the transfer of ownership of the Green Bay Cemetery and associated lands to the Township; and,

That the costs required for the transfer of the land be paid by the Township.

BACKGROUND:

The Green Bay Heritage Cemetery Association has approached the Township requesting that we assume responsibility for the Green Bay Cemetery, which would include the cemetery license as well as the cemetery land. Attached is a copy of the letter received from the association as well as a map of the cemetery.

The Funeral, Burial and Cremation Services Act (FBCSA) regulates cemeteries in the Province of Ontario, and is administered by the Ministry of Government and Consumer Services.

ANALYSIS/DISCUSSION:

A court abandonment process would typically takes place when a cemetery becomes abandoned for any reason (e.g. If the owner is unknown, the owner is unable to maintain the cemetery or if there is no licensed operator for the cemetery). Under the Act, if a cemetery is abandoned, the local municipality must become the owner and must take over all the assets, rights and obligations.

However, the Ministry has advised that the Township could accept the transfer request from the Green Bay Heritage Cemetery Association thereby avoiding the need to go through a court abandonment process.

As a first step, the Township would transfer the separate licensing of the cemetery to its existing license number in order to take over the operations and records maintenance.

The second step will be the transfer of the land where the cemetery is located. This is not owned by the Green Bay Heritage Cemetery Association but in preliminary discussions with the property owner, he is willing to donate the land. In order to transfer the land, a severance will need to take place which will require a survey and legal costs. This process would be done with the support of planning to ensure all legislated requirements are met.

Since the Township would be required under the act to assume the cemetery if it were abandoned, staff is recommending that the Township accept the requested transfer and associated costs.

FINANCIAL IMPLICATIONS:

The cost for survey and legal work is estimated at less than $2,000. The annual cost for additional maintenance is estimated at $2,500 annually which mostly consists of

REPORT TO COUNCIL

TREASURY DEPARTMENT

grass cutting and seasonal maintenance. Other costs are primarily funded through internment fees, interest from the Township's perpetual care reserve and taxation.

ATTACHMENTS:

- Map of cemetery
- Green Bay Heritage Cemetery Association letter

Prepared by:

Louise Fragnito
Director of Corporate Services & Treasurer

Submitted/approved by:

Neil Carbone
Chief Administrative Officer

Beattice Ln
Green Bay Rd
170 m
180 m
190 m
110 m

Feb. 11 ,2020

Twp. of South Frontenac
P.O. Box 100
Sydenham,On K0H 2TO

Attn: Louise Fragnito

Re: Green Bay Heritage Cemetery Association, or Known as Green Bay Cemetery

The Board of Directors for G.B.H.C. request that the municipality - Township of South Frontenac, Bedford District , assume duties of care and maintenance of the above noted cemetery-(permit No.3269548) , Lot 22 , Conc. 5, effective Jan,1 , 2020.

Site plans and all available former and current records will follow when necessary reports for 2019 are completed. These items, plus TDTrust Fund ,#96601 , and Bank Operating Account, 8019-497 , Bank of Montreal ,Westport, On , will also be available as per directive from B.A.O.

A financial report is available from Jan.1/19 to Dec.31/19 , and I am attaching a copy. Only Bank Surcharge will be processed after Dec. 31/19.

This request is necessary, as present Board members are reluctant to assume Executive duties, and I as Sec,/Treas. can no longer continue in this role, due to health and mobility issues.

Green Bay Cemetery Sec./Treas.

Lyle Thompson

President

Pat Barr

Pat Barr

REPORT TO COUNCIL
PUBLIC SERVICES DEPARTMENT

AGENDA DATE: June 2, 2020

SUBJECT: Tender No. PS-2020-09, 2020 Micro-Surfacing Program

RECOMMENDATION:

That Council approve the submission from Miller Paving Limited in the amount of $1,404,748.20 for Tender No. PS-2020-09, 2020 Micro-Surfacing Program.

BACKGROUND:

Pavement Preservation

Micro-surfacing is a pavement preservation technique that the Township has utilized for the last 5 years. It is a process applied to existing asphalt roads providing a new wearing surface that protects the asphalt from environmental damage such as water and snow/ice penetration.

The theory behind a preservation program is that by investing money in roads while they are in good condition, we save money in the long run and maintain a better overall road network. Micro-surfacing also provides a higher level of skid resistance to older roads where the granular in the asphalt has become polished, improving safety.

This treatment is not suitable for all situations as it will not mitigate road base defects. As a result, we need to be diligent in our selection of road segments for this sort of treatment. Road segments are generated from *Cartegraph*, the Township's asset management software program, based on information collected through the Township's bi-annual in-house road condition analysis .

Joint Procurement with City of Kingston

This year's Micro-Surfacing Tender was prepared in partnership with the City of Kingston and includes roads in both the Township of South Frontenac (Perth Road and Road 38) and in the City of Kingston (Perth Road and Taylor Kidd Boulevard). This joint effort results in consistent crosssections as you travel from one Municipality into another. The focus for the joint project this year was Perth Road, where the project limits are from McAdoos Lane to Davidson Road. This is an 11.25km section of roadway that is in good condition and meets the criteria set out in Cartegraph for this sort of pavement preservation.

Paved Shoulders

Along with and prior to this Micro-Surfacing on Perth Road we will also be introducing fully paved shoulders within our 2020 Pavement. This will provide a 10m wide platform inclusive of 1.5m paved shoulders per side.

For comparative purposes, the cost for traditional removal and replacement of the road surface with two lifts of asphalt including paved shoulders is approximately $5,000,000 with a life expectancy of 25-30 years. This portion of the Micro-Surfacing tender for that same segment is $750,000. When the cost for the addition of paved shoulders is included the total becomes $1,500,000 with a life expectancy of 10 years. With sound asset management practices the life expectancy of this asset can be further extended and greater savings achieved by utilizing this method of pavement preservation.

REPORT TO COUNCIL
PUBLIC SERVICES DEPARTMENT

Environmental Benefit

In addition to the financial benefit of paving the shoulders and applying Micro-Surfacing there is also an environmental benefit. The traditional method is called Full Depth Reclamation (FDR). FDR consists of pulverizing the existing asphalt back to a granular material and adding additional granular to create a consistent base.

The difference in greenhouse gas (GHG) emissions between the two approaches is illustrated below. It should be noted that but the FDR measurement is based on a single lift of asphalt, whereas the Township would typically place two lifts resulting in additional greenhouse gas (GHG) emissions.



Figure 4 Modeled Maintenance Treatment Greenhouse Gas Emissions



The Figure above is taken from the paper “Quantifying Greenhouse Gas Generation for Roadway Maintenance, Rehabilitation and Reconstruction Treatments” that was presented at the 2013 Transportation Association of Canada (TAC) conference in Winnipeg. This Figure outlines the significant reduction in GHG emissions by implementing Micro-Surfacing in place of traditional FDR.

It should be noted that additional GHG Emissions will be introduced as a result of the paved shoulders but this would have also been encountered with the FDR.

REPORT TO COUNCIL
PUBLIC SERVICES DEPARTMENT

ANALYSIS/DISCUSSION:

This tender was advertised on the Municipal website, on Biddingo, and in the local newspaper. This tender closed on May 13th, 2020.

The results, in ascending order, were as follows:

Supplier	Price (Incl. HST)
Miller Paving Ltd.	$1,404,748.20
Duncor Enterprises Inc.	$1,699,079.30

The submission of the low bidder has been evaluated and was found to be accurate and complete. Miller Paving Ltd. is a reputable contractor and has provided micro-surfacing services in and around South Frontenac for many years.

For these reasons, and because their price was $294,331.10 lower than the bid from Duncor Enterprises Inc., the Public Services Department recommends awarding the tender to Miller Paving Ltd., for $1,404,748.20, including HST.

For comparative purposes, below are the historical and current lowest unit prices:

Item	2016	2017	2018	2019	2020 Low Bid
Average Unit Price- $ / m²	$5.49	$5.83	$5.39	$5.98	$6.01

FINANCIAL/STAFFING IMPLICATIONS:

The total cost of this tender is shared between the City of Kingston and Township of South Frontenac.

The City of Kingston portion accounts for approximately 60% of the tender total. The City has provided a Purchase Order (PO) for this amount committing to covering their portion of the contract and have included an additional 5% for contingencies. As part of the joint procurement agreement, all invoices from the vendor will to be submitted to South Frontenac which will then invoice the City of Kingston.

The Township's portion amounts to approximately 40% of the tender total or $504,552.51. This amount is allocated as follows:

Road Segment	Cost (with non-rebatable HST)
Road 38	$244,631.52
Perth Road	$259,920.99
Total	$504,552.51

REPORT TO COUNCIL
PUBLIC SERVICES DEPARTMENT

The Micro-surfacing on Road 38 amounts to $244,631.52 inclusive of the non-rebatable portion of the HST. An amount of $1,129,000 was approved in the 2020 Capital Budget for hard surface preservation which includes the micro-surfacing on Road 38 from Desert Lake Road to the boundary, as well as amounts for other single surface treatment work.

South Frontenac's portion of the Micro-Surfacing tender on Perth Road amounts to $259,920.99 inclusive of the non-rebatable portion of the HST. An amount of $520,000 was included in the 2020 Capital Budget for the paved shoulders and Micro-Surfacing on South Frontenac's portion of Perth Road.

Sufficient funds have been budgeted for the Micro-Surfacing portions of each of these budget lines.

Submitted/approved by:

Mark Segsworth, P. Eng.
Director of Public Services

Prepared By:

David Holliday, CET
Technical Supervisor

Approved by:

Neil Carbone
Chief Administrative Officer

REPORT TO COUNCIL

PUBLIC SERVICES DEPARTMENT

AGENDA DATE: June 2, 2020

SUBJECT: Tender No. PS-2020-10, 2020 Pavement Program

RECOMMENDATION:

That council approve the submission from G. Williams Paving Limited in the amount of $1,027,113.50 for tender No. PS-2020-10, Pavement Program.

BACKGROUND:

This year's Pavement Program Tender was prepared in partnership with the City of Kingston and includes roads in both South Frontenac Township (Perth Road Shoulders and Road 38 at Portland WDS) and in the City of Kingston (Perth Road and Montreal Street). The focus for the joint project this year was Perth Road, where the project limits are from McAdoos Lane to Davidson Road. This is an 11.25km section of roadway which meets the criteria set out in the Township's Cartegraph asset management program.

Along with and prior to Micro-Surfacing on Perth Road the Township will also be introducing fully paved shoulders within our 2020 Pavement preservation program. This will provide a 10m wide platform inclusive of 1.5m paved shoulders per side.
On Road 38 our intent is to correct distorted asphalt at the Waste Disposal Site by milling and profiling the existing asphalt surface to a consistent platform then paving a surface course with a fibre reinforced asphalt. The purpose of the fibres is to mitigate the distortion. This technology has been used extensively around the area and within South Frontenac on Perth Road at Garrett Lane where it is performing as expected.

ANALYSIS/DISCUSSION:

This tender was advertised on the Municipal website, on Biddingo, and in the local newspaper. This tender closed on May 13th, 2020.

The results, in ascending order, were as follows:

Supplier	Price (Incl. HST)
G. Williams Paving Ltd.	$1,027,113.50
Kiley Paving Ltd.	$1,325,377.00
Coco Paving Inc.	$1,356,000.00

The submission of the low bidder has been evaluated and was found to be accurate and complete. G. Williams Paving Ltd. is a reputable contractor and has provided paving services in and around South Frontenac for many years.

REPORT TO COUNCIL

PUBLIC SERVICES DEPARTMENT

For these reasons, and because their price was $298,263.50 lower than the bid from Kiley Paving Ltd., the Public Services Department recommends awarding the tender to G. Williams Paving Ltd., for $1,027,113.50, including HST.

FINANCIAL/STAFFING IMPLICATIONS:

The total cost of this tender is shared between the City of Kingston and Township of South Frontenac.

The City of Kingston portion accounts for approximately 58% of the tender total. The City has provided a Purchase Order (PO) for this amount committing to covering its portion of the contract plus an additional 15% for contingencies. As part of the joint procurement agreement, all invoices from the vendor will to be submitted to South Frontenac which will then invoice the City of Kingston.

The Township's portion amounts to approximately 42% of the tender total or $387,197.56. This amount is allocated as follows:

Road Segment	**Cost** (with non-rebatable HST)
Road 38	$52,406.50
Perth Road	$334,791.06
Total	$387,197.56

An amount of $86,000 was approved in the 2020 Capital Budget for the asphalt repair work on Road 38. This section within the tender amounted to $52,406.50 inclusive of the non-rebatable portion of the HST.

Perth Road is a joint paved shoulder project to achieve a consistent 1.5m paved shoulder for the entire length of the project. South Frontenac's portion of this is $334,791.06 inclusive of the non-rebatable portion of the HST. An amount of $520,000 was included in the 2020 Capital Budget for Paved Shoulders and Micro-Surfacing on Perth Road. This cost coupled with the cost to Micro-Surface amounts to $594,712.05. As a result, an amount of $100,000 is proposed to be transferred from the linear capital contingency fund for this project. This additional funding will cover all anticipated costs and provide a contingency for any unanticipated overages that occur during construction.

Submitted/approved by:

Mark Segsworth, P. Eng.
Director of Public Services

Prepared By:

David Holliday, CET
Technical Supervisor

Approved by:

Neil Carbone
Chief Administrative Officer

REPORT TO COUNCIL

DEVELOPMENT SERVICES DEPARTMENT

AGENDA DATE: June 2, 2020

SUBJECT: Road & Property Exchange
By-law to Dedicate Lands as a Common Highway
Norman Road at Perth Road (Spicer/Postma)
Pt Lot 25, Conc. 14,and part of Norman Road, Registered Plan 1451, District of Loughborough,
Township of South Frontenac

RECOMMENDATION

THAT Council **pass** By-law 2020-29 to repeal By-law 2019-32 and to dedicate Part 2 on RP13R22212, Part Lot 25, Concession 14, Geographic Township of Loughborough, municipally known as the travelled portion of Norman Lane to be a common and public highway.

BACKGROUND

South Frontenac Council approved a request to stop up, close and sell a portion of an unused road that is part of the Norman Plan of Subdivision (RP 1451) and, in turn, purchase land for use as a road at the current intersection of Norman Lane with Perth Road.

The exchange included the sale and transfer of a portion of Norman Road which was land dedicated to the Township in the past as part of Norman Subdivision, however the municipality had never assumed the road, nor maintained it. The access to Norman Subdivision was established as a private lane that for the most part aligns with the unopened road known as Norman Road in the Norman Subdivision.

In this exchange, the Township solicitor transferred to Mr. Spicer an unopened portion of the “jog” (surveyed as Part 1 of RP1321964) of Norman Road adjacent to his property (5 Norman Lane) for the purpose of building a garage. Mr. Postma then transferred land to the Township that includes the traveled portion of Norman Lane at the intersection of Perth Road (surveyed as Part 2 of RP1321964).

The Township solicitor registered this transfer of land earlier this year at the Land Registry Office. The transfer of land from Mr. Postma to the Township, and the transfer of land from the Township to Mr. Spicer have been finalized.

Along with the transfer of land, the Township solicitor directed staff to prepare a dedication by-law for the portion of land that forms the travelled portion of Norman Lane (surveyed as Part 2 of RP22212 - attached).

At the May 21, 2019 meeting, such a by-law was prepared and approved by Council using a description being Part 1 on Reference Plan 13R13913.

DISCUSSION/ANALYSIS:

Upon registration of the dedication by-law, the Land Registry Office refused the description of these lands as the original reference plan neglected to show a pre-existing easement/right-of-way. This easement had been missed by the surveyor when the original plan was prepared.

The surveyor has prepared a new reference plan 13R22212 (attached). The land to be dedicated to the Township is now described as Part 2, subject to easement (as in FC102090 and RF763408) which are old rights-of-way in favour of property owners farther along Norman Road.

While fundamentally nothing changes from what had been approved initially by Council, it is recommended that a new by-law be passed that includes the correct reference to the new R-plan.

While the Township solicitor recommends the Township pass a dedication by-law for the travelled portion of Norman Lane, there is no change to the maintenance or ownership of Norman Lane as a result of this by-law.

Once this By-law is signed by the Mayor and Clerk, it will be forwarded along with the new reference plan (13R22212) to the Township Solicitor for registration.

FINANCIAL and STAFFING CONSIDERATIONS

None – this amended by-law will finalize a transfer already approved by Council in May 2019.

ATTACHMENTS

- Attachment #1 – Location Map – Norman Road Exchange
- Attachment #2 – Reference Plan 13R22212
- Attachment #3 – By-law 2020-29 to dedicate the travelled portion of Norman Lane to be a common and public highway (under By-law section of agenda 12 a)

Submitted by: Claire Dodds, MCIP, RPP, Director of Development Services

Approved by:
Neil Carbone, CAO

FRONTENAC | Spicer and Postmas Norman Road Exchange



Legend

- Assessment Parcels
- Citations

Notes

0.9 0 0.43 0.9 Kilometers

WGS_1984_Web_Mercator_Auxiliary_Sphere

© Latitude Geographics Group Ltd.

This map is a user generated static output from an Internet mapping site and is for reference only. Data layers that appear on this map may or may not be accurate, current, or otherwise reliable.

THIS MAP IS NOT TO BE USED FOR NAVIGATION

SCHEDULE			
PART	LOT	CON/PLAN	PIN
1	PART OF LOT 25	14	BEING PART OF PIN 36281–0756(LT)
2	PART OF LOT 25	14	BEING PART OF PIN 36281–0756(LT)

PART 2 IS SUBJECT TO EASEMENT
(AS IN INST. No. FC102090 & FR763408)

I REQUIRE THIS PLAN TO BE DEPOSITED UNDER THE LAND TITLES ACT.

APRIL 30, 2020
DATE:

LESLIE M. HIGGINSON O.L.S.

PLAN 13R 22052

RECEIVED AND DEPOSITED

May 1, 2020
DATE:

REPRESENTATIVE FOR LAND REGISTRAR
FOR THE LAND TITLES DIVISION OF
FRONTENAC No. 13

PLAN OF SURVEY
OF PART OF LOT 25
CONCESSION 14
TOWNSHIP OF SOUTH FRONTENAC
(GEOGRAPHIC TOWNSHIP OF LOUGHBOROUGH)
COUNTY OF FRONTENAC
SCALE: 1 : 200

5m 0 5 10 15 metres

METRIC
DISTANCES & COORDINATES SHOWN ON THIS PLAN ARE IN METRES AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048

LESLIE M. HIGGINSON SURVEYING Ltd.
2020



SURVEYOR'S CERTIFICATE:

I CERTIFY THAT:
1. THIS SURVEY AND PLAN ARE CORRECT AND IN ACCORDANCE WITH THE SURVEYS ACT, THE SURVEYORS ACT, THE LAND TITLES ACT AND THE REGULATIONS MADE UNDER THEM.
2. THE SURVEY WAS COMPLETED ON THE 23RD DAY OF MARCH, 2020.

LESLIE M. HIGGINSON SURVEYING Ltd.
ONTARIO LAND SURVEYOR
KINGSTON, ONTARIO

APRIL 1, 2020
DATE

LESLIE M. HIGGINSON
ONTARIO LAND SURVEYOR

NOTE & LEGEND:

BEARINGS SHOWN HEREON ARE GRID BEARINGS DERIVED FROM GPS OBSERVATIONS AND ARE RELATED TO UTM ZONE 18, (75° WEST LONGITUDE) NAD83 (CSRS) (2010.0).

COMPARISONS SHOWN IN BRACKETS ARE TO ASTRONOMIC BEARINGS

ALL DISTANCES SHOWN HEREON ARE HORIZONTAL GROUND DISTANCES.

GRID DISTANCES CAN BE CALCULATED BY MULTIPLYING THE GROUND DISTANCES SHOWN ON THE PLAN BY THE COMBINED SCALE FACTOR OF 0.999735.

INTEGRATION COORDINATE TABLE OBSERVED REFERENCE POINTS(ORPs) DERIVED FROM GPS OBSERVATIONS USING REAL TIME NETWORK(RTN) BASE AND ROVER BASELINES COORDINATES TO URBAN ACCURACY PER SEC. 14 (2) OF O.REG. 216/10		
POINT ID	NORTHING (M)	EASTING (M)
ORP A	4932242.53	384916.62
ORP B	4932224.62	384906.91
ORP C	4932149.57	384876.60
COORDINATES CANNOT, IN THEMSELVES, BE USED TO RE–ESTABLISH CORNERS OR BOUNDARIES SHOWN ON THIS PLAN.		

□	DENOTES	SURVEY MONUMENT PLANTED
■	"	SURVEY MONUMENT FOUND
SSIB	"	SHORT STANDARD IRON BAR
SIB	"	STANDARD IRON BAR
IB	"	IRON BAR
RP	"	ROCK POST
RB	"	ROCK BAR
WIT	"	WITNESS
CALC	"	CALCULATED
S	"	SET
M	"	MEASURED
1596	"	LESLIE M. HIGGINSON O.L.S.
681	"	D.C. SMITH O.L.S.
S&SK	"	SMITH & SMITH O.L.S.
1759	"	RALPH F. GRANDER O.L.S.
RP1	"	REGISTERED PLAN No. 1451
P1	"	PLAN 13R–13913
P2	"	PLAN 13R–7670
P3	"	PLAN 13R–16357
P4	"	EXPROPRIATION PLAN FR617133
P5	"	PLAN 13R–22052

SSIB'S WERE PLANTED WHERE OVERBURDEN WAS INSUFFICIENT TO SET SIB'S

ALL MEASURMENTS ARE IN AGREEMENT WITH PLAN 13R–22052

DATED APRIL 30, 2020

LESLIE M. HIGGINSON SURVEYING Ltd.
1064 GARDINERS ROAD
KINGSTON, ONTARIO K7P 1R7
(613) 389–7986 (fax)389–5578 or leslie@lmhigginson.com

FILE: LO'H 14–25 | LMH1442GNDC RPLAN rev2

TOWNSHIP OF SOUTH FRONTENAC
BY-LAW 2020-29

BEING A BY-LAW TO DEDICATE AS COMMON AND PUBLIC HIGHWAY CERTAIN LANDS IN THE TOWNSHIP OF SOUTH FRONTENAC, PURSUANT TO SECTION 31(6) OF THE MUNICIPAL ACT, 2001.

WHEREAS certain lands in the Township of South Frontenac were deeded to the Township of South Frontenac for the purpose of dedicating them to public use as common and public highways;

NOW THEREFORE THE CORPORATION OF THE TOWNSHIP OF SOUTH FRONTENAC, BY ITS COUNCIL, HEREBY ENACTS AS FOLLOWS:

Those lands herein described are dedicated as common and public highways.

1. PT LT 25 CON 14 GEOGRAPHIC TOWNSHIP OF LOUGHBOROUGH BEING PART 2 ON PLAN 13R-22212, SOUTH FRONTENAC

2. THAT By-law 2019-33 shall hereby be repealed.

This by-law shall come into force and take effect on the date of registration of this by-law.

Dated at the Township of South Frontenac this 2nd day of June, 2020.

Read a first and second time this 2nd day of June, 2020.

Read a third time and finally passed this 2nd day of June, 2020.

THE CORPORATION OF THE TOWNSHIP OF SOUTH FRONTENAC

_____

Ron Vandewal, Mayor

_____

Angela Maddocks, Clerk

Payment Listing
For the period of March 18, 2020 to June 2, 2020

Accounts Payable Payment Listing:		$	4,057,679.63
	For the period of March 18, 2020 to June 2, 2020		
Payroll Payment Listing:			
Pay Period #20-06	Pay date March 25 2020	$	91,989.50
	For the period of March 8, 2020 to March 21, 2020		
Pay Period #20-07	Pay date April 8 2020	$	93,955.70
	For the period of March 22, 2020 to April 4, 2020		
Pay Period #20-08	Pay date April 22 2020	$	90,984.09
	For the period of April 5, 2020 to April 18, 2020		
Pay Period #20-09	Pay date May 6 2020	$	94,784.48
	For the period of April 19, 2020 to May 2, 2020		
Pay Period #20-10	Pay date May 20 2020	$	97,413.33
	For the period of May 3, 2020 to May 16, 2020		
Council Honorarium:	Pay date March 31, 2020	$	14,435.17
	For the period of March 1, 2020 to March 31, 2020		
Council Honorarium:	Pay date April 30, 2020	$	12,843.05
	For the period of April 1, 2020 to April 30, 2020		
Council Honorarium:	Pay date May 29, 2020	$	12,767.37
	For the period of May 1, 2020 to May 31, 2020		
Total Payments		**$**	**4,566,852.32**

RECOMMENDATION:

1. It is recommended that Council receive for information the listing of the Accounts Payable and Payroll for the period ending June 2, 2020 in the amount of $ 4,566,852.32

Submitted by:

Mark Foster - Accounting Clerk

Approved by:

Emily Caird- Acting Deputy Treasurer

Ranges:	From:	To:	Distribution Types Included:
Cheque Date:	**2020-03-18**	**2020-06-02**	**PURCH, MISC**

10 GG

0000 Gen

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013117	2020-03-27		THE FRONTENAC NEWS		
		71938		Ads- Feb 6,13,20,27	$2,645.76
Total EFT000000013117					**$2,645.76**
EFT000000013163	2020-04-03		THE FRONTENAC NEWS		
		72180		Ads- Mar 5,12,19,26	$2,442.24
Total EFT000000013163					**$2,442.24**
EFT000000013246	2020-04-20		ZYCOM TECHNOLOGY INC.		
		IN-65930-01		Server Back Up	$8,459.31
Total EFT000000013246					**$8,459.31**
EFT000000013312	2020-05-15		COUNTY OF FRONTENAC		
		58849		Q1 FMIS + GIS	$29,592.76
Total EFT000000013312					**$29,592.76**
EFT000000013324	2020-05-15		THE FRONTENAC NEWS		
		72326		Ads- Apr 2,9,16,23,30	$3,307.20
Total EFT000000013324					**$3,307.20**
Total Gen					**$46,447.27**

0035 TaxSB-EP

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013125	2020-03-27		LIMESTONE DISTRICT SCHOOL		
		2020 MARCH LEVY		2020 MARCH LEVY	$1,276,156.60
Total EFT000000013125					**$1,276,156.60**
Total TaxSB-EP					**$1,276,156.60**

0036 TaxSB-ES

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013103	2020-03-27		ALGONQUIN AND LAKESHORE		
		2020 MARCH LEVY		2020 MARCH LEVY	$115,945.48
Total EFT000000013103					**$115,945.48**
Total TaxSB-ES					**$115,945.48**

0037 TaxSB-FP

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013111	2020-03-27		CONSEIL DES ECOLES PUBLIQUES		
		2020 MARCH LEVY		2020 MARCH LEVY	$6,348.67
Total EFT000000013111					**$6,348.67**
Total TaxSB-FP					**$6,348.67**

0038 TaxSB-FS

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013112	2020-03-27		CONSEIL SCOLAIRE CATHOLIQUE DU		
		2020 MARCH LEVY		2020 MARCH LEVY	$9,137.14
Total EFT000000013112					**$9,137.14**
Total TaxSB-FS					**$9,137.14**

1000

Cheque	Date	Inv #	Vendor	Description	Amount
070844	2020-03-30		SNIDER, PERCY		
		20/02/27-41		Snow Plowing	$839.52
Total 070844					**$839.52**
070892	2020-04-20		SNIDER, PERCY		
		20/02/28-50		Snow Plowing	$76.32
Total 070892					**$76.32**
070897	2020-04-20		RD ELLIOTT ROOFING		
		535		Repair Chimney	$411.11
Total 070897					**$411.11**
070898	2020-05-01		ATKINSON HOME BUILDING CENTRE		
		258799		Salt Softener	$24.39
Total 070898					**$24.39**
070920	2020-05-15		VERONA CARPET SALES		
		1243		Carpet + Install	$2,982.28
		1244		Block Vinyl + Install	$175.54
Total 070920					**$3,157.82**
070931	2020-05-29		SNIDER, PERCY		
		20/04/27-50		Sweeping	$198.43
		20/05/01-03		Sweeping	$396.86
Total 070931					**$595.29**
EFT000000013118	2020-03-27		INDEPENDENT TELEPHONE SERVICES		
		44866		Telephone Programming	$164.75
Total EFT000000013118					**$164.75**
EFT000000013130	2020-03-27		PINCHIN LTD.		
		1494228		Assessment	$2,696.64
Total EFT000000013130					**$2,696.64**
EFT000000013157	2020-04-03		CULLIGAN		

		87776TJ	Water	$28.79
Total EFT000000013157				**$28.79**
EFT000000013161	2020-04-03	EARL ROSEBUSH FUELS		
		0279-114251	412.30L @.949	$420.68
Total EFT000000013161				**$420.68**
EFT000000013182	2020-04-03	SUPERIOR PROPANE INC.		
		29137559	1749.9L @.45	$856.51
Total EFT000000013182				**$856.51**
EFT000000013202	2020-04-20	BUSINESS INTERIORS(ONTARIO)INC		
		1920-1989	Office Furniture	$9,335.22
Total EFT000000013202				**$9,335.22**
EFT000000013206	2020-04-20	CULLIGAN		
		96396TJ	Water	$38.56
		2695430	Cooler Rental	$10.12
Total EFT000000013206				**$48.68**
EFT000000013210	2020-04-20	DAHM PAINTING & DECORATING LTD		
		1097	Paint Lower Level	$1,857.12
Total EFT000000013210				**$1,857.12**
EFT000000013231	2020-04-20	SELECT DOOR AND FRAME		
		SI000972	Doors- Basement Reno	$3,117.67
Total EFT000000013231				**$3,117.67**
EFT000000013232	2020-04-20	SIMMONS PLUMBING & PUMP SERV.		
		6067	Repair Men's Toilet	$90.57
		6066	Service Call- UV Alarm	$76.32
Total EFT000000013232				**$166.89**
EFT000000013237	2020-04-20	TROUSDALE'S HOME HARDWARE		
		102102	Padlock	$14.74
Total EFT000000013237				**$14.74**
EFT000000013238	2020-04-20	UBCON CONSTRUCTION LTD		
		19-014-6	Phase 2- Apply Drywall	$7,650.82
Total EFT000000013238				**$7,650.82**
EFT000000013245	2020-04-20	XCG CONSULTANTS LTD.		
		56220	Drinking Water Sampling	$101.76
		56220	Drinking Water Sampling	$101.76
		56329	Drinking Water Sampling	$101.76
		56329	Drinking Water Sampling	$101.76
Total EFT000000013245				**$407.04**
EFT000000013261	2020-05-01	CULLIGAN		
		3861TJ	Water	$35.09
Total EFT000000013261				**$35.09**
EFT000000013274	2020-05-01	NORTHWAY HARDWARE		
		23701	Canadian Flag	$36.62
Total EFT000000013274				**$36.62**
EFT000000013278	2020-05-01	SIMMONS PLUMBING & PUMP SERV.		
		6102	UV Alarm Sounding	$190.80
Total EFT000000013278				**$190.80**
EFT000000013287	2020-05-01	TROUSDALE'S HOME HARDWARE		
		228353	Door Stops	$12.19
Total EFT000000013287				**$12.19**
EFT000000013314	2020-05-15	CULLIGAN		
		7982TJ	Water	$59.56
		2707273	Cooler Rental	$10.12
Total EFT000000013314				**$69.68**
EFT000000013327	2020-05-15	HARTINGTON EQUIPMENT LIMITED		
		WO22097	Repair Generator	$264.45
Total EFT000000013327				**$264.45**
EFT000000013334	2020-05-15	LIGHTING...FX INC.		
		61212	2X Emerg. Exit Combo Kits	$318.41
		61244	Running Man Light	$371.17
Total EFT000000013334				**$689.58**
EFT000000013336	2020-05-15	LONDRY ALARMS		
		202603	4X Alarm Codes	$40.70
Total EFT000000013336				**$40.70**
EFT000000013342	2020-05-15	R&D NELSON GENERAL MAINTENANCE		
		20/04-OFFICE	20/03+20/04 General Maint.	$1,358.50
		20/04-OFFICE	20/03+20/04 General Maint.	$98.40
Total EFT000000013342				**$1,456.90**
EFT000000013348	2020-05-15	SELECT DOOR AND FRAME		
		SI001056	3X Locksets	$185.52
Total EFT000000013348				**$185.52**
EFT000000013350	2020-05-15	SUPERIOR PROPANE INC.		
		29690059	AED + Battery	$529.85
Total EFT000000013350				**$529.85**
EFT000000013357	2020-05-15	TRUE ELECTRIC		
		6930	Electrical Renovation	$2,379.12
Total EFT000000013357				**$2,379.12**
EFT000000013374	2020-05-29	CULLIGAN		
		14482TJ	Water	$41.39
Total EFT000000013374				**$41.39**
EFT000000013404	2020-05-29	SIMMONS PLUMBING & PUMP SERV.		
		6113	Hot Water Tank	$901.59
		6116	Service Call	$76.32
		6117	Solenoid Valve	$432.48
		6119	Water Leak	$154.67
Total EFT000000013404				**$1,565.06**
EFT000000013405	2020-05-29	SPECIALIZED ONSITE SERVICES		
		1647	Water Testing	$4,522.21
Total EFT000000013405				**$4,522.21**
EFT000000013409	2020-05-29	TOTAL POWER LTD		

		SALES0089530		Annual Inspection	$1,047.11
Total EFT000000013409					**$1,047.11**
Total					**$44,936.27**

1100 Counc

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013217	2020-04-20		ESOLUTIONS GROUP		
		123547		Cludo Essential Lite Search	$712.32
Total EFT000000013217					**$712.32**
EFT000000013257	2020-05-01		CDW CANADA INC		
		XPF8937		Laptop For E-Council Meetings	$1,477.62
Total EFT000000013257					**$1,477.62**
EFT000000013280	2020-05-01		STRATEGY CORP INC.		
		11736		Strategic Review	$66,493.04
Total EFT000000013280					**$66,493.04**
Total Counc					**$68,682.98**

1210 CAO

Cheque	Date	Inv #	Vendor	Description	Amount
070917	2020-05-15		OMAA		
		2020-853-B		2020 Membership (9 months)	$300.19
Total 070917					**$300.19**
EFT000000013207	2020-04-20		CUNNINGHAM SWAN CARTY		
		163251		Legal Advice	$203.52
Total EFT000000013207					**$203.52**
Total CAO					**$503.71**

1250 Clk

Cheque	Date	Inv #	Vendor	Description	Amount
070922	2020-05-15		ZOOM VIDEO COMMUNICATIONS INC		
		INV18376781		2X Standard + 2X Webinar	$920.35
Total 070922					**$920.35**
EFT000000013108	2020-03-27		CDW CANADA INC		
		XFZ0637		Service Laserjet+ Input Sensor	$1,045.67
Total EFT000000013108					**$1,045.67**
EFT000000013139	2020-03-27		TROUSDALE'S FOODLAND		
		5815		Coffee + Cream	$37.57
		398		Milk + Cream	$10.62
		4113		Coffee + Cream	$22.49
		5402		Lunch	$83.15
Total EFT000000013139					**$153.83**
EFT000000013222	2020-04-20		INDEPENDENT TELEPHONE SERVICES		
		44898		Voicemail- Email E.C.	$86.50
		44905		Voicemail- Email A.M.	$86.50
Total EFT000000013222					**$173.00**
EFT000000013355	2020-05-15		TROUSDALE'S FOODLAND		
		229		Coffee + Sugar + Cream	$44.16
		1276		Cleaner + Cream	$7.05
		6003		2X Greeting Cards	$7.10
		2752		Milk + Cream	$5.88
Total EFT000000013355					**$64.19**
EFT000000013359	2020-05-15		UPPER CANADA OFFICE SYSTEMS		
		363081		Copier Usage	$617.77
Total EFT000000013359					**$617.77**
EFT000000013411	2020-05-29		TROUSDALE'S FOODLAND		
		3082		Coffee+ Cream + Sugar	$26.05
Total EFT000000013411					**$26.05**
Total Clk					**$3,000.86**

1275 Fin

Cheque	Date	Inv #	Vendor	Description	Amount
070895	2020-04-20		CAMERON, ALEXANDER		
		2020 LOTTERY		Lottery License Refund	$48.00
Total 070895					**$48.00**
EFT000000013105	2020-03-27		BAYRIDGE PRINTER PROS		
		24315		Service Laserjet+ Input Sensor	$223.81
Total EFT000000013105					**$223.81**
EFT000000013113	2020-03-27		CUNNINGHAM SWAN CARTY		
		163059		Legal Advice	$116.72
		163056		Legal Advice	$212.68
Total EFT000000013113					**$329.40**
EFT000000013118	2020-03-27		INDEPENDENT TELEPHONE SERVICES		
		44866		Telephone Programming	$38.31
		44883		Voicemail to Email	$28.83
Total EFT000000013118					**$67.14**
EFT000000013209	2020-04-20		D2 WIRELESS - TELUS AUTHORIZED DEALER		
		BUSKIIN7310		Internet Key	$81.41
Total EFT000000013209					**$81.41**
EFT000000013222	2020-04-20		INDEPENDENT TELEPHONE SERVICES		
		44889		7X Phones	$3,568.01
Total EFT000000013222					**$3,568.01**
EFT000000013257	2020-05-01		CDW CANADA INC		
		XPF1509		USB Microphone	$177.20
Total EFT000000013257					**$177.20**
EFT000000013271	2020-05-01		KKP		

		29080		Covid 19- Mail Out	$4,179.91
Total EFT000000013271					**$4,179.91**
Total Fin					**$8,674.88**

1280 HR

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013118	2020-03-27		INDEPENDENT TELEPHONE SERVICES		
		44883		Voicemail to Email	$14.41
Total EFT000000013118					**$14.41**
EFT000000013221	2020-04-20		HIBERNUM FARMS INC.		
		2		HR Consulting	$1,005.39
Total EFT000000013221					**$1,005.39**
Total HR					**$1,019.80**
Total GG					**$1,580,853.66**

20 PP&P

2100 Fire

Cheque	Date	Inv #	Vendor	Description	Amount
070844	2020-03-30		SNIDER, PERCY		
		20/02/27-45		Snow Plowing	$1,831.68
		20/02/27-44-2		Snow Plowing	$1,984.32
		20/02/27-43-2		Snow Plowing	$1,831.68
Total 070844					**$5,647.68**
070861	2020-03-27		ATKINSON HOME BUILDING CENTRE		
		253026		Crack Sealer+ Bulbs	$32.46
Total 070861					**$32.46**
070862	2020-03-27		FLUENT INFORMATION MANAGEMENT SYSTEMS INC.		
		INV-4607		Subscription + Rental Fee	$1,831.68
Total 070862					**$1,831.68**
070863	2020-03-27		KINGSTON FIRE AND RESCUE		
		5296		Q1 Dispatching Fees	$9,228.72
Total 070863					**$9,228.72**
070865	2020-03-27		MINISTER OF FINANCE		
		111202201102176		New Program Registration Fees	$195.00
Total 070865					**$195.00**
070866	2020-03-27		RECEIVER GENERAL RADIO LICENCES		
		20200033504		2020 Radio Licence Renewal	$460.90
		20200032885		2020 Radio Licence Renewal	$83.80
Total 070866					**$544.70**
070868	2020-03-27		TOWNSHIP OF RIDEAU LAKES		
		2019 BILLING		2019 Response	$4,600.00
Total 070868					**$4,600.00**
070881	2020-04-03		RECEIVER GENERAL RADIO LICENCES		
		20200033561		Radio Licence Renewals	$5,841.82
Total 070881					**$5,841.82**
070890	2020-04-20		1323661 ONTARIO INC O/A THE PIZZA PLACE		
		4156		4X Pizzas	$66.86
Total 070890					**$66.86**
070892	2020-04-20		SNIDER, PERCY		
		20/02/28-46		Snow Plowing	$152.64
		20/02/28-47		Snow Plowing	$152.64
		20/02/28-48		Snow Plowing	$152.64
Total 070892					**$457.92**
070899	2020-05-01		BUNZL CANADA INC		
		66369948		Cleaners	$6,100.51
Total 070899					**$6,100.51**
070901	2020-05-01		SNIDER, PERCY		
		20/04/10-45		Clean Gravel + Sand off Grass	$76.32
		20/04/09-06		Bin Rental+ Disposal	$318.53
Total 070901					**$394.85**
070913	2020-05-15		ATKINSON HOME BUILDING CENTRE		
		258975		Lumber+ Hooks+Shelf Brackets	$209.94
		260078		Vinyl Flooring	$780.05
Total 070913					**$989.99**
070914	2020-05-15		BUNZL CANADA INC		
		66370295		Clorox 360	$5,271.11
Total 070914					**$5,271.11**
070924	2020-05-29		BUNZL CANADA INC		
		66370984		4000X Masks	$7,530.24
Total 070924					**$7,530.24**
070926	2020-05-29		FASTENAL CANADA LTD		
		ONKIN110579		2X Gas Springs+ 2XSide Markers	$295.04
Total 070926					**$295.04**
070927	2020-05-29		H&R MACHINE WELDING & FABRICATION		
		5468		Forcible Entry Simulator	$7,937.28
Total 070927					**$7,937.28**
070928	2020-05-29		KINGSTON FIRE AND RESCUE		
		5431		Q2 Dispatch Fees	$9,228.72
Total 070928					**$9,228.72**
070931	2020-05-29		SNIDER, PERCY		
		20/04/27-01		Sweeping	$198.43
		20/04/27-49		Sweeping	$198.43
		20/05/01-04		Sweeping	$396.86
Total 070931					**$793.72**
EFT000000013100	2020-03-27		ABELL PEST CONTROL INC.		
		A2653205		20/02 Pest Control	$48.54

Total EFT000000013100				**$48.54**
EFT000000013102	2020-03-27	AJ STONE COMPANY LIMITED		
	152086		35X Facepieces	$16,371.46
Total EFT000000013102				**$16,371.46**
EFT000000013104	2020-03-27	ASSELSTINE HARDWARE		
	7016		Toilet Flapper + Aerator	$13.93
	7064		Turn Signal Bulb	$6.60
Total EFT000000013104				**$20.53**
EFT000000013107	2020-03-27	BOOKSTORE- ANNEX PUBLISHING & PRINTING		
	BK0003597		Guide to the Ont. Fire Code	$51.43
Total EFT000000013107				**$51.43**
EFT000000013115	2020-03-27	EARL ROSEBUSH FUELS		
	2706-112720		316.80L @.679	$236.20
Total EFT000000013115				**$236.20**
EFT000000013116	2020-03-27	FIRE MARSHAL'S PUBLIC FIRE		
	IN156492		Book: Water Rescue	$121.82
Total EFT000000013116				**$121.82**
EFT000000013120	2020-03-27	KENWORTH ONTARIO - KINGSTON		
	KS27297		2X Batteries	$529.22
	KS27089		Safety + Service + Muffler	$2,832.75
Total EFT000000013120				**$3,361.97**
EFT000000013124	2020-03-27	LEONARD FUELS		
	2706-1054341		Air Filter	$5.19
Total EFT000000013124				**$5.19**
EFT000000013126	2020-03-27	MESSER CANADA INC.		
	2102030135		Small Cylinder Utilization Fee	$76.32
	2102001912		Oxygen	$450.80
	2101964837		Oxygen	$221.45
Total EFT000000013126				**$748.57**
EFT000000013127	2020-03-27	MARK R. HALLADAY EMERGENCY		
	20/03/09		7X Basic Life Support	$1,296.42
Total EFT000000013127				**$1,296.42**
EFT000000013129	2020-03-27	NORTHWAY HARDWARE		
	16549		Rope + Electrical Tape	$43.02
Total EFT000000013129				**$43.02**
EFT000000013131	2020-03-27	PPE SOLUTIONS INC.		
	7971		Wipes	$751.59
Total EFT000000013131				**$751.59**
EFT000000013134	2020-03-27	ROSESON DISTRIBUTORS INC.		
	1057-12393		82.76L @.8995	$75.75
Total EFT000000013134				**$75.75**
EFT000000013135	2020-03-27	R. THURSTON TECHNOLOGIES		
	11519		Service Call	$86.50
	11538		Service Call- Pager Repeater	$432.48
Total EFT000000013135				**$518.98**
EFT000000013137	2020-03-27	SWISH MAINTENANCE LIMITED		
	K629489		Squeege Head + Cleaner	$37.89
Total EFT000000013137				**$37.89**
EFT000000013143	2020-03-27	WILLIAMS, KATHY		
	20/02/29		19/12-20/02 Cleaning	$455.00
Total EFT000000013143				**$455.00**
EFT000000013149	2020-04-03	BLACK DOG TIRE & LUBRICANTS		
	39658		Flat Repair	$175.98
Total EFT000000013149				**$175.98**
EFT000000013150	2020-04-03	BOOKSTORE- ANNEX PUBLISHING & PRINTING		
	BK0003631		Inpection+Code Enforcement	$157.73
Total EFT000000013150				**$157.73**
EFT000000013152	2020-04-03	CANADIAN TIRE		
	137376		Battery Charger	$56.98
Total EFT000000013152				**$56.98**
EFT000000013160	2020-04-03	DRAPER DOORS		
	20295		Service Call- Door Stuck	$198.43
Total EFT000000013160				**$198.43**
EFT000000013161	2020-04-03	EARL ROSEBUSH FUELS		
	1057-113674		357.60L @.623	$246.25
	3935-112732		269.6L @.712	$210.07
	1057-114730		470.00L @.569	$297.83
	1060-113727		363.50L @.949	$370.89
	2706-114732		303.00L @.572	$192.93
	4896-113711		303.00L @.572	$224.35
	0647-114746		795.20L @.569	$503.88
Total EFT000000013161				**$2,046.20**
EFT000000013162	2020-04-03	FIRE MARSHAL'S PUBLIC FIRE		
	IN156661		Exam Prep F.I. 1+2	$78.81
	IN156663		Fire Investigator 2nd.	$272.12
Total EFT000000013162				**$350.93**
EFT000000013168	2020-04-03	IMPACT BATTERY & POWERSPORT		
	32033		Motorcycle Battery	$94.43
Total EFT000000013168				**$94.43**
EFT000000013169	2020-04-03	JODY CAMPBELL'S SEPTIC SERVICE		
	16527		20/03-20/04 Toilet Rental	$101.76
Total EFT000000013169				**$101.76**
EFT000000013173	2020-04-03	KENWORTH ONTARIO - KINGSTON		
	KS27446		02 Strap stuck in door	$242.89
Total EFT000000013173				**$242.89**
EFT000000013180	2020-04-03	R. THURSTON TECHNOLOGIES		
	11547		In-Vehicle Repeater	$2,890.69
	11550		2X Service Calls	$216.24
Total EFT000000013180				**$3,106.93**

EFT000000013182	2020-04-03	SUPERIOR PROPANE INC.		
	29137557		3.3L @.45	$1.62
	29137558		2008.1L@.45	$982.90
Total EFT000000013182				**$984.52**
EFT000000013192	2020-04-03	WESTPORT HOME HARDWARE		
	20302		Cleaning Supplies	$137.95
Total EFT000000013192				**$137.95**
EFT000000013193	2020-04-15	TOWN & COUNTRY CHRYSLER LTD		
	41734		2020 Jeep Cherokee	$43,220.93
Total EFT000000013193				**$43,220.93**
EFT000000013194	2020-04-20	BOULTON SEPTIC/LARMON'S		
	31824		Holding Tank Pumped	$244.22
Total EFT000000013194				**$244.22**
EFT000000013195	2020-04-20	ABELL PEST CONTROL INC.		
	A2700962		20/03 Pest Control	$48.54
	A2678334		20/03 Pest Control	$41.18
	A2669297		20/03 Pest Control	$50.80
Total EFT000000013195				**$140.52**
EFT000000013198	2020-04-20	ASSELSTINE HARDWARE		
	7122		Paint	$202.26
	7126		3X Paint Pails	$17.37
	7130		Paint	$123.91
Total EFT000000013198				**$343.54**
EFT000000013199	2020-04-20	BELL MOBILITY (RADIO DIVISION)		
	1-254883		20/04 Site Rental	$295.38
Total EFT000000013199				**$295.38**
EFT000000013203	2020-04-20	CANADIAN TIRE		
	133868		9X Totes+ Batteries	$262.44
	137288		3X Totes + 6X Bags	$131.18
Total EFT000000013203				**$393.62**
EFT000000013205	2020-04-20	COLLINS SAFETY INC.		
	246640		29X Gloves + 71X Hoods	$1,176.80
Total EFT000000013205				**$1,176.80**
EFT000000013211	2020-04-20	DARCH FIRE		
	CI30000872		Nozzle	$371.42
Total EFT000000013211				**$371.42**
EFT000000013215	2020-04-20	EARL ROSEBUSH FUELS		
	0647-108060		669.00L @.755	$550.54
	4896-106927		240.50L @.747	$195.95
	4896-109623		480.20L @.769	$402.02
	1057-115721		333.70L @.564	$218.86
	3935-115731		251.40L @.564	$164.88
	0647-111902		906.70L @.711	$705.55
	1057-106876		497.50L @.747	$405.36
	1057-108036		515.30L @.770	$431.92
	1057-110573		661.50L @.748	$539.64
	1057-111875		474.60L @.730	$378.48
	1057-116409		149.30L @.574	$99.43
	2706-106890		283.10L @.733	$226.62
	2706-108044		245.60L @.770	$205.86
	2706-110582		347.60L @.748	$283.58
	3935-106924		407.90L @.760	$337.75
	3935-109622		210.10L @.769	$175.89
	4896-111910		439.30L @.710	$341.39
Total EFT000000013215				**$5,663.72**
EFT000000013218	2020-04-20	FIRE SERVICE MANAGEMENT		
	442500		Wash + Repair	$498.93
	442508		Freight	$224.38
Total EFT000000013218				**$723.31**
EFT000000013224	2020-04-20	KENWORTH ONTARIO - KINGSTON		
	KS27473		Alternator	$1,243.71
	KS27544		Replace Exhaust Pipe	$413.46
Total EFT000000013224				**$1,657.17**
EFT000000013225	2020-04-20	MESSER CANADA INC.		
	2102130124		Oxygen	$405.95
	2102158019		Cylinder Utilization Fee	$76.32
Total EFT000000013225				**$482.27**
EFT000000013229	2020-04-20	R. THURSTON TECHNOLOGIES		
	11556		20/04-20/06 Site Rental	$381.60
	11557		Repeater in Pumper 311	$2,890.69
	11561		Repeater	$2,890.69
Total EFT000000013229				**$6,162.98**
EFT000000013235	2020-04-20	TOTAL POWER LTD		
	86831		Annual Inspection	$872.08
Total EFT000000013235				**$872.08**
EFT000000013237	2020-04-20	TROUSDALE'S HOME HARDWARE		
	102457		Screws for Door	$4.66
Total EFT000000013237				**$4.66**
EFT000000013240	2020-04-20	UNIVERSAL SUPPLY GROUP		
	896-976162		12X Disposable Respirators	$251.30
Total EFT000000013240				**$251.30**
EFT000000013242	2020-04-20	WESTPORT HOME HARDWARE		
	1160		Hooks+ Screws+Brackets	$49.62
Total EFT000000013242				**$49.62**
EFT000000013249	2020-05-01	12 VOLT DOES IT		
	26		Lights + Sirens	$2,577.07
	31		Lighting repair	$223.87
	32		Speaker	$264.58
Total EFT000000013249				**$3,065.52**
EFT000000013256	2020-05-01	CANADIAN SAFETY EQUIPMENT		

		46230-1	300X Decon Bags	$953.49
Total EFT000000013256				**$953.49**
EFT000000013259	2020-05-01		COMMERCIAL DOOR SYSTEMS LTD.	
		41063	Remote + Programmed	$137.38
Total EFT000000013259				**$137.38**
EFT000000013261	2020-05-01		CULLIGAN	
		2700275	Water	$65.29
Total EFT000000013261				**$65.29**
EFT000000013262	2020-05-01		CUNNINGHAM SWAN CARTY	
		163521	Legal Services- Employment	$467.08
Total EFT000000013262				**$467.08**
EFT000000013264	2020-05-01		EARL ROSEBUSH FUELS	
		1057-117205	288.8L @.515	$175.01
		1058-117203	921.50L @.535	$577.16
		2706-117210	301.60L @.551	$193.81
		4896-116422	244.10L @.558	$158.60
Total EFT000000013264				**$1,104.58**
EFT000000013273	2020-05-01		LONDRY ALARMS	
		200716	Alarm Service Call	$201.48
Total EFT000000013273				**$201.48**
EFT000000013281	2020-05-01		SUPERIOR PROPANE INC.	
		29448519	Tank Rental	$0.91
Total EFT000000013281				**$0.91**
EFT000000013289	2020-05-01		WESTPORT HOME HARDWARE	
		20587	Cleaning Supplies	$36.26
Total EFT000000013289				**$36.26**
EFT000000013297	2020-05-15		ABELL PEST CONTROL INC.	
		A2749274	20/04 Pest Control	$48.54
Total EFT000000013297				**$48.54**
EFT000000013300	2020-05-15		ASSELSTINE HARDWARE	
		7174	White Paint	$41.30
Total EFT000000013300				**$41.30**
EFT000000013303	2020-05-15		BELL MOBILITY (RADIO DIVISION)	
		1-255291	20/05 Site Rental	$295.38
Total EFT000000013303				**$295.38**
EFT000000013317	2020-05-15		EARL ROSEBUSH FUELS	
		0647-117875	723.20L @ .510	$434.57
		1058-118626	568.00L @.435	$297.95
		3935-118222	287.40L @.435	$150.76
Total EFT000000013317				**$883.28**
EFT000000013321	2020-05-15		FIRE SERVICE MANAGEMENT	
		442599	Wash + Repair	$1,047.29
Total EFT000000013321				**$1,047.29**
EFT000000013323	2020-05-15		FORT GARRY FIRE TRUCKS LTD	
		32444	Tanker Chassis	$148,653.04
Total EFT000000013323				**$148,653.04**
EFT000000013332	2020-05-15		JODY CAMPBELL'S SEPTIC SERVICE	
		16774	Portable Toilet Rental	$101.76
Total EFT000000013332				**$101.76**
EFT000000013333	2020-05-15		LEONARD, ELIZABETH	
		20/03/20-16	Cleaning	$60.00
		20/04/15-13	Cleaning	$60.00
Total EFT000000013333				**$120.00**
EFT000000013335	2020-05-15		MESSER CANADA INC.	
		2102237901	Oxygen	$450.80
Total EFT000000013335				**$450.80**
EFT000000013336	2020-05-15		LONDRY ALARMS	
		202249	Alarm Repair	$148.57
Total EFT000000013336				**$148.57**
EFT000000013342	2020-05-15		R&D NELSON GENERAL MAINTENANCE	
		20/04-PRFH	20/03+20/04 General Maint.	$274.75
		20/04-PRFH	20/03+20/04 General Maint.	$76.51
Total EFT000000013342				**$351.26**
EFT000000013343	2020-05-15		RICOH CANADA INC.	
		SC092777163	20/03 Copier Usage + Rental	$106.23
Total EFT000000013343				**$106.23**
EFT000000013347	2020-05-15		R. THURSTON TECHNOLOGIES	
		11567	Radio + Antenna	$542.18
Total EFT000000013347				**$542.18**
EFT000000013352	2020-05-15		SWISH MAINTENANCE LIMITED	
		K632916	Gloves	$325.02
Total EFT000000013352				**$325.02**
EFT000000013353	2020-05-15		TOWN AND COUNTRY AUTO SUPPLY	
		6083-593391	Strobe Light	$152.96
		6083-593670	Circuit Tester	$14.24
Total EFT000000013353				**$167.20**
EFT000000013354	2020-05-15		TRIM-LINE OF SOUTH EAST	
		49138	Logos + Striping	$345.98
Total EFT000000013354				**$345.98**
EFT000000013362	2020-05-29		BOULTON SEPTIC/LARMON'S	
		31800	Snow Plowing	$45.79
Total EFT000000013362				**$45.79**
EFT000000013363	2020-05-29		ABELL PEST CONTROL INC.	
		A278188	20/05 Pest Control	$41.18
		A2784677	20/05 Pest Control	$50.80
Total EFT000000013363				**$91.98**
EFT000000013364	2020-05-29		ALLIED MEDICAL INSTRUMENTS INC	
		504581	100X Face Shield	$328.89
		504942	4X BP Units	$123.23

Total EFT000000013364					**$452.12**
EFT000000013378	2020-05-29		EARL ROSEBUSH FUELS		
		2706-122414		295.40L @.426	$152.25
		1057-123133		12.90L @.455	$7.03
Total EFT000000013378					**$159.28**
EFT000000013380	2020-05-29		FIRE SERVICE MANAGEMENT		
		442600		Freight	$224.38
Total EFT000000013380					**$224.38**
EFT000000013381	2020-05-29		FIRE MARSHAL'S PUBLIC FIRE		
		IN156813		10X Books	$604.79
Total EFT000000013381					**$604.79**
EFT000000013387	2020-05-29		HAMILL FORESTRY PRODUCTS		
		387560		Tubgrinder Rental	$7,479.36
Total EFT000000013387					**$7,479.36**
EFT000000013388	2020-05-29		JODY CAMPBELL'S SEPTIC SERVICE		
		17058		20/06 Portable Toilet Rental	$101.76
Total EFT000000013388					**$101.76**
EFT000000013392	2020-05-29		LEONARD FUELS		
		62279C		Service Call- Furnace	$174.01
Total EFT000000013392					**$174.01**
EFT000000013401	2020-05-29		ROSESON DISTRIBUTORS INC.		
		1057-13465		42.91L @.9791	$42.76
		1057-13688		99.01L @.7844	$79.03
		1057-13904		80.00L @.6340	$51.61
		1057-13950		87.53L @.7579	$67.51
		1057-14013		Gas+Premium + Tru Fuel	$110.15
Total EFT000000013401					**$351.06**
EFT000000013402	2020-05-29		R. THURSTON TECHNOLOGIES		
		11576		2X Repeaters	$5,781.37
Total EFT000000013402					**$5,781.37**
EFT000000013410	2020-05-29		TOWN AND COUNTRY AUTO SUPPLY		
		6083-594122		2X Bulbs	$12.74
		6083-595072		Stabil Marine Formula	$89.32
		6083-595083		Stabil Marine Formula	$89.32
Total EFT000000013410					**$191.38**
EFT000000013411	2020-05-29		TROUSDALE'S FOODLAND		
		10027		Water	$89.70
Total EFT000000013411					**$89.70**
Total Fire					**$336,247.73**

2110 Cvc#

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013349	2020-05-15		SIGNS PLUS		
		3183		2X Civic Blades	$18.32
		3185		2X Civic Blades	$18.32
Total EFT000000013349					**$36.64**
EFT000000013403	2020-05-29		SIGNS PLUS		
		3187		12X Civic Blades	$109.90
Total EFT000000013403					**$109.90**
Total Cvc#					**$146.54**

2400 Police

Cheque	Date	Inv #	Vendor	Description	Amount
070880	2020-04-03		MINISTER OF FINANCE-POLICE SERVICES		
		101603201409099		20/03 Policing Services	$252,881.00
Total 070880					**$252,881.00**
Total Police					**$252,881.00**

2410 Ride Program

Cheque	Date	Inv #	Vendor	Description	Amount
070880	2020-04-03		MINISTER OF FINANCE-POLICE SERVICES		
		101703201111036		OPP Wages	$590.08
Total 070880					**$590.08**
Total Ride Program					**$590.08**

2605 Build

Cheque	Date	Inv #	Vendor	Description	Amount
070845	2020-03-18		CITYVIEW		
		CT045598		Cityview	$220,185.24
Total 070845					**$220,185.24**
EFT000000013118	2020-03-27		INDEPENDENT TELEPHONE SERVICES		
		44866		Telephone Programming	$356.16
		44883		Voicemail to Email	$43.25
		44867		Forward 2226- 2236	$86.50
Total EFT000000013118					**$485.91**
EFT000000013213	2020-04-20		D.MARTIN WELDING & FABRICATING		
		9669		Fabricate SS Box	$1,011.50
Total EFT000000013213					**$1,011.50**
EFT000000013222	2020-04-20		INDEPENDENT TELEPHONE SERVICES		
		44892		Telephone Programming	$86.50
Total EFT000000013222					**$86.50**
EFT000000013247	2020-04-22		TOWN & COUNTRY CHRYSLER LTD		
		41966		2020 Jeep Cherokee	$45,152.95
Total EFT000000013247					**$45,152.95**
EFT000000013410	2020-05-29		TOWN AND COUNTRY AUTO SUPPLY		

		6083-596188	Oil	$38.41
		6083-596188	Filter	$6.55
Total EFT000000013410				**$44.96**
Total Build				**$266,967.06**

2620 Anml Ctl

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013096	2020-03-30		FRONTENAC MUNICIPAL LAW		
		SF-AC-2020-MARCH		20/03 Animal Control	$3,256.19
Total EFT000000013096					**$3,256.19**
EFT000000013122	2020-03-27		KINGSTON HUMANE SOCIETY		
		SF_KHS POUND_20-02		20/02 Pound Services	$1,569.00
		SF_KHS POUND_20-02		20/02 Pound Services	$15.00
		SF_KHS POUND_20-01		20/01 Pound Services	$1,569.00
		SF_KHS POUND_20-01		20/01 Pound Services	$24.00
Total EFT000000013122					**$3,177.00**
EFT000000013293	2020-04-30		FRONTENAC MUNICIPAL LAW		
		SF-AC-2020-APRIL		20/03 Animal Control	$3,256.19
Total EFT000000013293					**$3,256.19**
EFT000000013382	2020-05-29		FRONTENAC MUNICIPAL LAW		
		SF-AC-2020-MAY		20/05 Animal Control	$3,256.19
Total EFT000000013382					**$3,256.19**
Total Anml Ctl					**$12,945.57**

2640 Bylaw enf

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013096	2020-03-30		FRONTENAC MUNICIPAL LAW		
		SF-P-2020-MARCH		20/03 Parking	$457.92
		SF-P-2020-MARCH		20/03 Parking	$634.98
Total EFT000000013096					**$1,092.90**
EFT000000013293	2020-04-30		FRONTENAC MUNICIPAL LAW		
		SF-P-2020-APRIL		20/04 Parking	$457.92
		SF-P-2020-APRIL		20/04 Parking	$634.98
Total EFT000000013293					**$1,092.90**
EFT000000013344	2020-05-15		RIVOIRE, THOMAS R		
		46		Legal Services -Dog at large	$508.80
Total EFT000000013344					**$508.80**
EFT000000013382	2020-05-29		FRONTENAC MUNICIPAL LAW		
		SF-P-2020-MAY		20/05 Parking	$457.92
		SF-P-2020-MAY		20/05 Parking	$634.98
Total EFT000000013382					**$1,092.90**
Total Bylaw enf					**$3,787.50**
Total PP&P					**$873,565.48**

30 Trans

3000 PW OH

Cheque	Date	Inv #	Vendor	Description	Amount
070891	2020-04-20		BRENNAN, STEPHEN		
		2020 BUMPER		Damaged Bumpers	$3,014.16
Total 070891					**$3,014.16**
EFT000000013197	2020-04-20		ALLIANCE WIRELESS COMMUNICATIONS		
		C14258-040120		20/04 Answering Service	$315.80
Total EFT000000013197					**$315.80**
EFT000000013219	2020-04-20		GRAND & TOY LIMITED		
		P832321		Cleaning Supplies	$117.96
Total EFT000000013219					**$117.96**
EFT000000013299	2020-05-15		ALLIANCE WIRELESS COMMUNICATIONS		
		C14258-050120		20/05 Answering Service	$237.50
Total EFT000000013299					**$237.50**
EFT000000013320	2020-05-15		ESKEROD SIGNS		
		28816		Covid 19 - Closed Signs	$479.29
Total EFT000000013320					**$479.29**
EFT000000013343	2020-05-15		RICOH CANADA INC.		
		SC092777163		20/03 Copier Usage + Rental	$119.99
Total EFT000000013343					**$119.99**
Total PW OH					**$4,284.70**

3005 RdAdmOH

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013199	2020-04-20		BELL MOBILITY (RADIO DIVISION)		
		1-254883		20/04 Site Rental	$295.38
Total EFT000000013199					**$295.38**
EFT000000013303	2020-05-15		BELL MOBILITY (RADIO DIVISION)		
		1-255291		20/05 Site Rental	$295.38
Total EFT000000013303					**$295.38**
EFT000000013330	2020-05-15		INDEPENDENT TELEPHONE SERVICES		
		44996		VM to Email A.H.	$86.50
Total EFT000000013330					**$86.50**
Total RdAdmOH					**$677.26**

3010

Cheque	Date	Inv #	Vendor	Description	Amount

070860	2020-03-27		ATCO CHEMICAL CORP.	
		I0007498	Quickies	$163.39
Total 070860				**$163.39**
070861	2020-03-27		ATKINSON HOME BUILDING CENTRE	
		254111	Broom + Tape Measure	$69.18
Total 070861				**$69.18**
070869	2020-03-27		VERONA FOODLAND	
		1649	8X Disinfecting Wipes	$24.34
Total 070869				**$24.34**
070875	2020-04-03		ATCO CHEMICAL CORP.	
		I0007505	Quickies	$636.07
Total 070875				**$636.07**
070876	2020-04-03		DAVE BENNETT MOBILE AUTOGLASS	
		1151	Windshield+Moulding	$417.22
		1154	Windshield+Moulding	$417.22
Total 070876				**$834.44**
070877	2020-04-03		DOUG'S AUTO PARTS LTD	
		402046	Wheel	$127.20
Total 070877				**$127.20**
070878	2020-04-03		THE HYDRAULIC CO.	
		18500	Dump Cylinder	$2,441.22
Total 070878				**$2,441.22**
070884	2020-04-03		VERONA FOODLAND	
		2997	Water	$54.90
Total 070884				**$54.90**
070885	2020-04-03		VERONA CONVENIENCE PIZZA & SUB	
		20/03/13	Cleaning Supplies	$41.64
Total 070885				**$41.64**
070923	2020-05-29		ATKINSON HOME BUILDING CENTRE	
		261125	Duct Tape	$10.17
		263244	Batteries	$25.15
Total 070923				**$35.32**
070925	2020-05-29		DAVE BENNETT MOBILE AUTOGLASS	
		1211	2X Windshield	$895.49
Total 070925				**$895.49**
070929	2020-05-29		MIKAELA HUGHES ARCHITECT INC.	
		1911-02	Architectural Fees	$18,129.82
Total 070929				**$18,129.82**
070930	2020-05-29		SNC-LAVALIN GEM ONTARIO INC.	
		1487351	Compaction + Concrete Testing	$1,078.66
Total 070930				**$1,078.66**
070931	2020-05-29		SNIDER, PERCY	
		20/01/14-44	Triaxle Rental	$358.19
Total 070931				**$358.19**
EFT000000013100	2020-03-27		ABELL PEST CONTROL INC.	
		A2697399	Pest Control	$72.85
Total EFT000000013100				**$72.85**
EFT000000013101	2020-03-27		AINLEY GRAHAM & ASSOCIATES LTD	
		19593-1-3	Consulting	$13,615.49
Total EFT000000013101				**$13,615.49**
EFT000000013109	2020-03-27		CINTAS	
		4045084480	Uniform	$40.00
		4045084480	Cleaning Supplies	$115.81
		4045084539	Uniform	$10.16
		4045084539	Cleaning Supplies	$32.37
Total EFT000000013109				**$198.34**
EFT000000013114	2020-03-27		DRAPER DOORS	
		20242	Service Call-Door Not Closing	$91.58
Total EFT000000013114				**$91.58**
EFT000000013134	2020-03-27		ROSESON DISTRIBUTORS INC.	
		1058-12729	61.87L @ .9614	$60.53
		1058-12684	79.60L @.9614	$77.88
		1058-12604	59.71L @.9260	$56.26
		1058-12532	59.71L @.9260	$94.08
		1058-12497	59.71L @.9260	$66.10
		1058-12468	81.36L @.9326	$77.21
		1058-12441	82.94L @.8995+ 15.55L @1.0499	$92.53
		1058-12750	98.00L @.9414	$93.88
		1058-12762	68.45L @.9614	$66.97
		1058-12855	79.00L @1.0411	$83.69
		1058-13186	73.00L @.9968	$74.05
		1058-13161	100.00L @.9968	$101.43
Total EFT000000013134				**$944.61**
EFT000000013138	2020-03-27		TOWN AND COUNTRY AUTO SUPPLY	
		6083-587246	Air Hose	$293.98
		6083-587872	Oxygen Sensor	$57.93
		6083-587733	Oil	$141.95
		6083-587733	Filter	$9.22
		6083-587871	Battery	$230.40
		6083-588511	2X Caliper	$428.84
		6083-588488	Brake Pads+Rotors+ Sealant	$353.84
Total EFT000000013138				**$1,516.16**
EFT000000013139	2020-03-27		TROUSDALE'S FOODLAND	
		6313	Coffee+ Mate+ Sugar	$48.03
		6645.	Cleaning Supplies	$154.23
		1633..	Coffee + Mate	$33.95
Total EFT000000013139				**$236.21**
EFT000000013140	2020-03-27		TROUSDALE'S HOME HARDWARE	
		101924	Paper Towels	$40.65
		227898	Cleaning Supplies	$280.57

Total EFT000000013140				**$321.22**
EFT000000013142	2020-03-27		UNIVERSAL SUPPLY GROUP	
		173-264311	Pipes	$241.01
		173-264333	Pipe	$74.27
		173-264333	Pipe	$95.63
Total EFT000000013142				**$410.91**
EFT000000013147	2020-04-03		BATTLEFIELD EQUIPMENT RENTALS	
		24236482	Paint+ Measuring Wheel+ Brooms	$176.53
		24236482	Paint+ Measuring Wheel+ Brooms	$176.53
Total EFT000000013147				**$353.06**
EFT000000013148	2020-04-03		BENSON TRUCK & TRAILER	
		16102899	Repair RF Spring	$959.27
Total EFT000000013148				**$959.27**
EFT000000013149	2020-04-03		BLACK DOG TIRE & LUBRICANTS	
		40526	Tire Rotation	$122.11
Total EFT000000013149				**$122.11**
EFT000000013153	2020-04-03		CINTAS	
		4045691290	Uniform	$40.00
		4045691290	Cleaning Supplies	$151.04
		4045691291	Uniform	$10.16
		4045691291	Cleaning Supplies	$32.37
Total EFT000000013153				**$233.57**
EFT000000013154	2020-04-03		COMMERCIAL DOOR SYSTEMS LTD.	
		40885	Set up Timer on Gate	$152.64
Total EFT000000013154				**$152.64**
EFT000000013156	2020-04-03		CROSSIRON TRUCK & EQUIPMENT	
		W 1920	Injector	$4,453.26
Total EFT000000013156				**$4,453.26**
EFT000000013161	2020-04-03		EARL ROSEBUSH FUELS	
		1058-113685	738.20L @.579	$475.29
		0646-113732	588.30L @.608	$396.14
Total EFT000000013161				**$871.43**
EFT000000013165	2020-04-03		GRAND & TOY LIMITED	
		P800481	Cleaning Supplies	$35.53
		P800481	Office Supplies	$85.38
Total EFT000000013165				**$120.91**
EFT000000013172	2020-04-03		KENT AUTOMOTIVE	
		9307467808	43 Series Fittings	$239.61
Total EFT000000013172				**$239.61**
EFT000000013175	2020-04-03		MCNICHOLS CONSTRUCTION LTD	
		20/03/09	Floating	$305.28
		20/03/09	Floating	$305.28
		20/03/17	Float from Crossiron	$305.28
Total EFT000000013175				**$915.84**
EFT000000013176	2020-04-03		PAT'S RADIATOR SERVICE LTD.	
		145260	Recore Radiator	$2,914.20
Total EFT000000013176				**$2,914.20**
EFT000000013177	2020-04-03		PETRIE FORD	
		285313	Antifreeze	$59.02
Total EFT000000013177				**$59.02**
EFT000000013178	2020-04-03		PUROLATOR INC.	
		444168266	Shipping of Hand Wipes	$70.49
Total EFT000000013178				**$70.49**
EFT000000013179	2020-04-03		RIGNEY BUILDING SUPPLIES	
		INA210636	Insulated Tarp	$95.71
Total EFT000000013179				**$95.71**
EFT000000013181	2020-04-03		SELECT DOOR AND FRAME	
		SI000718	Hardware Installed	$2,193.32
Total EFT000000013181				**$2,193.32**
EFT000000013183	2020-04-03		SWISH MAINTENANCE LIMITED	
		K630883	2X Garbage Bags	$63.09
		K631064	Cleaning Supplies	$149.04
		K630311	Gloves + Wipes	$23.17
		K630311	Gloves + Wipes	$23.17
		K630311	Gloves + Wipes	$23.16
		K630550	Wipes	$136.36
		K630550	Wipes	$136.36
		K630550	Wipes	$136.36
Total EFT000000013183				**$690.71**
EFT000000013184	2020-04-03		TOROMONT INDUSTRIES LTD.	
		PS040672094	Parts for Roller	$354.42
Total EFT000000013184				**$354.42**
EFT000000013185	2020-04-03		TOWN AND COUNTRY AUTO SUPPLY	
		6083-589435	Filter	$6.17
		6083-589435	Filter	$6.17
		6083-589435	Filter	$6.16
		6083-589435	Oil	$38.72
		6083-589435	Oil	$38.71
		6083-589435	Bulb	$10.52
		6083-589435	Bulbs	$42.08
Total EFT000000013185				**$148.53**
EFT000000013186	2020-04-03		TROUSDALE'S FOODLAND	
		153	Coffee + Cream	$15.68
		5855	Water	$39.92
Total EFT000000013186				**$55.60**
EFT000000013187	2020-04-03		TROUSDALE'S HOME HARDWARE	
		102057	Screen Door Closer	$20.34
		102101	Cleaning Supplies	$121.90
Total EFT000000013187				**$142.24**
EFT000000013189	2020-04-03		UNIVERSAL SUPPLY GROUP	

		173-265263	Piggy Back Kits+ Clamp	$83.09
		173-265263	2X Piggy Back Kits+5X Clamps	$192.62
Total EFT000000013189				**$275.71**
EFT000000013190	2020-04-03	VERONA HARDWARE LIMITED		
		101042197	Cleaning Supplies	$42.64
Total EFT000000013190				**$42.64**
EFT000000013196	2020-04-20	AIR LIQUIDE CANADA INC.		
		71284988	Oxygen	$35.32
Total EFT000000013196				**$35.32**
EFT000000013200	2020-04-20	BLACK DOG TIRE & LUBRICANTS		
		40471	4X Tires	$973.84
Total EFT000000013200				**$973.84**
EFT000000013204	2020-04-20	CINTAS		
		4046935342	Uniform	$10.16
		4046935342	Cleaning Supplies	$42.68
		4046935354	Uniform	$40.00
		4046935354	Cleaning Supplies	$1,133.62
Total EFT000000013204				**$1,226.46**
EFT000000013214	2020-04-20	DRAPER DOORS		
		20249	Replace Door Operator	$1,526.40
Total EFT000000013214				**$1,526.40**
EFT000000013215	2020-04-20	EARL ROSEBUSH FUELS		
		0646-108114	442.90L @.761	$367.18
		0646-110626	516.20L @.777	$436.36
		3160-114749	333.90L @ .607	$224.49
		4185-109643	594.00L @1.049	$666.53
		4185-115743	570.40L @.939	$576.21
		0646-116431	469.80L @.553	$302.86
		3160-106925	378.60L @.760	$313.49
		3160-110600	382.20L @.748	$311.80
Total EFT000000013215				**$3,198.92**
EFT000000013220	2020-04-20	HD SUPPLY CANADA, INC		
		109100687	Carabiner	$77.37
Total EFT000000013220				**$77.37**
EFT000000013225	2020-04-20	MESSER CANADA INC.		
		2102125012	Oxygen + Acetylene	$25.01
		2102131749	Gases	$251.91
		2102158138	Cylinder Utilization Fee	$49.86
Total EFT000000013225				**$326.78**
EFT000000013230	2020-04-20	SAFETY-KLEEN CANADA, INC.		
		82457011	Parts Cleaner	$465.09
Total EFT000000013230				**$465.09**
EFT000000013232	2020-04-20	SIMMONS PLUMBING & PUMP SERV.		
		6068	Service Call- Boiler	$114.48
Total EFT000000013232				**$114.48**
EFT000000013234	2020-04-20	TOROMONT INDUSTRIES LTD.		
		PS040672155	2X Filters	$180.82
Total EFT000000013234				**$180.82**
EFT000000013236	2020-04-20	TROUSDALE'S FOODLAND		
		7271	Cream + Tissues	$13.16
Total EFT000000013236				**$13.16**
EFT000000013237	2020-04-20	TROUSDALE'S HOME HARDWARE		
		228324	Batteries	$112.87
Total EFT000000013237				**$112.87**
EFT000000013240	2020-04-20	UNIVERSAL SUPPLY GROUP		
		173-266093	LED Lights+Grommets+AmberDome	$318.90
		173-266093	LED Lights+Grommets	$115.56
		173-265757	DEF+Rotary Pump Manual	$367.32
Total EFT000000013240				**$801.78**
EFT000000013244	2020-04-20	WURTH CANADA LIMITED		
		23796610	Premium Nitrile Gloves	$127.14
Total EFT000000013244				**$127.14**
EFT000000013251	2020-05-01	AINLEY GRAHAM & ASSOCIATES LTD		
		19593-1-2	Consulting	$2,442.24
Total EFT000000013251				**$2,442.24**
EFT000000013253	2020-05-01	BENSON TRUCK & TRAILER		
		16103202	Leaf Spring + Repairs	$1,545.14
Total EFT000000013253				**$1,545.14**
EFT000000013254	2020-05-01	BLACK DOG TIRE & LUBRICANTS		
		41330	Service Call- Flat Repair	$116.01
		41339	Service Call- Flat Repair	$79.37
Total EFT000000013254				**$195.38**
EFT000000013259	2020-05-01	COMMERCIAL DOOR SYSTEMS LTD.		
		41063	Remote + Programmed	$137.38
Total EFT000000013259				**$137.38**
EFT000000013260	2020-05-01	CROSSIRON TRUCK & EQUIPMENT		
		W 2063	Service + Inspection	$2,462.52
		W 2066	Service + Inspection	$3,362.32
		W 2093	Loose Terminals+ Air Leak	$351.01
		W 2135	2500 Hour Service	$2,723.72
		W 2136	Safety Inspection + Repairs	$6,835.81
Total EFT000000013260				**$15,735.38**
EFT000000013268	2020-05-01	HP ENGINEERING		
		920035	Engineering Services	$679.25
		920035	Engineering Services	$11,809.76
Total EFT000000013268				**$12,489.01**
EFT000000013269	2020-05-01	HYDRO ONE		
		3000288779	Hydro Work	$3,130.28
Total EFT000000013269				**$3,130.28**
EFT000000013272	2020-05-01	LEONARD FUELS		

		0646-62307	Nozzle+ Cleaned out Furnace	$125.16
Total EFT000000013272				**$125.16**
EFT000000013274	2020-05-01		NORTHWAY HARDWARE	
		23700	Cleaning Supplies	$147.17
		23701	Canadian Flag	$36.62
Total EFT000000013274				**$183.79**
EFT000000013275	2020-05-01		PETRIE FORD	
		286389	Oil + Brake Cleaner	$118.99
Total EFT000000013275				**$118.99**
EFT000000013277	2020-05-01		PREMIER TRUCK GROUP	
		864143590	Head	$121.33
Total EFT000000013277				**$121.33**
EFT000000013283	2020-05-01		SYDENHAM LANDSCAPE PRODUCTS	
		4993	Grass Seed	$151.62
Total EFT000000013283				**$151.62**
EFT000000013284	2020-05-01		TOROMONT INDUSTRIES LTD.	
		PS040672619	Tie Rod	$733.56
Total EFT000000013284				**$733.56**
EFT000000013285	2020-05-01		TOWN AND COUNTRY AUTO SUPPLY	
		6083-592564	Oil	$38.72
		6083-592564	Oil	$77.42
		6083-592564	Filters	$12.19
		6083-592564	Filter	$6.16
		6083-592642	Oil	$289.32
		6083-592646	Filter	$9.50
		6083-592646	Transmission Fluid	$41.58
		6083-593015	4X Thread Sealant	$85.77
Total EFT000000013285				**$560.66**
EFT000000013287	2020-05-01		TROUSDALE'S HOME HARDWARE	
		228408	Bags + Nozzle + Cleaner	$136.13
		228653	2X Rust Killer Primer	$38.65
Total EFT000000013287				**$174.78**
EFT000000013288	2020-05-01		UNIVERSAL SUPPLY GROUP	
		173-268410	3X Air Brake Tube	$22.77
Total EFT000000013288				**$22.77**
EFT000000013298	2020-05-15		AIR LIQUIDE CANADA INC.	
		71380039	Oxygen	$34.19
Total EFT000000013298				**$34.19**
EFT000000013304	2020-05-15		BENSON TRUCK & TRAILER	
		16103281	Alignment	$632.53
Total EFT000000013304				**$632.53**
EFT000000013305	2020-05-15		BLACK DOG TIRE & LUBRICANTS	
		39298	Replace Sensor	$50.82
Total EFT000000013305				**$50.82**
EFT000000013309	2020-05-15		CINTAS	
		4049215177	Uniform	$10.16
		4049215177	Cleaning Supplies	$81.93
		4049215205	Uniform	$40.00
		4049215205	Cleaning Supplies	$275.64
		4046317918	Uniform	$40.00
		4046317918	Cleaning Supplies	$115.81
		4046317957	Uniform	$10.16
		4046317957	Cleaning Supplies	$32.37
		4047503642	Uniform	$40.00
		4047503642	Cleaning Supplies	$115.81
		4047503653	Uniform	$10.16
		4047503653	Cleaning Supplies	$32.37
		4048066393	Uniform	$10.16
		4048066393	Cleaning Supplies	$32.37
		4048066444	Uniform	$40.00
		4048066444	Cleaning Supplies	$95.39
		4048659284	Uniform	$10.16
		4048659284	Cleaning Supplies	$32.37
		4048659329	Uniform	$40.00
		4048659329	Cleaning Supplies	$95.32
Total EFT000000013309				**$1,160.18**
EFT000000013313	2020-05-15		CROSSIRON TRUCK & EQUIPMENT	
		W 2137	Safety + Repairs	$3,537.54
		W 2180	Coolant Leak	$1,469.03
		W 2183	Full Major Service	$4,874.59
		W 2164	Service Call	$343.95
Total EFT000000013313				**$10,225.11**
EFT000000013317	2020-05-15		EARL ROSEBUSH FUELS	
		1058-106875	852.90L @.76	$706.21
		1058-108037	612.00L @.755	$503.63
		1058-110574	768.70L @1.049	$862.57
		1058-111877	565.60L @.710	$439.54
Total EFT000000013317				**$2,511.95**
EFT000000013322	2020-05-15		FISH, DOROTHY	
		43179	Cleaning	$164.00
Total EFT000000013322				**$164.00**
EFT000000013326	2020-05-15		GRAND & TOY LIMITED	
		P926761	Office Supplies	$118.41
Total EFT000000013326				**$118.41**
EFT000000013331	2020-05-15		J.L. RICHARDS & ASSOCIATES LIMITED	
		92248	20/03 Engineering Services	$1,076.11
Total EFT000000013331				**$1,076.11**
EFT000000013333	2020-05-15		LEONARD, ELIZABETH	
		20/03/28-17	Cleaning	$300.00
		20/04/25-15	Cleaning	$300.00
Total EFT000000013333				**$600.00**

EFT000000013335	2020-05-15		MESSER CANADA INC.	
		2102238597	Gases	$251.91
		2102265725	Cylinder Utilization Fees	$49.86
Total EFT000000013335				**$301.77**
EFT000000013341	2020-05-15		PREMIER TRUCK GROUP	
		864143939	Lamp Assy + Side Turn Lens	$52.10
Total EFT000000013341				**$52.10**
EFT000000013342	2020-05-15		R&D NELSON GENERAL MAINTENANCE	
		20/04-G,B.P	20/03+20/04 General Maint.	$195.38
		20/04-G,B.P	20/03+20/04 General Maint.	$195.38
		20/04-G,B.P	20/03+20/04 General Maint.	$139.32
		20/04-G,B.P	20/03+20/04 General Maint.	$139.32
Total EFT000000013342				**$669.40**
EFT000000013346	2020-05-15		ROSESON DISTRIBUTORS INC.	
		1058-13280	104.01L @.9349	$98.94
		1058-13300	10.00L @1.0765- Chainsaw	$10.96
		1058-13316	47.00L @.9083	$43.44
		1058-13379	97.26L @.8906	$88.14
		1058-13438	70.98L @.8706	$62.88
		1058-13477	88.70L @.8640	$77.99
		1058-13503	40.84L @.8640	$35.91
		1058-13561	61.91L @.8640	$54.43
		1058-13573	51.60L @.8375	$43.97
		1058-13674	67.72L @.8375	$57.71
		1058-13720	76.40L @.7313	$56.85
		1058-13743	47.00L @.7313	$34.97
		1058-13840	41.51L @.6694	$28.28
		1058-13865	76.00L @.6517	$50.40
		1058-13921	76.00L @.6517	$59.36
		1058-13963	50.54L @.5986	$30.78
		1058-13784	63.01L @.6871	$44.05
Total EFT000000013346				**$879.06**
EFT000000013355	2020-05-15		TROUSDALE'S FOODLAND	
		3583	Water	$29.90
		10137	Tissues+ Coffee+ Cream	$18.11
Total EFT000000013355				**$48.01**
EFT000000013356	2020-05-15		TROUSDALE'S HOME HARDWARE	
		102286	Cleaning Supplies	$76.26
		102742	Shovel + Rake	$217.69
Total EFT000000013356				**$293.95**
EFT000000013361	2020-05-15		TOMLINSON ENVIRONMENTAL SERVICES	
		2010003PPC2	Payment Cert. #2	$409,756.57
Total EFT000000013361				**$409,756.57**
EFT000000013365	2020-05-29		ARMTEC CANADA CULVERT	
		6-201976	Culverts	$22,207.61
		6-202292	Culverts + Couplers	$20,849.27
Total EFT000000013365				**$43,056.88**
EFT000000013366	2020-05-29		BATTLEFIELD EQUIPMENT RENTALS	
		24237838	Rock Bits+ Air tool oil	$464.74
Total EFT000000013366				**$464.74**
EFT000000013367	2020-05-29		BLACK DOG TIRE & LUBRICANTS	
		41713	Tire Change + 6X Rims	$2,067.39
Total EFT000000013367				**$2,067.39**
EFT000000013370	2020-05-29		CINTAS	
		4049788032	Uniform	$10.16
		4049788032	Cleaning Supplies	$32.37
		4049788062	Uniform	$40.00
		4049788062	Cleaning Supplies	$115.81
Total EFT000000013370				**$198.34**
EFT000000013371	2020-05-29		CITY ELECTRIC SUPPLY	
		KIN/103563	2X Exit Signs	$264.47
Total EFT000000013371				**$264.47**
EFT000000013372	2020-05-29		COLLINS SAFETY INC.	
		247317	Lens Cleaning Tissues	$18.30
Total EFT000000013372				**$18.30**
EFT000000013375	2020-05-29		DEDICATED ENVIRONMENTAL SERVICES INC	
		3950	Cleanout Oil/Water Seperators	$916.57
		3950	Cleanout Oil/Water Seperators	$916.57
		3950	Cleanout Oil/Water Seperators	$916.57
		3950	Cleanout Oil/Water Seperators	$916.57
		3950	Cleanout Oil/Water Seperators	$916.57
Total EFT000000013375				**$4,582.85**
EFT000000013377	2020-05-29		D.MARTIN WELDING & FABRICATING	
		9732	12X Grates +Angle in Trenches	$5,736.78
		9731	Straighten Bracket for Wheel	$152.64
Total EFT000000013377				**$5,889.42**
EFT000000013378	2020-05-29		EARL ROSEBUSH FUELS	
		0646-122434	334.90L @.431	$174.31
		3160-121992	60.50L @.426	$31.18
Total EFT000000013378				**$205.49**
EFT000000013379	2020-05-29		HUBB CAP	
		1020536	22X Culverts	$8,718.80
Total EFT000000013379				**$8,718.80**
EFT000000013383	2020-05-29		GANANOQUE CHEVROLET BUICK GMC	
		301888	Transmission	$5,599.33
Total EFT000000013383				**$5,599.33**
EFT000000013384	2020-05-29		GREER GALLOWAY CONSULTING ENGINEERS	
		23222	Engineering Services	$8,374.08
Total EFT000000013384				**$8,374.08**
EFT000000013385	2020-05-29		GROUNDWORK ENGINEERING LTD	
		2798	Geotechnical Investigation	$2,747.52

Total EFT000000013385				**$2,747.52**
EFT000000013386	2020-05-29		G WILLIAMS PAVING LTD	
		7350-HB	Entrance Repair Amey Rd.-HB	$3,336.71
		7365	Driveway Ends	$5,830.85
Total EFT000000013386				**$9,167.56**
EFT000000013398	2020-05-29		PETRIE FORD	
		287127	Oil	$73.32
Total EFT000000013398				**$73.32**
EFT000000013399	2020-05-29		PREMIER TRUCK GROUP	
		864143912	Filters	$271.06
Total EFT000000013399				**$271.06**
EFT000000013401	2020-05-29		ROSESON DISTRIBUTORS INC.	
		1058-14280	59.65L @.6605	$40.09
		1058-14324	87.16L @.6605	$58.58
		1058-14341	47.50L @.6605	$31.92
		1058-14367	99.29L @.6605	$66.74
		1058-14376	58.00L @.6605	$38.98
		1058-14378	12.11L @.6782	$8.35
		1058-14436	66.20L @.6782	$45.69
		1058-14465	51.18L @.6517	$33.94
		1058-14580	55.01L @.6870	$38.45
		1058-14616	83.54L @.6670	$56.70
		1058-14635	10.01L @.8287	$8.43
		1058-14647	Lubes	$199.10
		1058-14670	53.50L @.8287	$45.11
Total EFT000000013401				**$672.08**
EFT000000013408	2020-05-29		TOROMONT INDUSTRIES LTD.	
		PS040672972	Washer + Bolt	$2.12
		PS040672973	Grommet + Clip	$89.37
Total EFT000000013408				**$91.49**
EFT000000013410	2020-05-29		TOWN AND COUNTRY AUTO SUPPLY	
		6083-592896	3X Batteries	$336.03
		6083-595439	Oil	$49.90
		6083-595439	Oil	$24.95
		6083-595439	Filter	$6.17
		6083-595439	Battery Terminal	$7.56
		6083-595439	Rotors + Brakes	$545.93
		6083-595443	2X Oil Filters	$12.31
		6083-593434	Grease Gun + Grease	$611.09
		6083-596188	Rotors + Pads	$240.92
		6083-596349	Drill	$53.40
		6083-596353	3X Bearing Kits	$52.53
		6083-596378	Bearing Kit	$19.80
		6083-596520	Pads + Rotors	$726.63
		6083-596521	Pads + Rotors	$262.91
Total EFT000000013410				**$2,950.13**
EFT000000013411	2020-05-29		TROUSDALE'S FOODLAND	
		7852	Water	$24.90
Total EFT000000013411				**$24.90**
EFT000000013412	2020-05-29		TROUSDALE'S HOME HARDWARE	
		229076	2X Rakes + Batteries	$44.74
		229244	Batteries+Stakes+Weed Barrier	$172.42
		229245	2X Rakes	$44.75
		229248	Batteries	$32.54
Total EFT000000013412				**$294.45**
EFT000000013413	2020-05-29		UNIVERSAL SUPPLY GROUP	
		173-270946	2X Drums	$512.99
		173-271120	2X Safety Latches	$21.19
Total EFT000000013413				**$534.18**
Total				**$629,650.36**

3210 Brushing

Cheque	Date	Inv #	Vendor	Description	Amount
070844	2020-03-30		SNIDER, PERCY		
		20/03/03-12		Flagging	$226.67
		20/03/05-14		Flagging	$377.78
		20/03/04-13		Flagging	$377.78
Total 070844					**$982.23**
070882	2020-04-03		SNIDER, PERCY		
		20/03/10-20		Flagging	$352.60
		20/03/12-19		Flagging	$377.78
		20/03/12-21		Flagging	$201.48
Total 070882					**$931.86**
070918	2020-05-15		SNIDER, PERCY		
		20/04/15-50		Flagging	$402.97
		20/04/16-01		Flagging	$377.78
Total 070918					**$780.75**
070931	2020-05-29		SNIDER, PERCY		
		20/04/20-19		Flagging	$398.64
		20/04/22-21		Flagging	$474.20
		20/04/23-22		Flagging	$474.20
		20/04/24-23		Flagging	$474.20
		20/04/30-25		Flagging	$373.46
		20/05/04-41		Flagging	$478.53
		20/05/04-43		Flagging	$274.88
		20/05/05-39		Flagging	$514.14
		20/05/05-44		Flagging	$274.88
		20/05/06-42		Flagging	$239.27
		20/05/06-45		Flagging	$274.88
		20/05/07-40		Flagging	$514.14

		20/05/07-46		Flagging	$274.88
		20/05/08-47		Flagging	$463.77
Total 070931					**$5,504.07**
EFT000000013366	2020-05-29		BATTLEFIELD EQUIPMENT RENTALS		
		24237657		Gas Blower	$203.46
Total EFT000000013366					**$203.46**
EFT000000013406	2020-05-29		SWEET'S SAND & GRAVEL		
		S-0063423		Brush Cutter Rental	$14,954.66
Total EFT000000013406					**$14,954.66**
Total Brushing					**$23,357.03**

3215 Drainage

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013365	2020-05-29		ARMTEC CANADA CULVERT		
		6-202656		15X Couplers	$244.22
Total EFT000000013365					**$244.22**
Total Drainage					**$244.22**

3220 Ctc,Cb&gtr

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013212	2020-04-20		DEDICATED ENVIRONMENTAL SERVICES INC		
		3889		Catch Basin Repairs	$4,937.85
Total EFT000000013212					**$4,937.85**
EFT000000013315	2020-05-15		DEDICATED ENVIRONMENTAL SERVICES INC		
		3940		Seal Leak	$885.52
Total EFT000000013315					**$885.52**
Total Ctc,Cb&gtr					**$5,823.37**

3310 Hardtop Patching

Cheque	Date	Inv #	Vendor	Description	Amount
070844	2020-03-30		SNIDER, PERCY		
		20/03/05-07		Patching	$934.16
		20/03/04-06		Patching	$934.16
		20/03/03-05		Patching	$934.16
Total 070844					**$2,802.48**
070918	2020-05-15		SNIDER, PERCY		
		20/04/14-02		Patching	$934.16
		20/04/15-03		Patching	$934.16
		20/04/16-04		Patching	$934.16
Total 070918					**$2,802.48**
070931	2020-05-29		SNIDER, PERCY		
		20/04/17-18		Patching	$934.16
		20/05/05-33		Patching	$817.39
		20/05/06-34		Patching	$992.55
Total 070931					**$2,744.10**
EFT000000013094	2020-03-30		BOULTON SEPTIC/LARMON'S		
		31630		Patching	$1,825.57
Total EFT000000013094					**$1,825.57**
EFT000000013141	2020-03-27		TW PATCHING		
		988322		Patching	$3,627.74
Total EFT000000013141					**$3,627.74**
EFT000000013144	2020-04-03		BOULTON SEPTIC/LARMON'S		
		31764		Patching	$3,190.18
Total EFT000000013144					**$3,190.18**
EFT000000013248	2020-04-22		TW PATCHING		
		988323		Patching	$5,909.71
		988324		Patching	$10,181.09
Total EFT000000013248					**$16,090.80**
EFT000000013296	2020-05-15		BOULTON SEPTIC/LARMON'S		
		31894		Patching	$686.88
		31895		Patching	$874.63
		31896		Patching	$1,554.89
		31897		Patching	$1,749.25
		31898		Patching	$1,554.89
		31899		Patching	$1,360.53
		31900		Patching	$1,846.43
		31901		Patching	$1,554.89
Total EFT000000013296					**$11,182.39**
EFT000000013339	2020-05-15		O. BETTSCHEN		
		44417		Cold Patch	$7,686.07
		44441		Cold Patch	$7,720.78
		44456		Cold Patch	$441.64
		44468		Cold Patch	$4,777.57
		44484		Cold Patch	$880.12
Total EFT000000013339					**$21,506.18**
EFT000000013362	2020-05-29		BOULTON SEPTIC/LARMON'S		
		31720		Patching	$2,051.48
Total EFT000000013362					**$2,051.48**
Total Hardtop Patching					**$67,823.40**

3315 Sweeping

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013170	2020-04-03		JOE JOHNSON EQUIPMENT INC.		
		P33522		Sweeper Brooms	$1,467.14
Total EFT000000013170					**$1,467.14**

EFT000000013389	2020-05-29		JOE JOHNSON EQUIPMENT INC.		
		P33634		Sweeping Brushes	$4,590.23
Total EFT000000013389					**$4,590.23**
Total Sweeping					**$6,057.37**

3325 Pavmnt Preserv

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013178	2020-04-03		PUROLATOR INC.		
		444110910		Shipment- Roadlast	$14.25
Total EFT000000013178					**$14.25**
Total Pavmnt Preserv					**$14.25**

3405 Washout

Cheque	Date	Inv #	Vendor	Description	Amount
070882	2020-04-03		SNIDER, PERCY		
		20/03/11-17		Patching	$817.39
Total 070882					**$817.39**
070931	2020-05-29		SNIDER, PERCY		
		20/04/02-26		Patching	$639.56
Total 070931					**$639.56**
EFT000000013136	2020-03-27		SWEET'S SAND & GRAVEL		
		S-0062920		Gravel	$4,742.12
		S-0062919		Gravel	$12,884.83
Total EFT000000013136					**$17,626.95**
EFT000000013339	2020-05-15		O. BETTSCHEN		
		44418		Gravel	$1,969.33
		44428		Gravel	$1,688.74
		44430		Gravel	$1,517.17
		44469		Gravel	$141.25
Total EFT000000013339					**$5,316.49**
EFT000000013406	2020-05-29		SWEET'S SAND & GRAVEL		
		S-0063062		Gravel	$5,033.83
Total EFT000000013406					**$5,033.83**
Total Washout					**$29,434.22**

3415 dust layer

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013396	2020-05-29		MORRIS CHEMICALS INCORPORATED		
		INV0078092		Calcium Chloride	$5,174.83
		INV0078093		Calcium Chloride	$5,113.76
		INV0078094		Calcium Chloride	$5,234.02
		INV0078111		Calcium Chloride	$6,075.80
		INV0078112		Calcium Chloride	$4,982.05
		INV0078120		Calcium Chloride	$5,944.11
		INV0078121		Calcium Chloride	$6,119.71
Total EFT000000013396					**$38,644.28**
Total dust layer					**$38,644.28**

3425 Gradng & Grvl resurf

Cheque	Date	Inv #	Vendor	Description	Amount
070882	2020-04-03		SNIDER, PERCY		
		20/03/11-18		Grading	$267.12
Total 070882					**$267.12**
070918	2020-05-15		SNIDER, PERCY		
		20/04/03-47		Grading	$267.12
Total 070918					**$267.12**
070931	2020-05-29		SNIDER, PERCY		
		20/04/08-31		Grading	$305.28
		20/04/30-06		Grading	$343.44
Total 070931					**$648.72**
EFT000000013282	2020-05-01		SWEET'S SAND & GRAVEL		
		S-0062957		Grader Rental	$4,655.52
		S-0062965		Gravel	$10,672.48
Total EFT000000013282					**$15,328.00**
EFT000000013339	2020-05-15		O. BETTSCHEN		
		44419		Gravel	$2,119.27
		44420		Gravel	$1,724.06
		44421		Gravel	$1,767.80
		44448		Gravel	$1,226.09
		44449		Gravel	$420.98
		44450		Recycled Asphalt	$291.25
		44451		Gravel	$853.20
		44467		Gravel	$1,476.32
		44431		Gravel	$647.69
Total EFT000000013339					**$10,526.66**
EFT000000013351	2020-05-15		SWEET'S SAND & GRAVEL		
		S-0062924		Gravel	$4,477.57
Total EFT000000013351					**$4,477.57**
EFT000000013406	2020-05-29		SWEET'S SAND & GRAVEL		
		S-0063071		Gravel	$3,215.96
		S-0063096		Gravel	$3,695.42
Total EFT000000013406					**$6,911.38**
EFT000000013412	2020-05-29		TROUSDALE'S HOME HARDWARE		
		103117		Jerry Can	$15.25
Total EFT000000013412					**$15.25**
EFT000000013415	2020-05-29		WHITE'S WEARPARTS LTD		

		132109		7X Grader Blades	$931.43
Total EFT000000013415					**$931.43**
Total Gradng & Grvl resurf					**$39,373.25**

3502 Winter Prop Damage

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013412	2020-05-29		TROUSDALE'S HOME HARDWARE		
		229405		Lumber + Key	$16.06
Total EFT000000013412					**$16.06**
Total Winter Prop Damage					**$16.06**

3505 Snw Plwng

Cheque	Date	Inv #	Vendor	Description	Amount
070844	2020-03-30		SNIDER, PERCY		
		20/03/03-50		Snow Plowing	$195.38
		20/03/03-49		Snow Plowing	$146.53
		20/03/03-48		Snow Plowing	$318.51
		20/03/02-34		Snow Plowing	$195.38
		20/03/02-33		Snow Plowing	$146.53
		20/03/02-32		Snow Plowing	$318.51
		20/02/27-44		Snow Plowing	$162.82
		20/02/19-39		Snow Plowing	$152.64
		20/02/28-31		Snow Plowing	$195.38
		20/02/28-30		Snow Plowing	$146.53
		20/02/28-29		Snow Plowing	$318.51
		20/02/27-28		Snow Plowing	$390.76
		20/02/27-27		Snow Plowing	$293.07
		20/02/27-26		Snow Plowing	$637.02
		20/03/03-25		Snow Plowing	$184.19
		20/03/02-24		Snow Plowing	$184.19
		20/02/28-23		Snow Plowing	$184.19
		20/02/27-22		Snow Plowing	$184.19
		20/03/02-21		Snow Plowing	$905.66
		20/02/28-15		Snow Plowing	$905.66
		20/02/27-14		Snow Plowing	$905.66
Total 070844					**$7,071.31**
070931	2020-05-29		SNIDER, PERCY		
		20/01/16-29		Snow Plowing	$905.66
Total 070931					**$905.66**
EFT000000013123	2020-03-27		K MULROONEY TRUCKING LIMITED		
		2019-27501		Snow Plowing	$1,144.42
		2019-27502		Snow Plowing	$610.36
		2019-27504		Snow Plowing	$639.46
		2019-27503		Snow Plowing	$577.69
		2019-27507		Snow Plowing	$633.41
		2019-27506		Snow Plowing	$559.53
		2019-27505		Snow Plowing	$319.73
Total EFT000000013123					**$4,484.60**
EFT000000013250	2020-05-01		BOULTON SEPTIC/LARMON'S		
		31799		Snow Plowing	$50.88
		31803		Snow Plowing	$356.16
		31804		Snow Plowing	$305.28
		31805		Snow Plowing	$305.28
Total EFT000000013250					**$1,017.60**
EFT000000013337	2020-05-15		MCNICHOLS CONSTRUCTION LTD		
		20/03/02-ROUTE 11		Snow Plowing	$630.91
		20/03/02-ROUTE12		Snow Plowing	$284.93
Total EFT000000013337					**$915.84**
Total Snw Plwng					**$14,395.01**

3506 Snow Clearing Sidewalks

Cheque	Date	Inv #	Vendor	Description	Amount
070844	2020-03-30		SNIDER, PERCY		
		20/03/02-03		Snow Plowing	$69.20
		20/03/02-03		Snow Plowing	$203.52
		20/03/02-02		Snow Plowing	$101.76
		20/03/02-02		Snow Plowing	$93.62
		20/03/02-01		Snow Plowing	$193.34
		20/02/27-44		Snow Plowing	$162.82
		20/02/27-43		Snow Plowing	$305.28
		20/02/27-43		Snow Plowing	$101.76
		20/02/19-40		Snow Plowing	$244.22
		20/02/19-39		Snow Plowing	$254.40
		20/02/28-37		Snow Plowing	$101.76
		20/02/28-37		Snow Plowing	$93.62
		20/02/28-36		Snow Plowing	$203.52
		20/02/28-36		Snow Plowing	$69.20
		20/02/27-35		Snow Plowing	$193.34
		20/02/27-35		Snow Plowing	$101.76
		20/02/27-42		Snow Plowing	$366.34
		20/02/27-42		Snow Plowing	$203.52
		20/02/28-38		Snow Plowing	$193.34
		20/02/28-38		Snow Plowing	$101.76
		20/02/19-41		Snow Plowing	$254.40
		20/02/19-41		Snow Plowing	$152.64
Total 070844					**$3,765.12**
EFT000000013250	2020-05-01		BOULTON SEPTIC/LARMON'S		
		31802		Snow Plowing	$178.08
		31802		Snow Plowing	$178.08

Total EFT000000013250					**$356.16**
Total Snow Clearing Sidewalks					**$4,121.28**

3515 Stock Snd&Slt

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013266	2020-05-01		HARTINGTON EQUIPMENT LIMITED		
		IV60325		Mirror	$552.01
Total EFT000000013266					**$552.01**
EFT000000013270	2020-05-01		K+S WINDSOR SALT LTD		
		5300486297		Winter Salt	$7,796.34
Total EFT000000013270					**$7,796.34**
Total Stock Snd&Slt					**$8,348.35**

3525 Snw Remvl

Cheque	Date	Inv #	Vendor	Description	Amount
070844	2020-03-30		SNIDER, PERCY		
		20/02/12-12		Flagging	$287.47
Total 070844					**$287.47**
Total Snw Remvl					**$287.47**

3535 Surface Fldng

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013311	2020-05-15		COMPTON PROPANE SOLUTIONS		
		6507		100lbs Propane	$441.28
Total EFT000000013311					**$441.28**
EFT000000013385	2020-05-29		GROUNDWORK ENGINEERING LTD		
		2799		Geotechnical Investigation	$2,976.48
Total EFT000000013385					**$2,976.48**
Total Surface Fldng					**$3,417.76**

3601 Barricds & Sfty Matls

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013306	2020-05-15		BMR MANUFACTURING INC.		
		363815		Orange Cones	$1,572.70
Total EFT000000013306					**$1,572.70**
EFT000000013366	2020-05-29		BATTLEFIELD EQUIPMENT RENTALS		
		24237639		Orange Paint+ Safety Vest	$224.56
Total EFT000000013366					**$224.56**
Total Barricds & Sfty Matls					**$1,797.26**

3605 Pvmt Mrkng

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013207	2020-04-20		CUNNINGHAM SWAN CARTY		
		163255		Legal Advice	$457.92
Total EFT000000013207					**$457.92**
EFT000000013286	2020-05-01		TRILLIUM PAVEMENT MARKING		
		3895777		Line Painting	$20,739.81
Total EFT000000013286					**$20,739.81**
Total Pvmt Mrkng					**$21,197.73**

3615 Street signs

Cheque	Date	Inv #	Vendor	Description	Amount
070923	2020-05-29		ATKINSON HOME BUILDING CENTRE		
		265319		Lumber	$53.92
Total 070923					**$53.92**
EFT000000013106	2020-03-27		BMR MANUFACTURING INC.		
		363608		Signs	$23,438.58
Total EFT000000013106					**$23,438.58**
EFT000000013349	2020-05-15		SIGNS PLUS		
		3183		Street Sign	$37.59
		3185		2X Street Signs	$65.02
Total EFT000000013349					**$102.61**
EFT000000013368	2020-05-29		BMR MANUFACTURING INC.		
		363733		21X Street Signs	$1,607.81
Total EFT000000013368					**$1,607.81**
EFT000000013403	2020-05-29		SIGNS PLUS		
		3187		Street Sign	$37.59
Total EFT000000013403					**$37.59**
Total Street signs					**$25,240.51**

3620 Reg signs

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013368	2020-05-29		BMR MANUFACTURING INC.		
		363984		300X U Channel Posts	$6,769.07
		363988		4X Safety Signs	$349.76
Total EFT000000013368					**$7,118.83**
EFT000000013390	2020-05-29		KENT AUTOMOTIVE		
		9307575038		Cable Ties	$389.24
Total EFT000000013390					**$389.24**
Total Reg signs					**$7,508.07**

3625 RR cross mnt

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013151	2020-04-03		CANADIAN PACIFIC RAILWAY		
		11120078		20/03 Flasher Contract	$888.00
Total EFT000000013151					**$888.00**
EFT000000013307	2020-05-15		CANADIAN PACIFIC RAILWAY		
		11120909		20/04 Flasher Contract	$888.00
Total EFT000000013307					**$888.00**
Total RR cross mnt					**$1,776.00**

3630 Gd ps/rl mnt

Cheque	Date	Inv #	Vendor	Description	Amount
070864	2020-03-27		MILLAR CEDAR POSTS LIMITED		
		4793		500X Cedar Posts	$6,487.20
Total 070864					**$6,487.20**
070931	2020-05-29		SNIDER, PERCY		
		20/04/29-24		Flagging	$474.20
Total 070931					**$474.20**
EFT000000013319	2020-05-15		HUBB CAP		
		1020392		Spacers+Staples+Cable	$1,832.65
Total EFT000000013319					**$1,832.65**
EFT000000013362	2020-05-29		BOULTON SEPTIC/LARMON'S		
		32016		Flagging	$310.37
		32017		Flagging	$931.10
		32018		Flagging	$931.10
		32019		Flagging	$931.10
		32020		Flagging	$931.10
		32021		Flagging	$931.10
Total EFT000000013362					**$4,965.87**
EFT000000013379	2020-05-29		HUBB CAP		
		1020455		Reflector Strips	$406.02
Total EFT000000013379					**$406.02**
EFT000000013397	2020-05-29		PERFECT SOLUTIONS		
		11650		Assorted Safety Equipment	$853.78
Total EFT000000013397					**$853.78**
Total Gd ps/rl mnt					**$15,019.72**

3638 Locates

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013340	2020-05-15		ONTARIO ONE CALL		
		202010907		20/04 Notifications	$59.98
Total EFT000000013340					**$59.98**
Total Locates					**$59.98**

3800 Crssng Guards

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013155	2020-04-03		COMMISSIONAIRES SECURITY SOLUTIONS		
		91793		Crossing Guards	$884.81
Total EFT000000013155					**$884.81**
EFT000000013310	2020-05-15		COMMISSIONAIRES SECURITY SOLUTIONS		
		91998		Crossing Guards	$1,135.91
Total EFT000000013310					**$1,135.91**
Total Crssng Guards					**$2,020.72**

Total Trans $950,589.63

40 Env

4110 Water Treat

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013207	2020-04-20		CUNNINGHAM SWAN CARTY		
		163254		Legal Advice	$381.60
Total EFT000000013207					**$381.60**
EFT000000013302	2020-05-15		BELL CANADA-WATER TOWER PHONE LINE		
		N6027631-20/04		20/04 Telephone	$89.61
Total EFT000000013302					**$89.61**
Total Water Treat					**$471.21**

5005 SW & Fac OH

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013237	2020-04-20		TROUSDALE'S HOME HARDWARE		
		228202		Hay Fork	$35.61
		228202		Gloves	$64.07
Total EFT000000013237					**$99.68**
EFT000000013252	2020-05-01		ALLIED MEDICAL INSTRUMENTS INC		
		504679		24X QuikCare Waterless	$239.23
Total EFT000000013252					**$239.23**
EFT000000013258	2020-05-01		COLLINS SAFETY INC.		
		247108		Bib Overalls	$141.44
Total EFT000000013258					**$141.44**
EFT000000013325	2020-05-15		GILMORE REPRODUCTIONS		
		298929		Covid 19 Signage	$2,919.49
Total EFT000000013325					**$2,919.49**

EFT000000013352	2020-05-15		SWISH MAINTENANCE LIMITED		
		K632731		Wipes + Gloves	$365.58
		K632763		Face Masks	$74.69
		K633221		Sanitizer + Wipes	$397.27
Total EFT000000013352					**$837.54**
EFT000000013357	2020-05-15		TRUE ELECTRIC		
		6931		Install LED Lighting	$2,198.02
Total EFT000000013357					**$2,198.02**
EFT000000013394	2020-05-29		LIGHTING...FX INC.		
		61234		LED Fixture	$223.62
Total EFT000000013394					**$223.62**
Total SW & Fac OH					**$6,659.02**

5105 Garb coll

Cheque	Date	Inv #	Vendor	Description	Amount
070844	2020-03-30		SNIDER, PERCY		
		20/03 FUEL ADJ.		20/03 Garbage- Fuel Adj.	$38.51
		20/03 FUEL ADJ.		20/03 Garbage Fuel Adj	$31.79
		20/03 COLLECTION		20/03 Garbage Collection	$12,179.56
		20/03 COLLECTION		20/03 Garbage Collection	$10,053.68
Total 070844					**$22,303.54**
070901	2020-05-01		SNIDER, PERCY		
		20/04 COLLECTION		20/04 Garbage Collection	$12,179.56
		20/04 COLLECTION		20/04 Garbage Collection	$10,053.68
Total 070901					**$22,233.24**
070916	2020-05-15		MADDOCKS ENGINEERING		
		22768		4X TyeDee Bins	$3,388.86
Total 070916					**$3,388.86**
070931	2020-05-29		SNIDER, PERCY		
		20/05 COLLECTION		20/05 Garbage Collection	$12,179.56
		20/05 COLLECTION		20/05 Garbage Collection	$10,053.68
		20/04-07		12X Garbage Cans	$122.11
		20/04/28-20		Cleaning Garbage Bins	$101.76
Total 070931					**$22,457.11**
EFT000000013094	2020-03-30		BOULTON SEPTIC/LARMON'S		
		20/03 COLLECTION		20/03 Garbage Collection	$12,441.75
		20/03-FUEL ADJ.		20/03 Garbage- Fuel Adj.	$39.35
Total EFT000000013094					**$12,481.10**
EFT000000013237	2020-04-20		TROUSDALE'S HOME HARDWARE		
		102177		Lumber + Screws	$69.29
		102181		Paint + Supplies-Garbage Lids	$48.77
Total EFT000000013237					**$118.06**
EFT000000013290	2020-04-30		BOULTON SEPTIC/LARMON'S		
		20/04 COLLECTION		20/04 Garbage Collection	$12,441.75
Total EFT000000013290					**$12,441.75**
EFT000000013362	2020-05-29		BOULTON SEPTIC/LARMON'S		
		20/05 COLLECTION		20/05 Garbage Collection	$12,441.75
Total EFT000000013362					**$12,441.75**
EFT000000013403	2020-05-29		SIGNS PLUS		
		3189		10X Logo Decals	$40.19
Total EFT000000013403					**$40.19**
Total Garb coll					**$107,905.60**

5110 Gab disp

Cheque	Date	Inv #	Vendor	Description	Amount
070844	2020-03-30		SNIDER, PERCY		
		20/02/25-20		Portland Dump/Excavator	$1,790.98
		20/02/24-17		Portland Dump/Truck Rental	$610.56
		20/02/26-16		Portland Dump/Truck Rental	$152.64
		20/02/26-13		Portland Dump/Waste	$1,246.56
		20/02-11		20/02 Bin Rental	$152.64
		20/03/05-46		Portland Dump/Waste	$712.32
		20/03/05-04		Portland Dump/Dozer	$651.26
		20/02/25-08		Portland Dump/Truck Rental	$152.64
		20/03/05-10		Portland Dump/Truck Rental	$343.44
Total 070844					**$5,813.04**
070867	2020-03-27		SNIDER, PERCY		
		20/03/02-11		Portland Dump/Truck Rental	$190.80
Total 070867					**$190.80**
070871	2020-03-27		WASTE MANAGEMENT OF CANADA CORP		
		30022-0639-3		ICI Waste	$3,350.03
		30022-0639-3		ICI Waste	$2,982.11
Total 070871					**$6,332.14**
070882	2020-04-03		SNIDER, PERCY		
		20/03/06-23		Hauling Plastic to Kingston	$343.44
		20/03/10-16		Portland Dump/Waste	$712.32
		20/03/12-22		Portland Dump	$152.64
		20/03/12-24		Portland Dump	$1,567.10
Total 070882					**$2,775.50**
070892	2020-04-20		SNIDER, PERCY		
		20/03/13-26		Portland Dump/Dozer	$325.63
		20/03/13-27		Portland/Truck Rental	$343.44
		20/03/16-37		Excavator + Truck	$3,060.94
		20/03/17-36		Excavator + Truck	$3,826.18
		20/03/18-25		Portland Dump/Waste	$1,068.48
		20/03/18-31		Portland Dump/Dozer	$569.86
		20/03/19-35		Excavator + Truck	$3,443.56
		20/03-34		20/03 Bin Rental	$152.64

		20/03/20-38	Truck Rental	$223.87
		20/03/20-39	Excavator+Tandem+ Dozer	$1,681.07
		20/03/23-40	Excavator+Tandem+ Dozer	$1,681.07
		20/03/24-41	Excavator+Tandem+ Dozer	$1,440.92
		20/03/25-43	Excavator+Tandem+ Dozer	$1,681.07
Total 070892				**$19,498.73**
070894	2020-04-20	WASTE MANAGEMENT OF CANADA CORP		
		30053-0639-8	ICI Waste	$4,570.66
		30053-0639-8	ICI Waste	$1,158.83
		30053-0639-8	ICI Waste	$374.70
Total 070894				**$6,104.19**
070901	2020-05-01	SNIDER, PERCY		
		20/04/08-46	Portland Dump/Dozer	$569.86
Total 070901				**$569.86**
070921	2020-05-15	WASTE MANAGEMENT OF CANADA CORP		
		30071-0639-0	ICI Waste	$4,956.93
		30100-0639-7	ICI Waste	$4,884.51
Total 070921				**$9,841.44**
070931	2020-05-29	SNIDER, PERCY		
		20/04-05	20/04 Bin Rental	$152.64
		20/04/17-14	Portland Dump/Dozer	$244.22
		20/04/20-08	Triaxle Rental	$537.29
		20/04/20-09	Triaxle Rental	$671.62
		20/04/20-10	Triaxle Rental	$716.39
		20/04/20-15	Back Hoe + Dozer	$1,577.28
		20/04/22-11	Triaxle Rental	$537.29
		20/04/22-16	Backhoe + Dozer	$1,104.10
		20/04/23-12	Triaxle Rental	$761.16
		20/04/23-17	Portland Dump/Dozer	$814.08
		20/04/28-13	Portland Dump/Dozer	$244.22
		20/05/04-35	Tandem Truck Rental	$116.01
		20/05/04-37	Backhoe Rental	$305.28
		20/05/05-36	Portland Dump/Dozer	$244.22
		20/05/07-32	Portland Dump/Waste	$356.16
		20/05/08-38	Portland Dump/ Shovel	$244.22
Total 070931				**$8,626.18**
EFT000000013098	2020-03-30	WHALEY, GEORGE		
		20/03 DISPOSAL	20/03 Disposal	$1,935.80
Total EFT000000013098				**$1,935.80**
EFT000000013100	2020-03-27	ABELL PEST CONTROL INC.		
		02061464	Pest Control	$58.81
		02061464	Pest Control	$58.81
		02061464	Pest Control	$58.81
Total EFT000000013100				**$176.43**
EFT000000013119	2020-03-27	JODY CAMPBELL'S SEPTIC SERVICE		
		16489	Portable Toilet 17/03-20/04	$4,446.91
Total EFT000000013119				**$4,446.91**
EFT000000013166	2020-04-03	HAMILL FORESTRY PRODUCTS		
		387559	Tubgrinder Rental	$1,526.40
Total EFT000000013166				**$1,526.40**
EFT000000013216	2020-04-20	ENVIRO-GUARD PLUS INC.		
		97291	20/02 Pest Control	$46.81
		97012	20/01 Pest Control	$46.81
Total EFT000000013216				**$93.62**
EFT000000013223	2020-04-20	JODY CAMPBELL'S SEPTIC SERVICE		
		16654	20/04 Portable Toilet Rental	$117.02
		16654	20/04 Portable Toilet Rental	$117.02
Total EFT000000013223				**$234.04**
EFT000000013241	2020-04-20	WASTE CONNECTIONS OF CANADA		
		7150-0000347944	Dump + Remove	$642.40
Total EFT000000013241				**$642.40**
EFT000000013243	2020-04-20	WHALEY, GEORGE		
		812375	20/03 Landfill Maintenance	$3,917.76
Total EFT000000013243				**$3,917.76**
EFT000000013255	2020-05-01	CAMBIUM INC.		
		2019-29812	Report	$3,108.77
		2019-29813	Report	$3,109.79
		2019-29814	Report	$2,940.86
		2019-29815	Report	$2,949.00
		2019-29816	Report	$2,949.00
		2019-29817	Report	$2,788.22
Total EFT000000013255				**$17,845.64**
EFT000000013295	2020-04-30	WHALEY, GEORGE		
		20/04 DISPOSAL	20/04 Disposal	$1,935.80
Total EFT000000013295				**$1,935.80**
EFT000000013297	2020-05-15	ABELL PEST CONTROL INC.		
		3061774	20/03 Pest Control	$58.81
		3061774	20/03 Pest Control	$58.81
		3061774	20/03 Pest Control	$58.81
		A2791030	20/05 Pest Control	$111.21
Total EFT000000013297				**$287.64**
EFT000000013318	2020-05-15	ENVIRO-GUARD PLUS INC.		
		97576	20/03 Pest Control	$46.81
Total EFT000000013318				**$46.81**
EFT000000013320	2020-05-15	ESKEROD SIGNS		
		28824	8X Signs for HHW	$610.56
Total EFT000000013320				**$610.56**
EFT000000013332	2020-05-15	JODY CAMPBELL'S SEPTIC SERVICE		
		16741	20/05 Portable Toilet Rental	$117.02
Total EFT000000013332				**$117.02**
EFT000000013339	2020-05-15	O. BETTSCHEN		

		44450		Shot Rock	$340.00
Total EFT000000013339					**$340.00**
EFT000000013356	2020-05-15		TROUSDALE'S HOME HARDWARE		
		228909		Shovel + Rake	$120.88
		305491		Lumber + Screws+ Washers	$37.36
		606482		Plexiglass	$68.17
Total EFT000000013356					**$226.41**
EFT000000013363	2020-05-29		ABELL PEST CONTROL INC.		
		A2731760		20/04 Pest Control	$111.21
Total EFT000000013363					**$111.21**
EFT000000013369	2020-05-29		CAMBIUM INC.		
		2020-30006		Spring + Railway Sampling	$4,635.17
		2020-30007		Spring Sampling	$5,143.97
		2020-30008		Spring Sampling	$2,762.78
		2020-30009		Spring Sampling	$3,159.65
		2020-30010		Spring Sampling	$2,223.46
		2020-30011		Spring Sampling	$1,495.87
		2020-30012		Spring Sampling	$1,333.06
		2020-30013		Spring Sampling	$2,065.73
Total EFT000000013369					**$22,819.69**
EFT000000013395	2020-05-29		MCNICHOLS CONSTRUCTION LTD		
		20/05/12-SALEM		Triaxle + Excavator Rental	$2,859.46
		20/05/13-GREEN BAY		Triaxle + Excavator Rental	$3,999.17
		20/05/14-BRADSHAW		Triaxle + Excavator Rental	$3,714.24
Total EFT000000013395					**$10,572.87**
EFT000000013414	2020-05-29		WHALEY, GEORGE		
		20/05 DISPOSAL		20/05 Disposal	$1,935.80
		812376		20/04 Landfill Services	$4,525.27
Total EFT000000013414					**$6,461.07**
Total Gab disp					**$134,099.96**

5200 Recyc

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013188	2020-04-03		UBCON CONSTRUCTION LTD		
		19-014-3		Build 2X Recyle Centres	$2,826.89
Total EFT000000013188					**$2,826.89**
Total Recyc					**$2,826.89**

5205 Recyc Coll

Cheque	Date	Inv #	Vendor	Description	Amount
070844	2020-03-30		SNIDER, PERCY		
		20/03 FUEL ADJ.		20/03 Garbage- Fuel Adj.	$41.54
		20/03 FUEL ADJ.		20/03 Garbage- Fuel Adj.	$36.23
		20/03 FUEL ADJ.		20/03 Garbage- Fuel Adj.	$38.67
		20/03 COLLECTION		20/03 Garbage Collection	$13,138.72
		20/03 COLLECTION		20/03 Garbage Collection	$11,456.83
		20/03 COLLECTION		20/03 Garbage Collection	$12,229.28
Total 070844					**$36,941.27**
070901	2020-05-01		SNIDER, PERCY		
		20/04 COLLECTION		20/04 Garbage Collection	$13,138.72
		20/04 COLLECTION		20/04 Garbage Collection	$11,456.83
		20/04 COLLECTION		20/04 Garbage Collection	$12,229.28
Total 070901					**$36,824.83**
070931	2020-05-29		SNIDER, PERCY		
		20/05 COLLECTION		20/05 Garbage Collection	$13,138.72
		20/05 COLLECTION		20/05 Garbage Collection	$11,456.83
		20/05 COLLECTION		20/05 Garbage Collection	$12,229.28
Total 070931					**$36,824.83**
EFT000000013094	2020-03-30		BOULTON SEPTIC/LARMON'S		
		20/03 COLLECTION		20/03 Garbage Collection	$10,702.58
		20/03-FUEL ADJ.		20/03 Garbage- Fuel Adj.	$33.83
Total EFT000000013094					**$10,736.41**
EFT000000013290	2020-04-30		BOULTON SEPTIC/LARMON'S		
		20/04 COLLECTION		20/04 Garbage Collection	$10,702.58
Total EFT000000013290					**$10,702.58**
EFT000000013362	2020-05-29		BOULTON SEPTIC/LARMON'S		
		20/05 COLLECTION		20/05 Garbage Collection	$10,702.58
Total EFT000000013362					**$10,702.58**
Total Recyc Coll					**$142,732.50**

5210 Rec Disp/Prc

Cheque	Date	Inv #	Vendor	Description	Amount
070844	2020-03-30		SNIDER, PERCY		
		20/03/02-47		Green Bay Recycle	$864.96
Total 070844					**$864.96**
070882	2020-04-03		SNIDER, PERCY		
		20/03/06-15		Portland Recycle	$534.24
Total 070882					**$534.24**
Total Rec Disp/Prc					**$1,399.20**

5305 HHW

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013201	2020-04-20		BRENDAR ENVIRONMENTAL INC.		
		20200054		20/03 HHW Services	$4,026.69
Total EFT000000013201					**$4,026.69**

Total HHW **$4,026.69**

Total Env **$400,121.07**

70 Cem

7000 Health

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013095	2020-03-30		D G YOUNGE CONCRETE BURIAL VAULTS		
		20/03 SERVICES		20/03 Cemetary Services	$875.14
Total EFT000000013095					**$875.14**
EFT000000013292	2020-04-30		D G YOUNGE CONCRETE BURIAL VAULTS		
		20/04 SERVICES		20/04 Cemetary Services	$875.14
Total EFT000000013292					**$875.14**
EFT000000013316	2020-05-15		D G YOUNGE CONCRETE BURIAL VAULTS		
		2674		20/03 Cemetary Services	$585.12
		2674		20/03 Cemetary Services	$2,925.60
		2674		20/03 Cemetary Services	$585.12
Total EFT000000013316					**$4,095.84**
EFT000000013376	2020-05-29		D G YOUNGE CONCRETE BURIAL VAULTS		
		20/05 SERVICES		20/05 Cemetary Services	$875.14
		2712		20/04 Cemetary Services	$152.64
		2712		20/04 Cemetary Services	$864.96
		2712		20/04 Cemetary Services	$788.64
		2712		20/04 Cemetary Services	$381.60
Total EFT000000013376					**$3,062.98**
Total Health					**$8,909.10**
Total Cem					**$8,909.10**

80 Rec

8000 Rec

Cheque	Date	Inv #	Vendor	Description	Amount
070844	2020-03-30		SNIDER, PERCY		
		20/02/27-41		Snow Plowing	$839.52
		20/02/27-42-2		Snow Plowing	$1,058.30
Total 070844					**$1,897.82**
070872	2020-03-27		BRABANT, THOMAS		
		20/03/29-REFUND		20/03/29-REFUND	$44.25
Total 070872					**$44.25**
070873	2020-03-27		PILBROW, JACQUELINE		
		2020 REFUND		04/18+03/28 Refund	$180.00
Total 070873					**$180.00**
070889	2020-04-03		ZABIZEWSKI, MIKE		
		20/03/21 REFUND		20/03/21 Refund	$80.00
Total 070889					**$80.00**
070892	2020-04-20		SNIDER, PERCY		
		20/02/28-49		Snow Plowing	$81.41
		20/02/28-50		Snow Plowing	$76.32
Total 070892					**$157.73**
070897	2020-04-20		RD ELLIOTT ROOFING		
		534		Sealed AC Unit	$283.91
Total 070897					**$283.91**
070929	2020-05-29		MIKAELA HUGHES ARCHITECT INC.		
		1726-05		Architectural Fees	$7,021.44
		2008-01		Architectural Fees	$3,113.86
Total 070929					**$10,135.30**
070931	2020-05-29		SNIDER, PERCY		
		20/04/27-02		Sweeping	$396.86
		20/04/27-48		Sweeping	$396.86
		20/04/27-50		Sweeping	$198.43
		20/05/01-05		Sweeping	$198.43
Total 070931					**$1,190.58**
EFT000000013097	2020-03-30		LEONARD, ELIZABETH		
		20/03 MAINTENANCE		20/03 Maintenance	$142.50
Total EFT000000013097					**$142.50**
EFT000000013099	2020-03-27		BOULTON SEPTIC/LARMON'S		
		31748		Holding Tank Pumped	$244.22
Total EFT000000013099					**$244.22**
EFT000000013115	2020-03-27		EARL ROSEBUSH FUELS		
		0838-112714		414.20L @.679	$308.82
Total EFT000000013115					**$308.82**
EFT000000013117	2020-03-27		THE FRONTENAC NEWS		
		72088		Activity Guide	$8,140.80
Total EFT000000013117					**$8,140.80**
EFT000000013121	2020-03-27		KFLA PUBLIC HEALTH UNIT		
		20/03/24 REFUND		20/03/24 Refund	$80.00
Total EFT000000013121					**$80.00**
EFT000000013128	2020-03-27		FRONTENAC COMMUNITY ARENA		
		1568		Full Forum Non-Member A.P.	$1,047.11
Total EFT000000013128					**$1,047.11**
EFT000000013146	2020-04-03		ASSELSTINE HARDWARE		
		7079		Cable Ties	$17.29
Total EFT000000013146					**$17.29**
EFT000000013159	2020-04-03		D2 WIRELESS - TELUS AUTHORIZED DEALER		
		BUSKIIN7274		Samsung Galazy A5. A.P.	$30.53
		BUSKIIN7332		Galaxy A50 Case	$66.08

Total EFT000000013159				**$96.61**
EFT000000013161	2020-04-03	EARL ROSEBUSH FUELS		
		1361-114244	382.3L @ .569	$242.26
Total EFT000000013161				**$242.26**
EFT000000013187	2020-04-03	TROUSDALE'S HOME HARDWARE		
		101910	Light Bulbs	$17.29
Total EFT000000013187				**$17.29**
EFT000000013213	2020-04-20	D.MARTIN WELDING & FABRICATING		
		9670	Garbage Can Lid	$224.63
		9670	Garbage Can Lid	$224.62
		9670	Garbage Can Lid	$224.62
		9670	Garbage Can Lid	$224.62
		9670	Garbage Can Lid	$224.62
		9670	Garbage Can Lid	$224.62
		9670	Garbage Can Lid	$224.62
		9670	Garbage Can Lid	$224.63
		9670	Garbage Can Lid	$224.63
		9670	Garbage Can Lid	$224.63
Total EFT000000013213				**$2,246.24**
EFT000000013215	2020-04-20	EARL ROSEBUSH FUELS		
		0838-115720	478.50L @.564	$313.82
		0838-106878	324.00L @.760	$268.28
		0838-109399	495.00L @.7749	$417.38
		1361-109415	106.60L @.778	$90.23
Total EFT000000013215				**$1,089.71**
EFT000000013226	2020-04-20	LONDRY ALARMS		
		202345	20/04 Monitoring + Rental	$28.49
		202345	20/04 Monitoring + Rental	$28.49
Total EFT000000013226				**$56.98**
EFT000000013232	2020-04-20	SIMMONS PLUMBING & PUMP SERV.		
		6092	Urinal Repairs	$599.87
Total EFT000000013232				**$599.87**
EFT000000013237	2020-04-20	TROUSDALE'S HOME HARDWARE		
		604688	Siding + Trim + Wrap + Strap	$2,975.22
Total EFT000000013237				**$2,975.22**
EFT000000013238	2020-04-20	UBCON CONSTRUCTION LTD		
		19-017-5	Progress Draw #5	$32,104.77
Total EFT000000013238				**$32,104.77**
EFT000000013245	2020-04-20	XCG CONSULTANTS LTD.		
		56220	Drinking Water Sampling	$101.76
		56220	Drinking Water Sampling	$101.76
		56220	Drinking Water Sampling	$101.76
		56220	Drinking Water Sampling	$101.76
		56329	Drinking Water Sampling	$101.76
		56329	Drinking Water Sampling	$101.76
		56329	Drinking Water Sampling	$101.76
		56329	Drinking Water Sampling	$101.76
Total EFT000000013245				**$814.08**
EFT000000013264	2020-05-01	EARL ROSEBUSH FUELS		
		0838-117865	350.40L @.510	$210.55
Total EFT000000013264				**$210.55**
EFT000000013265	2020-05-01	GILMORE REPRODUCTIONS		
		299078	Boat Launch Signs	$1,111.30
Total EFT000000013265				**$1,111.30**
EFT000000013274	2020-05-01	NORTHWAY HARDWARE		
		23701	Canadian Flag	$36.61
		23701	Canadian Flag	$36.62
Total EFT000000013274				**$73.23**
EFT000000013276	2020-05-01	PINCHIN LTD.		
		1499565	Retrieval of Radon Detectors	$6,665.28
Total EFT000000013276				**$6,665.28**
EFT000000013279	2020-05-01	SLEETH, SARAH		
		20/03/27-08	Cleaning	$420.00
Total EFT000000013279				**$420.00**
EFT000000013294	2020-04-30	LEONARD, ELIZABETH		
		20/04 MAINTENANCE	20/04 Maintenance	$142.50
Total EFT000000013294				**$142.50**
EFT000000013336	2020-05-15	LONDRY ALARMS		
		202671	20/05 Monitoring + Rental	$28.49
		202671	20/05 Monitoring + Rental	$28.49
Total EFT000000013336				**$56.98**
EFT000000013342	2020-05-15	R&D NELSON GENERAL MAINTENANCE		
		20/04-LIB	20/03+20/04 General Maint.	$305.28
		20/04-LIB	20/03+20/04 General Maint.	$66.59
		20/04-G,B.P	20/03+20/04 General Maint.	$195.38
		20/04-G,B.P	20/03+20/04 General Maint.	$139.31
Total EFT000000013342				**$706.56**
EFT000000013378	2020-05-29	EARL ROSEBUSH FUELS		
		1361-122009	418.90L @.421	$213.78
Total EFT000000013378				**$213.78**
EFT000000013393	2020-05-29	LEONARD, ELIZABETH		
		20/05 MAINTENANCE	20/05 Maintenance	$142.50
Total EFT000000013393				**$142.50**
EFT000000013404	2020-05-29	SIMMONS PLUMBING & PUMP SERV.		
		6118	Service UV Light	$480.82
Total EFT000000013404				**$480.82**
Total Rec				**$74,416.86**

8035 NFCA

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013338	2020-05-15		FRONTENAC COMMUNITY ARENA		
		1575		2020 Grants	$75,091.00
Total EFT000000013338					**$75,091.00**
Total NFCA					**$75,091.00**

8037 Her Cmte

Cheque	Date	Inv #	Vendor	Description	Amount
070883	2020-04-03		SOTO GORDON, STEPHANIE		
		20/03/05-HERITAGE		20/03/05-Heritage	$33.12
		20/03/05-HERITAGE		20/03/05-Heritage	$11.99
Total 070883					**$45.11**
070886	2020-04-03		BRADLEY BARBEAU		
		20/03/05 - HERITAGE		20/03/05 - Heritage	$33.12
		20/03/05 - HERITAGE		20/03/05 - Heritage	$3.07
Total 070886					**$36.19**
070888	2020-04-03		MILLAR, MARK		
		20/03/05 HERITAGE		20/03/05 Heritage	$33.12
		20/03/05 HERITAGE		20/03/05 Heritage	$1.59
Total 070888					**$34.71**
EFT000000013164	2020-04-03		GEMMELL, MICHAEL		
		20/03/05-HERITAGE		20/03/05-Heritage	$33.12
		20/03/05-HERITAGE		20/03/05-Heritage	$24.36
Total EFT000000013164					**$57.48**
EFT000000013171	2020-04-03		KENNY, WILMA		
		20/03/05-HERITAGE		20/03/05-Heritage	$33.12
Total EFT000000013171					**$33.12**
Total Her Cmte					**$206.61**

8210 VCA

Cheque	Date	Inv #	Vendor	Description	Amount
070870	2020-03-27		VERONA COMPUTER STORE		
		1728		Sign Troubleshooting	$172.99
Total 070870					**$172.99**
070933	2020-05-29		VERONA FOODLAND		
		1479-VCA		Produce Basket	$22.38
		9833-VCA		Produce Basket	$25.93
Total 070933					**$48.31**
EFT000000013110	2020-03-27		COLEMAN, DONALD		
		2020002		20/03/11 Directors Refreshment	$23.23
Total EFT000000013110					**$23.23**
EFT000000013301	2020-05-15		BATES, LINDA		
		2020004		Gloves + Wipes	$116.41
Total EFT000000013301					**$116.41**
EFT000000013373	2020-05-29		CONWAY, WAYNE		
		2020005		100 Facemasks	$122.11
Total EFT000000013373					**$122.11**
Total VCA					**$483.05**

8220 VMC

Cheque	Date	Inv #	Vendor	Description	Amount
070919	2020-05-15		STRYKER CA LP		
		30782292		AED + Battery	$2,961.98
		30782292		AED + Battery	-$2,961.98
Total 070919					**$0.00**
Total VMC					**$0.00**

8245 BCHC

Cheque	Date	Inv #	Vendor	Description	Amount
070893	2020-04-20		TYENDINAGA PROPANE		
		293531		661.6L @.5290	$356.15
Total 070893					**$356.15**
070932	2020-05-29		TYENDINAGA PROPANE		
		299406		301.30L @.5290	$162.19
		300578		Tank Rental	$66.14
Total 070932					**$228.33**
EFT000000013328	2020-05-15		HAYES, CELINE		
		20/04/27-PATIO DOOR		Final Payment of Patio Door	$161.44
Total EFT000000013328					**$161.44**
Total BCHC					**$745.92**

8405 Ver&Dis Hist

Cheque	Date	Inv #	Vendor	Description	Amount
070900	2020-05-01		THE ONTARIO HISTORICAL SOCIETY		
		2020 PORT. HERITAGE		2020 Membership	$102.00
Total 070900					**$102.00**
Total Ver&Dis Hist					**$102.00**

Total Rec **$151,045.44**

90 Plan

9000 Plan

Cheque	Date	Inv #	Vendor	Description	Amount
070879	2020-04-03		IBI GROUP		
		10056481		20/02 Planning Services	$10,316.78
Total 070879					**$10,316.78**
070896	2020-04-20		WILLISON, ELISE		
		2020 TRAVEL		Travel Expenses	$1,152.42
Total 070896					**$1,152.42**
070915	2020-05-15		DEAN, FRED		
		20/04/23		Webinar- Council C.W.	$228.96
		20/04/27		Webinar- Council A.G.	$228.96
Total 070915					**$457.92**
070922	2020-05-15		ZOOM VIDEO COMMUNICATIONS INC		
		INV18376781		2X Standard + 2X Webinar	$394.43
Total 070922					**$394.43**
EFT000000013118	2020-03-27		INDEPENDENT TELEPHONE SERVICES		
		44866		Telephone Programming	$84.88
Total EFT000000013118					**$84.88**
EFT000000013139	2020-03-27		TROUSDALE'S FOODLAND		
		1988		Food- Growth Management Study	$47.33
Total EFT000000013139					**$47.33**
EFT000000013191	2020-04-03		WATSON & ASSOCIATES ECONOMISTS LTD		
		26170		Growth Analysis	$4,834.29
Total EFT000000013191					**$4,834.29**
EFT000000013219	2020-04-20		GRAND & TOY LIMITED		
		P822233		File Folders	$58.00
Total EFT000000013219					**$58.00**
EFT000000013227	2020-04-20		NOLAN, MIKE		
		20/03 COA		20/03 COA	$50.00
		20/03 COA		20/03 COA	$106.49
Total EFT000000013227					**$156.49**
EFT000000013257	2020-05-01		CDW CANADA INC		
		XNX0289		2X Keyboard + Mouse C.W.+ A.G.	$36.45
		XPL2617		4X Monitors C.W. + A.G.	$1,021.72
		XPF1984		2X Laptops A.G. + C.W.	$3,464.11
Total EFT000000013257					**$4,522.28**
EFT000000013263	2020-05-01		D2 WIRELESS - TELUS AUTHORIZED DEALER		
		BUSKIIN7421		2X Cell phones+Cases C.W.+ A.G	$142.36
Total EFT000000013263					**$142.36**
EFT000000013308	2020-05-15		CDW CANADA INC		
		XQH9799		3X Backpacks	$259.24
Total EFT000000013308					**$259.24**
EFT000000013329	2020-05-15		IBI GROUP		
		10057764		20/03 Planning Services	$11,657.88
Total EFT000000013329					**$11,657.88**
EFT000000013330	2020-05-15		INDEPENDENT TELEPHONE SERVICES		
		44994		Ext 2350+2221 A.G. + C.W.	$86.50
Total EFT000000013330					**$86.50**
EFT000000013360	2020-05-15		WATSON & ASSOCIATES ECONOMISTS LTD		
		26229		Growth Analysis	$2,196.69
Total EFT000000013360					**$2,196.69**
Total Plan					**$36,367.49**

9800 Dev Serv

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013145	2020-04-03		AINLEY GRAHAM & ASSOCIATES LTD		
		IN0019415		Peer Review-Valleyview Estates	$1,376.74
Total EFT000000013145					**$1,376.74**
EFT000000013158	2020-04-03		CUNNINGHAM SWAN CARTY		
		162706		Legal Advice	$780.88
		162708		Legal Advice	$101.76
Total EFT000000013158					**$882.64**
Total Dev Serv					**$2,259.38**
Total Plan					**$38,626.87**

99

9999

Cheque	Date	Inv #	Vendor	Description	Amount
EFT000000013132	2020-03-27		REALTAX INC		
		75635		First Notices	$468.95
		75636		First Notices	$423.75
		75637		First Notices	$615.85
Total EFT000000013132					**$1,508.55**
EFT000000013133	2020-03-27		ROSEN ENERGY GROUP		
		642508		F 2856.1L CLR @.9017	$2,620.68
		642507		F 2100.2L GAS @.8872	$1,896.09
		642515		B 496.5L MKD @.7687	$388.39
		642514		B 1795.1L CLR @.9017	$1,647.13
		642513		B 756.1L GAS @.8872	$682.62
		642510		P 1989.8L CLR @.9017	$1,825.78
		642511		P 618.4L MKD @.7687	$483.73
		642509		F 794.4L MKD @.7687	$621.42
		642761		B 210.0L GAS @.7492	$160.09
		642675		F 135.4L MKD @.7041	$97.01
		642674		F 548.9L CLR @.8387	$468.46

		642673	F 1868.6L GAS @.7492	$1,424.59
		642659	SUN 1851.6L CLR @.7717	$1,454.03
Total EFT000000013133				**$13,770.02**
EFT000000013167	2020-04-03		HUGHSON FENCING & GUIDERAIL	
		5509	Extruder Terminal System	$8,418.50
Total EFT000000013167				**$8,418.50**
EFT000000013228	2020-04-20		ROSEN ENERGY GROUP	
		642912	F 1305.4L GAS @.6132	$814.56
		642914	F 1120.5L MKD @.6047	$689.49
		642913	F 2346.1L CLR @.7367	$1,758.79
		642916	P 1841.2L MKD @.6497	$1,217.28
		642915	P 3338.8L CLR @.7827	$2,659.28
		642918	B 593.1L GAS @.6132	$370.09
		642920	B 396.4L MKD @.6047	$243.92
		642919	B 98.6L CLR @.7367	$73.92
		643222	F 880.5L CLR @.7827	$701.30
		643223	F 292.1L MKD @.6497	$193.12
		643230	F 2336.5L GAS @.5722	$1,360.47
		643293	SUN 4000.7L CLR @.6910	$3,140.86
Total EFT000000013228				**$13,223.08**
EFT000000013345	2020-05-15		ROSEN ENERGY GROUP	
		643489	F 1775.9L GAS @.5760	$1,160.74
		643500	SUN 1181.7L CLR @.68	$914.51
		643540	SUN 800.7L CLR @.6740	$614.76
		643558	F 1100.7L GAS @.5870	$731.76
		643560	F 907.4L MKD @.5404	$573.32
		643559	F 998.9L CLR @.6734	$766.32
		643564	B 641.7L GAS @.5870	$426.60
		643566	B 1421.5L MKD @.5404	$898.14
		643565	B 2500.5L CLR @.6734	$1,918.31
		643841	SUN 138.4L CLR @.57	$91.61
		643842	F 1500.3L GAS @.5720	$974.49
		643843	F 887.4L CLR @.5700	$587.42
		643844	F 545.7L MKD @.46	$300.13
		643845	P 3245.6L CLR @.57	$2,148.42
		643846	P 1332.4L MKD @.46	$732.83
Total EFT000000013345				**$12,839.36**
EFT000000013400	2020-05-29		ROSEN ENERGY GROUP	
		644093	F 1404.7L CLR @.5650	$922.70
		644095	F 1750.6L MKD @.4320	$912.97
		644096	P 1402.1L CLR @.5650	$921.00
		644097	P 528.0L @.4320	$275.36
		644094	F 1592.3L GAS @.66	$1,176.84
Total EFT000000013400				**$4,208.87**
Total				**$53,968.38**
Total				**$53,968.38**
Total				**$4,057,679.63**

Questions for Council from the Public regarding COVID-19 and Township Services

JUNE 2, 2020

Do you have a pandemic related question for Council?

1. Submitted at Sunday May 19TH 2020 10:23 AM

Any news on the public meetings? With construction opening up in the next day or so, is their potential that the meetings will start so people who are severing a lot for building can get started too?

Township Response:

Township staff are in the process of setting up virtual public meetings to be able to move consent and minor variance applications ahead in the coming weeks. We will be advising applicants once we have a firm date for our first virtual Committee of Adjustment meeting.

Council passed a by-law delegating authority to staff to make decisions on consent applications that meet all planning policies and do not have any public objection. This decision was made to assist with moving ahead straightforward consent applications without the need to have a public hearing at Committee of Adjustment. If there are no objections from the public on your severance application, you may be able to benefit from this recent decision of Council.

Planning staff will be in contact with applicants in the next week to 10 days to advise of the status of your application and timelines for proceeding towards a decision.

2. Submitted at May 24th 2020 11:28 AM

Is the Point Beach open to swim? I see people gathering with the warm weather and the sign at the Point is not explicit. In fact there is black tape over some of it that does not look official. I don't see an update in some time and with restrictions changing this is unclear to me.

Township Response:
Thank you for reaching out to us. The Beach is still closed as per the Provincial Emergency Declaration order. The signage is being changed to make this clear to the Public.

KFLA Public Health confirmed that under orders 104/20 and 51/20, ALL recreation water facilities, whether indoor or outdoor remain closed.

3. Submitted at May 26th, 2020 1:53 PM

Hi there, I live in Kingston. I rented a cottage in South Frontenac County for a week in July. Is this still permitted? Thanks

Township Response:

As you are aware, most of the restrictions are province wide and not specific to one municipality. The following excerpt is from the Province's webpage regarding short-term rentals:

Questions for Council from the Public regarding COVID-19 and Township Services

JUNE 2, 2020

Short term rentals

1. Every person who provides short term rentals in rental accommodations shall ensure that any rentals booked after April 4, 2020 are only provided to individuals who are in need of housing during the emergency period.

2. Subsection (1) does not apply in respect of hotels, motels and student residences.

This information can be found at the end of the essential services regulation O. Reg 82/20 here: https://www.ontario.ca/laws/regulation/200082

4. Submitted at May 27th, 2020 7:56 AM

Now that so many more stores are open, are yard sales permitted? We'd encourage distancing and have a jar for cash and live in an area where it wouldn't be really busy anyways, but we also don't want to get penalized if it's not permitted yet. Thank you!

Township Response:

Although a bit more challenging given social distancing requirements, KFL&A Public Health provided us with an interpretation of the current permitted business rules that allows Garage/Yard Sales to go ahead.

Essentially, if residents want to hold garage/yard sales, they must ensure that persons in the “place of business” (read: customers in their yard/garage) can maintain physical distancing of at least two metres from each other at all times through one or more of the following:

1. Using alternative methods of sale such as curb side pick-up or delivery

2. Operating by appointment

3. Limiting the number of people who may be in the place of business at any one time

Garage sale hosts may also want to consider having hand sanitizer available to visitors. There is added risk associated with payment since garage sales don’t typically accept ‘tap’ transactions. So any resident/host would have to appreciate the risk of exchanging money.

So, garage sales are technically allowed but there are some risks (physical distancing, payment, hand hygiene) you have to consider and should address.

5. Submitted on May 27th, 2020 8:56 AM

What happens if your neighbor arrived from the US and is not following her quarantine plan?

Township Response:

There is an enforcement provision for these types of issues. KFL&A Public Health are empowered to regulate, inspect and act upon non-compliance issues related to the COVID-19 Pandemic. There is a “Submit a COVID-19 Complaint form” option at the bottom of the page on the website link https://www.kflaph.ca/en/healthy-living/covid-19-enforcement.aspx

Questions for Council from the Public regarding COVID-19 and Township Services

JUNE 2, 2020

6. Submitted on May 28th, 2020 12:05 PM

I read the notice on the website dated March 30th for outdoor amenities.

Are all these restrictions still in place? It says until further notice.....I know some places have lifted some restrictions and was just looking for clarity from South Frontenac.

The obvious rules for physical distancing, I know are definitely in place. However, what about being at a beach for a swim? Are The Point, Davidson Beach and such closed for swimming?

I am a resident of South Frontenac, and understand why we need restrictions. I am in NO way opposing the rules, I just want to know what we are allowed to do.

Township Response:

All beaches are still closed as per the Provincial Emergency Declaration orders 104/20 and 51/20 which mandate that ALL recreational water facilities, whether indoor or outdoor remain closed at this time. Local signage is being updated to make this clear to the Public.

The province has recently relaxed restrictions on specific outdoor amenities including off-leash dog parks, tennis courts and public washrooms. Boat Launches and marinas are also able to reopen for recreational purposes; the Township has kept its launches open since the beginning due to the significant number of residents that must access their residential properties via watercraft. Use of launches for this purpose was exempted from the initial restrictions.

The Township's most recent updates and public service announcements regarding the COVID-19 pandemic and its impact on our services and facilities can be found here: https://www.southfrontenac.net/en/covid-19-coronavirus-information.aspx

TOWNSHIP OF SOUTH FRONTENAC
BY-LAW 2020-30

A BY-LAW TO CONFIRM GENERALLY PREVIOUS ACTIONS OF THE COUNCIL OF THE CORPORATION OF THE TOWNSHIP OF SOUTH FRONTENAC.

THEREFORE THE CORPORATION OF THE TOWNSHIP OF SOUTH FRONTENAC, BY ITS COUNCIL, HEREBY ENACTS AS FOLLOWS:

1. The actions of the Council of the Corporation of the Township of South Frontenac at its Council Meeting of June 2, 2020 be confirmed.

2. Execution by the Mayor and the Clerk of all Deeds, Instruments and other Documents necessary to give effect to any such Resolution, Motion or other action and the affixing of the Corporate Seal to any such Deed, Instruments or other Documents is hereby authorized and confirmed.

3. This By-law shall come into force and take effect on the date of its passage.

Dated at the Township of South Frontenac this 2 day of June, 2020.

Read a first and second time this 2 day of June, 2020.

Read a third time and finally passed this 2 day of June, 2020.

THE CORPORATION OF THE
TOWNSHIP OF SOUTH FRONTENAC

_____
Ron Vandewal, Mayor

_____
Angela Maddocks, Clerk